KEY

Soft Landscaping

- Existing Trees/Vegetation Retained
- Proposed Tree Planting
- Proposed Single Species Hedge Planting
- Proposed Mixed Native Hedge Planting
- Proposed Shrub Planting
- Proposed Amenity Grass
- Proposed Sports Pitch Grass
- Proposed Wetland Grassland
  N7 Wetland Meadow Mixture at 5 g per m sq
- Proposed Grassland
  N9 Hedgerow Meadow Mixture at 5 g per m sq
- Proposed Suds Basin with Pond Edge and Aquatic Marginal Planting
- Proposed Rabbit Fencing
- Proposed Deer Fencing
- Proposed 2.5m High Chain Link Fencing with Lockable Vehicular and Pedestrian Gate at entrance

Hard Landscaping

- Proposed Permeable Block Paving
- Proposed Golpa Grass Cellular Confinement System
- Proposed Paving Slabs
- MUGA Rubber Surfacing

N

0 50m

TREE PLANTING

Code	Species	Form	Girth cm	Height cm	Root condition	Quantity
AC	Acer campestre	EHS	14-16	425-600	65/85 L	9
BP	Betula pendula	EHS	14-16	425-600	65/85 L	6

SHRUB PLANTING

Code	Species	Height/ spread cm	Pot size (Litres)	Habit	Min no. of breaks	No. / m2	Quantity
CMWF	Cornus sanguinea 'Midwinter Fire'	40-60	3L	Branched	3	4	28
HR	Hebe rakaiensis	20-30	3L	Bushy	5	3	15
HH	Hypericum 'Hidcote'	30-40	3L	Bushy	5	2	13
POL	Prunus 'Otto Luyken'	30-40	3L	Bushy	3	2	30
RK	Rosa 'Kent'	30-40	3L	Bushy	4	3	18
SS	Senecio 'Sunshine'	30-40	3L	Bushy	4	2	15

HEDGE PLANTING

Code	Species	Height/ spread cm	Pot size (Litres)	Habit	Min no. of breaks	No. / m2	Quantity
FSH	Fagus sylvatica (hedge)	60-80	2L	Feathered	4	5/lin m	448

NATIVE HEDGE TRANSPLANTS MIX A @ 7 per linear metre in triple staggered row

Code	Species	Root Condition	Age + Times Transpl	Height cm	Quantity
AG	Alnus glutinosa (15%)	Bagged	1+1	60-90	20
CM	Crataegus monogyna (20%)	Bagged	1+1	60-90	28
CA	Corylus avellana (20%)	Bagged	1+1	60-90	28
PA	Prunus avium (10%)	Bagged	1+1	60-90	14
PS	Prunus spinosa (20%)	Bagged	1+1	60-90	28
RC	Rosa canina (5%)	Bagged	1+1	60-90	6
SN	Sambucus nigra (5%)	Bagged	1+1	60-90	6
VO	Viburnum opulus (5%)	Bagged	1+1	60-90	6

NATIVE HEDGE TRANSPLANTS MIX B @ 7 per linear metre in triple staggered row

Code	Species	Root Condition	Age + Times Transpl	Height cm	Quantity
AC	Acer campestre (20%)	Bagged	1+1	60-90	112
CM	Crataegus monogyna (30%)	Bagged	1+1	60-90	168
CA	Corylus avellana (10%)	Bagged	1+1	60-90	56
CS	Cornus sanguineum (10%)	Bagged	1+1	40-60	56
IA	Ilex aquifolium (10%)	9cm pot	-	30-40	56
PS	Prunus spinosa (10%)	Bagged	1+1	60-90	56
RC	Rosa canina (10%)	Bagged	1+1	60-90	56

POND EDGE (planted randomly – up to 0.5m above settled water level)

Species	Root condition	No. / m2	Total
Caltha palustris	P9/0.5lt	3	6
Carex acutiformis	P9/0.5lt	3	6
Epilobium hirsutum	P9/0.5lt	3	6
Filipendula ulmaria	P9/0.5lt	3	6
Lythrum salicaria	P9/0.5lt	3	6
Mentha aquatica	P9/0.5lt	3	6
Rumex hydrolapathum	P9/0.5lt	3	6

AQUATIC MARGINALS (planted randomly - to 0.3m below settled water level)

Species	Root condition	No. / m2	Total
Alisma plantago-aquatica	P9/0.5lt	2	5
Butomus umbellatus	P9/0.5lt	2	5
Iris pseudacorus	P9/0.5lt	2	5
Ranunculus lingua	P9/0.5lt	2	5
Scirpus lacustris	P9/0.5lt	2	5
Typha augustifolia	P9/0.5lt	2	5

Revision	Description	Date
-	First issue	29/1/21
A	Second issue	15/3/21
B	Third issue	13/4/21
C	Fourth issue	27/9/21

LANDARB SOLUTIONS

Project:
Adderbury Sports and Community Pavilion

Description:
Soft Landscape Proposals

Status:
For Planning

Scale:	Drawn I Checked	Date:
1:500 @A1	**DP MP**	**27/09/2021**
Job Number:	Drawing Number:	Revision:
LAS 205	**01**	**C**