

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL GENERAL ARRANGEMENT AND PROJECT DETAILS DRAWINGS.

2. UNLESS NOTED OTHERWISE, ALL VERTICAL DIMENSIONS ARE MEASURED FROM DPC/FFL

2100 INDICATES THE VERTICAL DISTANCE ABOVE DPC/FFL

3. EAVES DIMENSION SHOWN MEASURED FROM BRICK/BLOCK FACE TO EXTERNAL FACE OF FASCIA

4. WINDOW LEGEND, REFERENCES AND ABBREVIATIONS USED;

W WINDOW/EXTERNAL DOOR

SG DENOTES SAFETY GLASS # DENOTES EMERGENCY ESCAPE WINDOW TO COMPLY WITH AD PART B1

EMJ EXTERNAL MOVEMENT JOINT FFL FINISHED FLOOR LEVEL FCL FINISHED CEILING LEVEL RWP RAIN WATER PIPE

(OB) DENOTES OBSCURE GLASS

5. MINIMUM DISTANCE BETWEEN EXTRACTS AND OPENINGS TO BE 300MM. SIZES OF EXTRACTS AND FLUES TO BE AS MANUFACTURER'S RECOMMENDATIONS. COLOURS TO MATCH SURROUNDING MATERIAL AS APPROPRIATE.


6. FOR WALL, ROOF, WINDOW AND RAINWATER GOODS FINISHES REFER TO MATERIALS SCHEDULE.

7. GROUND LEVEL IS SHOWN APPROXIMATE ONLY. FOR PRECISE LEVELS REFER TO THE CIVIL ENGINEER'S DRAWINGS.

8. FOR ALL MOVEMENT JOINT LOCATIONS REFER TO STRUCTURAL ENGINEERS DRAWINGS - COLOUR OF MOVEMENT JOINT SEALANT TO MATCH FACING BRICK.


9. ELEVATIONS SHOWN ARE FOR A TYPICAL DETACHED UNIT "AS DRAWN". REFER TO THE RELEVANT BLOCK PLAN DRAWINGS FOR TERRACE GARAGES.

REFER TO DRAWING HT4A-09-01 FOR SCHEDULES




TYPICAL BRICK CORBEL DETAIL (SCALE 1:20)

REAR ELEVATION



FRONT ELEVATION SIDE ELEVATION



SIDE ELEVATION

PHASE 9E PLOTS - (OPP) 762,763 DORCHESTER Trower Davies

Architectural Consultants UPPER HEYFORD, PHASE 9 BICESTER Drawing Title: HOUSE TYPE 4A **ELEVATIONS [BRICK]** Drawn by: 1:50 @ A1 MAY 22 MJR Project Number: Drawing Number: Revision: 727 HT4A-09-06 PRELIMINARY

Statutory approvals to be received prior to commencement of works. Building control submission to be deposited prior to any works. Check / trace positions of existing services / drainage prior to new works.

Ensure no Easements / rights of way exist on site prior to construction.

Do NOT scale from this drawing. Check dimensions on site against site survey prior to any new works. Report and resolve any discrepencies

Relevant Party Wall notices to be served and agreed before new works.

CDM Co-ordinator to be appointed with Health & Safety file in place prior

prior to any new building works.