



Symbol	Label	Quantity	Category Number	Description	Lumens Per Lamp	Wattage
A1	2	DSK1.2LA224 FW on 8m Column	D-Series 1 Luminaire	24252	208	
AW	14	DSK1.2LA164 FW on Wall Bracket at 8m AFEL	D-Series 1 Luminaire	24252	208	
B1	4	DSK1.2LA164 FW on 8m Column	D-Series 1 Luminaire	17044	131	
BW	6	DSK1.2LA164 FW on Wall Bracket at 8m AFEL	D-Series 1 Luminaire	17044	131	
C1	14	DSK1.2LA164 AY on 8m Column	D-Series 1 Luminaire	16556	131	
C1BL	14	DSK1.2LA164 AY BL S on 8m Column	D-Series 1 Luminaire with Back Light Shield	13416	131	
E	26	DWL 1 LAD14 BKW007 at 2.7m AFEL	Denver ID Wall	897	6.5	
XA	6	EXISTING DSK1.2LA164 FW on 8m Column	D-Series 1 Luminaire	17044	131	

Description	Symbol	Avg	Min	Max	MixKw
Access Road	+	25 km	7 km	0.28	
Spit	+	1 km	0 km	0.90	
Unit 5 Parking	+	22 km	9 km	0.41	
Unit 5 Pathway	+	10 km	2 km	0.20	
Unit 6	+	14 km	7 km	0.50	
Unit 7 Car Park	+	22 km	14 km	0.64	
Unit 7 Parking	+	23 km	10 km	0.43	
Unit 7 Pathway	+	11 km	5 km	0.45	
Unit 8 Parking	+	23 km	14 km	0.61	
Unit 8 Pathway	+	23 km	11 km	0.48	
Unit 9 Pathway	+	11 km	5 km	0.45	
Unit 9 Parking	+	20 km	10 km	0.48	
Unit 9 Pathway	+	20 km	10 km	0.48	
Unit 10 Parking	+	21 km	10 km	0.48	
Unit 10 Pathway	+	20 km	10 km	0.48	
Unit 10 Parking	+	20 km	10 km	0.48	
Unit 10 Pathway	+	20 km	10 km	0.48	
Unit 11 Parking	+	20 km	10 km	0.48	
Unit 11 Pathway	+	20 km	10 km	0.48	
Unit 12 Parking	+	20 km	10 km	0.48	
Unit 12 Pathway	+	20 km	10 km	0.48	
Unit 13 Parking	+	20 km	10 km	0.48	
Unit 13 Pathway	+	20 km	10 km	0.48	
Unit 14 Parking	+	20 km	10 km	0.48	
Unit 14 Pathway	+	20 km	10 km	0.48	



NOTES:
 WHERE SWA CABLE CROSSES A CARRIAGEWAY/VEHICLE ENTRANCE, IT IS CONTAINED:
 1. WITHIN A 100mm HIGH IMPACT UPVC DUCT AT A DEPTH OF NOT LESS THAN 750mm
 2. NO GREATER THAN 1000mm



10m SCALE 1:750

NO.	DESCRIPTION OF HAZARD	CONTROL MEASURES	ACTION BY
1	UNDEVELOPED SERVICES AND SERVICES IDENTIFIED IN PREVIOUS LOCATIONS	IDENTIFICATION OF EXISTING UNDERGROUND SERVICES DRAWINGS AND CAT (JOINING OF STRANDS)	CONTRACTOR
		CAREFUL EXCAVATION USING SLOT TRENCHES AND CAT (JOINING OF STRANDS)	

- NOTES**
- THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL OTHER ENGINEERING SERVICES CONSULTANCY LIMITED DRAWINGS
 - THE EXTERNAL LIGHTING SHALL BE DESIGNED TO ENSURE THAT REQUIRED LIGHTING LEVELS ARE ACHIEVED WHILST MINIMISING GLARE AND LIGHT SPILLAGE TO THE SURROUNDING AREAS AND TO ENSURE THERE IS NO DIRECT CONTRIBUTION TO UPWARD LIGHT POLLUTION.
 - THE EXTERNAL LIGHTING SCHEME SHALL BE PROVIDED IN ACCORDANCE WITH THE LOCAL PLANNING AUTHORITIES REQUIREMENTS/RESTRICTIONS.
 - WHERE COLUMNS ARE POSITIONED NEAR TO NEIGHBOURING PROPERTIES, OR LOCATED ON THE PERIMETER OF THE SITE, THEY SHALL BE COMPLETE WITH SUITABLE BACK-SHIELDS TO PREVENT LIGHT SPILL.
 - ALL COLUMNS SHALL HAVE A FLEXIBLE DUCT PASSING INTO THE BASE, THROUGH THE CONCRETE, TO ENSURE THAT FUTURE REWIRING OF THE CIRCUITS IS POSSIBLE.
 - WHERE LUMINAIRES ARE FIXED DIRECTLY TO THE EXTERNAL BUILDING FABRIC, THE LUMINAIRES SHALL BE THE SAME RAL COLOUR AS THE CLADDING PANELS. ALL LUMINAIRE FIXING BOLTS ETC. SHALL BE THE SAME COLOUR AS THE LUMINAIRE.
 - GENERALLY, THE COLUMNS SHALL BE GALVANISED STEEL CONSTRUCTION. THE ELECTRICAL CONTRACTOR SHALL Liaise WITH THE ARCHITECT TO ASCERTAIN THE RAL COLOUR OF THE COLUMNS. THE COLUMN HEADS SHALL MATCH THE RAL COLOUR OF THE COLUMN.
 - WHERE SERVICES NEED TO BE INSTALLED WITHIN DUCTS / TRENCHES, THE ELECTRICAL CONTRACTOR SHALL SUPPLY THE MAIN CONTRACTOR WITH DETAILS OF REQUIRED DUCT ROUTES AND DRAW FIT LOCATIONS.
 - DURING INSTALLATION OF THE EXTERNAL LIGHTING A DRAW WIRE SHALL BE PULLED THROUGH WITH THE CABLING TO PROVIDE A MEANS OF INSTALLING FUTURE SERVICES

P1 23.05.22 Issued for planning CP
 Rev. Date Details Initials
 Engineering Services Consultancy Ltd
 Griffin House
 19 Ludgate Hill
 Birmingham
 B3 1DW
 T: 0121 214 8998
 F: 0121 214 9999
 W: www.oscuk.com
 Client
ALBION LAND

Project
Catalyst Phase 2.1

Drawing Title
External Lighting Layout

Purpose
PLANNING

Drawn **DM** Engineer **AW** Approved **CP**
 Project No. **1760** Date **May 2022** Scale @ A0 **1:750**
 Drawing No. **1760-ESC-00-ZZ-DR-E-2104** Revision **P1**

THIS DRAWING IS FOR INFORMATION ONLY TO DEMONSTRATE DESIGN INTENT AND REPRESENTS THE AGREED SERVICING STRATEGY AND MINIMUM STANDARDS TO BE ACHIEVED. WHERE ADDITIONAL DETAILS HAVE BEEN SHOWN, THIS HAS BEEN PROVIDED IN ORDER TO CONVEY GREATER UNDERSTANDING OF THE CONCEPTUAL REQUIREMENTS AND SHALL NOT BE TAKEN AS DETAILED DESIGN.

IT HAS NOT BEEN PRODUCED TO ACCURATE DESIGN CALCULATIONS AND SHALL NOT BE USED FOR INSTALLATION PURPOSES.

THE CONTRACTOR WILL BE RESPONSIBLE FOR THE DESIGN OF THE ENGINEERING SERVICES IN ACCORDANCE WITH THE DESIGN AND BUILD CONTRACT. PLANT SIZING IS INDICATIVE AND THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR THE DETAILED DESIGN OF ALL PLANT AND EQUIPMENT.

THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL CONTRACT DOCUMENTS, PROJECT SPECIFICATIONS AND DRAWINGS