

# BREEAM UK NEW CONSTRUCTION

2018 Pre-Assessment

PROJECT:

### **KINGSMERE BICESTER**

PROJECT NUMBER:

P2669

DOCUMENT REF:

P2669-BRE-R04

DATE:

24/08/2023

**REVISION:** 

**Rev 04** 

(	% Score	
(	BREEAM Rating	E
(	Assessment Type	M

**KENT (HQ)** Unit 3 Grove Dairy Farm Business Centre I Bobbing Hill I Bobbing I Sittingbourne I Kent I ME9 8NY

> LONDON One Bridge Wharf I 56 Caledonian Road I London I N1 9UU



## **BREEAM PRE-ASSESSMENT**

The explanation and outline of how to achieve each credit is found below in the following sections:

#### Scope

Please note: the final BREEAM score is confirmed by the BRE, <u>not</u> QuinnRoss Energy. The final score will be based on the quality of information provided by the whole team, <u>not</u> solely QuinnRoss Energy.

Scope of Assessment	
Project type	Multi-residential
Building type	Care home
Is the building designed to be untreated?	Ν
Heating system type	Y
Cooling system type	Ν
Are industrial-sized refrigeration and storage systems specified?	Y
Are building user lifts present?	Y
Are building user escalators or moving walks present?	Ν
Are laboratories present?	Ν
Are there any water demands present other than those assessed in Wat 01?	Y
Does the building have external areas within the boundary of the assessed development?	Y
Are there statutory requirements, or other issues outside of the control of the project, that impact the ability to provide outdoor space?	Ν
Are systems specified that contribute to the unregulated energy load?	Y
Are the post occupancy stage credits targeted in Ene 01?	Ν

#### Credit Distribution



Sub-Section	Available Credits	Targeted Credits
Management (Man)	21	18
Health and Wellbeing (Hea)	19	14
Energy (Ene)	24	16
Transport (Tra)	12	4
Water (Wat)	9	5
Materials (Mat)	14	10
Waste (Wst)	9	8
Land Use and Ecology (LE)	13	8
Pollution (Pol)	12	9
Innovation (Inn)	10	3

BREEAM Rating	% Score
Pass	30%
Good	45%
Very Good	55%
Excellent	70%
Outstanding	85%
Proposed Development	70.6%

Score





### BREEAM NEW BUILD - PRE ASSESSMENT

The explanation and outline of how to achieve each credit is found below in the following sections:

Please note: The client/client's representative will be responsible for sourcing the "consultant" credits. QuinnRoss Energy can help sourcing fees for these if instructed but cannot confirm works and funds. Please note: Red items are mandatory

#### Management (Man)

Man 01: Project brief and design	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements	Typical Responsibility	Stage Due
Stakeholder consultation (project delivery)	1	1	Roles, responsibilities and contributions for each phase of the project delivery have beer clearly defined and inputs have influenced early design options	Stage/options reports	RPS	Stage 4
Stakeholder consultation (third party)	1	1	Third party stakeholders have been consulted and their contributions and outcomes are documented and shown if they have influenced design	Construction programme Consultation plan List of consultees Documented design changes that were influenced by consultation exercise	RPS	Concept stage
Sustainability Champion (design)	1	0	BREEAM AP is appointed to define the BREEAM target for the project	BREEAM AP appointment/ agreed targets	-	-
Sustainability Champion (monitoring progress)	1	0	BREEAM AP is appointed to monitor and oversee BREEAM target through the design	BREEAM AP appointment/ stage reports	-	-

Man 02: Life cycle cost and service life planning	Available Credits	Excellent Rating		Evidence Requirements	Typical Responsibility	Stage Due
Elemental life cycle cost (LCC)	2	2	An elemental LCC analysis is carried out at RIBA stage 2. The LCC indicates future replacement costs and service life, maintenance and operation costs. It must show how it has influenced the design		Consultant	Stage 2
Component level LLC Plan	1	1	A component level LCC plan is developed by the end of RIBA stage 4. It must show how it has influenced the design	LCC analysis	Consultant	Stage 2
Capital cost reporting	1	1	Capital cost for the building in pounds per square metre is reported	Confirmation letter showing £/m²	RPS	Stage 2

Man 03: Responsible construction practices	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements	Typical Responsibility	Stage Due
Timber	0	0	All timber and timber-based products used on the project are to be legally harvested and traded timber	Contract clause/ written confirmation	Contractor	Prior to construction starting
Environmental Management	1	1	Principal contractor operates a certified EMS (ISO14001) Principal contractor implements best practice pollution prevention policies on-site. (PPG6)	Copy of the ISO14001 certificate, ensure contractor is registered with UKAS Signed copy of the PPG6 checklist (QuinnRoss can provide this document for contractors to fill in and sign)	Contractor	Prior to construction starting
Sustainability Champion (construction)	1	0	BREEAM AP is appoint to monitor and oversee BREEAM target through construction and has an active presence on site	BREEAM AP appointment/ stage reports - AP will require at least 5 site visits during construction site	-	-
Considerate construction	2	2	The site achieves a Considerate Constructors Scheme (CCS) score of at least 35 with at least a score of 7 in each of the 5 sections.	Written confirmation contractor is registered with CCS and copy of checklist to confirm score	Contractor	At project completion
			Responsibility is assigned to an individual to monitor, record and report energy, water and transport data resulting from on-site construction processes.	Written confirmation a single person has been assigned for monitoring purposes only		At project completion
			Energy consumption is monitored and records in kWh (and where relevant litres of fuel used)	Amount of energy consumed by site activities in kWh		
			Water consumption is monitored and records in m <sup>3</sup>	Amount of potable water consumed by site activities in m <sup>3</sup>		
Monitoring of construction-site-impacts	2	2	Transport of materials to site is monitored (total distance (km), litres of fuel (I), material	Distance transport vehicles cover to deliver materials to site in km by material delivered	Contractor	
			type)	Litres of fuel consumed by transport vehicles, based on the above		
				Distance transport vehicles cover to remove/dump materials from site in km by material removed		
			Transport of waste from site is monitored (total distance (km), litres of fuel (I))	Litres of fuel consumed by transport vehicles, based on the above		



1

1

1

### Management (Man) Continued

Man 04: Commissioning and handover	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements	Typical Responsibility	Stage Due
				Commissioning schedule, outlining scope of commissioning works including timescales		Prior to construction starting
Commissioning and testing schedule	1	1	A commissioning manager is appointed to monitor and programme commissioning in accordance with the relevant standards.	Project programme accounting for commissioning dates	Contractor	Prior to construction starting
				Schedule must outline conformity with relevant build regs, BSRIA and CIBSE guidelines		At project completion
				Commissioning certificates		At project completion
	1		For complex building services, a specialist commissioning manager is appointed	Commissioning schedule, outlining scope of commissioning works including timescales		Prior to construction starting
Commissioning building services		1		Project programme accounting for commissioning dates	Contractor	Prior to construction starting
				Schedule must outline conformity with relevant build regs, BSRIA and CIBSE guidelines		At project completion
				Commissioning certificates		At project completion
				Thermographic survey results		
Testing and inspecting building fabric	1	1	Perform a thermographic survey of the building and an air permeability test. Rectify any faults found from these tests prior to construction	Air permeability test certificate	Consultant	At project completion
Mandatory - Handover	1	1	A building user guide is developed along with a training schedule prior to handover	Scope of building user guide & facilities management training schedule	Contractor	Prior to construction starting
	_					
Man 05: Aftercare	Available	Excellent	Credit	Evidence	Typical	Stage Due
	Credits	Rating	Requirements	Requirements	Responsibility	Stage Due
			Have a meeting and training session with future tenant. Introduce BUG, aftercare support available and how the building is to be used.	Training programme for initiation meeting	RPS	
			Provide initial aftercare support for at least the first month	Written confirmation from client outlining who is providing this	RPS	

Provide long-term aftercare support for the first 12 months

occupant interviews, review of internal temps and ventilation

Consultant must be independent of the design of the building

occupancy

Collect and monitor energy and water consumption for the first 12 months

Perform commissioning activities for at least the first 12 months analysing plant usage,

A POE consultant is appointed to monitor the building and its use one year after

Aftercare support

Commissioning implementation

Post occupancy evaluation (POE)



Requirements	Responsibility	
Training programme for initiation meeting	RPS	
Written confirmation from client outlining who is providing this	RPS	
Copy of letter of appointment and contract to aftercare support consultant	RPS	
Copy of letter of confirmation from aftercare support consultant their responsibilities	RPS	Prior to construction starting
Copy of letter of appointment and contract to aftercare support consultant	RPS	
Copy of letter of appointment and contract to aftercare support consultant	RPS	
		Training programme for initiation meeting       RPS         Written confirmation from client outlining who is providing this       RPS         Copy of letter of appointment and contract to aftercare support consultant       RPS         Copy of letter of confirmation from aftercare support consultant their responsibilities       RPS         Copy of letter of appointment and contract to aftercare support consultant their RPS       RPS         Copy of letter of appointment and contract to aftercare support consultant       RPS

### Health and Wellbeing (Hea)

Hea 01: Visual comfort	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements
Glare control	1	0	Identify areas vulnerable to glare and design anti-glare systems to mitigate	Glare modelling report
Daylighting	2	0	Daylight modelling is required to demonstrate good practice daylight factors are achieved	Daylight modelling report
View out	1	0	95% of the occupied rooms have a wall with a windows that provided a view out (window >20% of the surrounding wall area)	Marked up plans and elevations
			Internal and external lighting is designed in accordance with the reference standards.	Specification/ M&E proforma confirming design standards
Internal and external lighting levels, zoning and control	1	1	The lighting is zoned and control in the relevant areas. - zones of no more than four workplaces Internal and external lighting is designed in accordance with the reference standards. The lighting is zoned and control in the relevant areas. - zones of no more than four workplaces - workstations adjacent to windows are separately zoned	Internal and External lighting drawings

Hea 02: Indoor air quality	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements	Typical Responsibility	Stage Due
Indoor air quality (IAQ) plan	0	0	An indoor air quality plan is developed for when the building is occupied	Copy of the indoor air quality plan	Consultant	Stage 4
Ventilation	1	1	Ensure the building has been designed to minimise pollutants internally	Drawings showing how building has been designed to minimise pollutants Drawings showing vent pathways have minimised air-pollutants Drawings showing HVAC systems have incorporated suitable filtration Install demand controlled ventilation Supply & exhaust intakes and outtakes must be 10m apart horizontally	Cudd Bentley	Stage 4
Emissions from construction products	2	2	1 credit - 3 out of 5 products from table 5.11 meet the VOC's emissions criteria. 2 credits - all products from table 5.11 meet the VOC's emissions criteria	Manufacturer's testing certificates and results	Consultant	At project completion
Post-construction indoor air quality measurement	1	1	The formaldehyde concentration in indoor air is measured post construction and does not exceed 100 µg/ m <sup>3</sup> averaged over 30 minutes The total volatile organic compound (TVOC) concentration in indoor air is measured post construction and does not exceed 500 µg/ m <sup>3</sup> over 8 hours.	Consultant's report	Consultant	At project completion
Hea 04: Thermal comfort	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements	Typical Responsibility	Stage Due
Thermal modelling	1	1	Dynamic thermal modelling is carried out to demonstrate operative temperatures are in accordance with the requirements.	Thermal modelling report	Consultant	
Adaptability - for a project climate change scenario	1	1	The thermal modelling analysis is run against a future weather scenario	Thermal modelling report	Consultant	Stage 4
Thermal zoning and Controls	1	1	The thermal modelling analysis has informed the temperature control strategy	Drawings showing the heating, cooling and ventilation strategy in accordance with the criteria.	Consultant	
Hea 05: Acoustic Performance	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements	Typical Responsibility	Stage Due
Sound Insulation	2	2	Sound insulation between rooms complies with Section 7 of BS 8233:2014			Recommendation report -
Indoor ambient noise levels	1	1	Indoor ambient noise levels comply with Section 7 of BS 8233:2015	Acoustic statement/report confirming compliance	Consultant	Stage 4. Final testing at project completion
Room acoustics	1	1	Sound reverberation levels comply with Section 7 of BS 8233:2016			p. 5joor completion

Hea 04: Thermal comfort				
	Credits	Rating	Requirements	Requirements
Thermal modelling	1	1	Dynamic thermal modelling is carried out to demonstrate operative temperatures are in accordance with the requirements.	Thermal modelling report
Adaptability - for a project climate change scenario	1	1	The thermal modelling analysis is run against a future weather scenario	Thermal modelling report
Thermal zoning and Controls	1	1	The thermal modelling analysis has informed the temperature control strategy	Drawings showing the heating, cooling and ventilation strategy in acc criteria.
Hea 05: Acoustic Performance	Available	Excellent	Credit	Evidence
Hea 05. Acoustic Performance	Credits	Rating	Requirements	Requirements
Sound Insulation	2	2	Sound insulation between rooms complies with Section 7 of BS 8233:2014	
Indoor ambient noise levels	1	1	Indoor ambient noise levels comply with Section 7 of BS 8233:2015	Acoustic statement/report confirming compliance



Typical Responsibility	Stage Due
-	-
-	-
-	-
Cudd Bentley	Stage 4

### Health and Wellbeing (Hea) Continued

Available       Credits       Rating       Requirements       Responsibility       Concept statist         Security of site and building       1       1       Security specialist conducts a security needs assessment (At concept design Stage)       Security specialist report/statement in accordance with       Consultant       Concept statist         Hea 07: Safe and Healthy Surroundings       Available       Excellent       Credits       Requirements       Credit       Requirements       Concept statist       Requirements       Concept statist       Concept statist       Requirements       Concept statist       Concept s	<b>U</b> ( )						
Security of site and building       1       1       Security specialist develops a list of recommendations Recommendations are implemented in the design       Drawings/ specification detailing how recommendations have been incorporated       Consultant       Concept st         Hea 07: Safe and Healthy Surroundings       Available Credits       Excellent Rating       Credit Requirements       Credit Requirements       Credit Requirements       Credit Requirements       Credit Requirements       Evidence Requirements	Hea 06: Safety and Security						Stage Due
Security specialist develops a list of recommendations Recommendations are implemented in the design       Drawings/ specification detailing how recommendations have been incorporated       Typical Recommendations         Hea 07: Safe and Healthy Surroundings       Available Credits       Excellent Rating       Credit Requirements       Credit Requirements       Excellent Requirements       Typical Responsibility       Stage Du Responsibility         Safe access       1       0       Criteria must be met for cycle paths, footpaths, drop-off areas, pedestrian crossings, signposting and access road lighting Criteria must be met for parking, waiting areas, turning areas and storage areas for       Design drawings (including a scaled site plan), AND/OR relevant sections of the specification highlighting all necessary compliant features and dimensions       Image: Criteria must be met for parking, waiting areas, turning areas and storage areas for	On write of site and building	1	1	Security specialist conducts a security needs assessment (At concept design Stage)	Security specialist report/statement in accordance with	Orment	0
Hea U/: Safe and Healthy Surroundings       Credits       Rating       Requirements       Requirements       Requirements       Requirements       Responsibility       Stage Duty         Safe access       1       0	Security of site and building	I		• • • • • • • • • • • • • • • • • • •	Drawings/ specification detailing how recommendations have been incorporated	Consultant	Concept stage
Hea UY: Safe and Healthy Surroundings       Credits       Rating       Requirements       Requirements       Requirements       Requirements       Responsibility       Stage Duty         Safe access       1       0       Criteria must be met for cycle paths, footpaths, drop-off areas, pedestrian crossings, signposting and access road lighting       Design drawings (including a scaled site plan), AND/OR relevant sections of the previous of the period burget of the previous of the period burget of the period burg		Available	Excellent	Credit	Evidence	Typical	
Safe access 1 0 signposting and access road lighting areas, turning areas and storage areas for parking, waiting all necessary compliant features and dimensions	Hea 07: Safe and Healthy Surroundings					1 C C C C C C C C C C C C C C C C C C C	Stage Due
Criteria must be met for parking, waiting areas, turning areas and storage areas for specification highlighting all necessary compliant features and dimensions	Safe access	1	0			_	_
delivery / goods vehicles		ľ	0	Criteria must be met for parking, waiting areas, turning areas and storage areas for delivery / goods vehicles	specification highlighting all necessary compliant features and dimensions		
Outside Space       1       1       There must be an "outside space" near to the site for building users to use       Drawings/site plan showing outside amenity       Corstorphine & Wright       Stage 4	Outside Space	1	1	There must be an "outside space" near to the site for building users to use	Drawings/site plan showing outside amenity		Stage 4

### Energy (Ene)

Ene 01: Reduction of energy use and carbon emissions	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements
Mandatory >4 - Energy performance	9	5	Calculate the Energy Performance Ratio (EPR). Compare the EPR achieved with the benchmarks in Table - 25 and award the corresponding number of BREEAM credits	Dynamic Simulation Modelling (DSM) output files
Prediction of operational energy consumption	4	4	Hold a workshop focusing on operational energy and efficiency	Meeting minutes / workshop outcomes report
Frediction of operational energy consumption	4	4	Undertake energy modelling to predict building's energy consumption and highlight risks to monitor during construction and commissioning	Energy modelling report
	Available	Excellent	Credit	Evidence
Ene 02: Energy monitoring	Credits	Rating	Requirements	Requirements
Mandatory - Sub metering of major energy consuming systems	1	1	Install energy metering systems that can assign fuel to each end use	Spec's and drawings/schematics
Sub metering of high energy load and tenancy areas	0	0	Install separate accessible sub-meters to each unit that have open communication protocol to enable future connection to an energy monitoring & management system	Spec's and drawings/schematics
	Available	Excellent	Credit	Evidence
Ene 03: External lighting	Credits	Rating	Requirements	Requirements
			Average luminous efficacy is not less than 60 luminaire lumens per circuit Watt	External lighting schedule/ specification/calculations
External lighting	1	1	External lighting includes for a timeclock, daylight sensor and presence detection	External lighting drawings
			(where appropriate)	External lighting datasheets
Ene 04: Low carbon design	Available	Excellent	Credit	Evidence
Life 04. Low carbon design	Credits	Rating	Requirements	Requirements
Passive design	1	1	A passive design analysis is undertaken and the Hea 04 thermal comfort credit has been achieved	Energy report Evidence as required for Hea 04
Free cooling	1	1	Implementation of free cooling solutions	Ventilation analysis using free cooling methods
Low and zero carbon technologies	1	1	A low and zero carbon feasibility study has been undertaken	LZC Energy strategy
Low and zero darborr technologies	I		A fow and zero carbon redaibility study has been undertaken	Specification/drawings showing renewable tech



Typical Responsibility	Stage Due
Consultant	Concept, update at stage 4, update at PC
Consultant	Stage 4
Typical Responsibility	Stage Due
Cudd Bentley	Stage 4
-	-
Typical Responsibility	Stage Due
Cudd Bentley	Stage 4
Typical Responsibility	Stage Due
Consultant	Concept stage
Consultant	Concept stage
Consultant	Concept stage

### BREEAM NEW BUILD - PRE ASSESSMENT

The explanation and outline of how to achieve each credit is found below in the following sections:

Ene 05: Energy efficient cold storage	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements
Refrigeration energy consumption	1	1	Install a refrigeration system in accordance with the Code of Conduct for carbon reduction in the refrigeration retail sector, BS EN 378-2:2016 Install a refrigeration system that is included on the Enhanced Capital Allowance (ECA) Energy Technology Product List (ETPL)	Manufacturer / product certification
			Commission the refrigeration plant	Commissioning certificate
Indirect Greenhouse gas emissions	1	0	Demonstrate a saving in greenhouse gas emissions from the installed refrigeration system	Report & calculations outlining reductions
Ene 06: Energy efficient transportation systems	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements
Energy consumption	1	1	An analysis of the transportation demand and usage patterns for the building, to determine the optimum number and size of lifts The energy consumption has been estimated in accordance with BS EN ISO 25745 Energy performance of lifts, escalators and moving walks, Part 2: Energy calculation and classification for lifts (elevators).	Usage pattern analysis Energy Performance Certificate
			Consider the use of regenerative drives, or justify why one is not beneficial (i.e. if the lift is not going to be high use/high speed).	Usage and energy consumption analysis and calculations
Energy efficient features	1	1	Lift can operate in a standby condition Lift display lighting is above 70 lm/W Lift uses VVVF controls	Confirmation from lift manufacturer Bulb tech details Confirmation and product details from lift manufacturer
Ene 08: Energy efficient equipment	Available	Excellent	Use a regenerative drive, if its proven to save energy Credit	Confirmation and product details OR calculations showing minimal energy wi Evidence
	One alter	D II	Description	De su incere ente

Ene 08: Energy efficient equipment	Available	Excellent		Evidence
Ene bo. Energy emolent equipment	Credits	Rating	Requirements	Requirements
Energy efficient assessment criteria	2		Identify the building's unregulated energy consuming loads, and estimate their yearly contribution to total unregulated energy consumption Demonstrate how the total annual unregulated energy consumption of the building can be reduced.	Report & calculations outlining reductions

### Transport (Tra)

Tra 01: Transport assessment and travel plan	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements	Typical Responsibility	Stage Due
Travel plan	2	2	Develop a travel plan based on a site-specific travel assessment	Copy of travel plan	Consultant	Concept stage
Tra 02: Proximity to amenities	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements	Typical Responsibility	Stage Due
			Al is > 8.0	Al calculation	-	-
			Increase AI through negotiation with local bus, train and tram services with dedicated services for this building	Confirmation from local authority	-	-
			Provide a dedicated transport information system for inhabitants	Photograph of system on site	-	-
			10% of all car park spaces have electric vehicle charging stations	drawings and photographs of units on site	Corstorphine & Wright	Stage 4
			Set up car sharing group, promote with marketing provide priority parking spaces for car sharing vehicles	Confirmation from car share group and copies of marketing material	-	-
Transport options implementation	10	2	Consult with local authorities on cycling and pedestrian routes. Agree how to improve it and implement on site	Proof of consultation with local authority, drawings and photos showing measures on site	-	-
			1 cycle space per 10 staff members	Drawings and photos showing spaces on site	Corstorphine & Wright	Stage 4
			Achieve cycle spaces outlined above, and at least two of the following: showers, changing facilities, lockers, drying spaces	Drawings and photos showing facilities on site	-	-
			At least three existing accessible amenities are present, see Table 7.6 on page 191	Map and photos showing amenities	-	-
			Ensure one or more new amenities are available	Drawings and photos showing amenities	-	-
			Implement a transport improvement measure not outlined above	Robust evidence showing measure on site	-	-



Typical Responsibility	Stage Due
Contractor	At project completion
Contractor	
-	-

	Typical Responsibility	Stage Due
	Contractor	Stage 4
y will be saved	Contractor	Stage 4

Typical
Responsibility

Responsibility	Stage Due
-	-

Stago Duo

### Water (Wat)

Wat 01: Water consumption	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements
Mandatony > 1 aradit we want a	5		An assessment of the building's predicted water using components is undertaken using	Component data sheet confirming inputs
Mandatory > 1 credit - Water consumption	5		the Wat 01 calculator in line with Table 8.3	Wat 01 Calculator
Wat 02: Water monitoring	Available	Excellent	Credit	Evidence
wat uz. water monitoring	Credits	Rating	Requirements	Requirements
Mandatory - Water monitoring & metering	1		Specification of a mains water meter on each supply, easily accessible meters and	Water metering schematic/drawing
water monitoring & metering	'		pulsed connection to a BMS	Water meter datasheet
Wat 03: Water leak detection and prevention	Available	Excellent	Credit	Evidence
wat 05. Water leak detection and prevention	Credits	Rating	Requirements	Requirements
Leak detection system	1	1	A mains water leak detection system is installed	Specification/drawings
Flow control devices	1	1	Install flow control devices to all sanitary fittings	Specification/drawings/product data sheets
Wat 04: Water efficient equipment	Available	Excellent	Credit	Evidence
wat 04. water emclent equipment	Credits	Rating	Requirements	Requirements
			Identify all water demands that are not listed under Wat 01.	
Water efficient equipment	1	0	Identify systems or processes that can reduce the water demand from said water	Report & calculations outlining reductions
			demands, and establish a reduction in the total water demand.	

### Materials (Mat)

Mat 01: Environmental impacts from construction products - Building life cycle assessment (LCA)	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements
Superstructure	7	5	Carry out an LCA on the superstructure at concept stage Carry out an LCA on the superstructure at design stage	Mat 01 tool
Superstructure	,		Optimise materials use at concept stage	4 no. Mat 01 tool options
			Optimise materials use at design stage	3 no. Mat 01 tool options
Substructure and hard landscaping options	1		Substructure and hard landscaping material use optimisation at concept stage	6 no. Mat 01 tool options
Mat 02: Environmental impacts from construction	Available	Excellent	Credit	Evidence
products - Environmental Product Declarations (EPD)	Credits	Rating	Requirements	Requirements
Specification of products with a recognised EPD	1	0	Only specify building material products that achieve EPD points	EPD's from material manufacturers
Specification of products with a recognised EPD	I	0	Only specify building material products that achieve EFD points	Mat 02 tool
Mat 03: responsible sourcing of construction materials	Available	Excellent	Credit	Evidence
Mat be. responsible sourcing of construction materials	Credits	Rating	Requirements	Requirements
Mandatory - Timber	0		All timber and timber-based products used on the project is to be legally harvested and	
	0	0	traded timber	Contract clause/ written confirmation
	0	0		Contract clause/ written confirmation
Enabling sustainable procurement plan	1	1		Contract clause/ written confirmation Copy of the site specific sustainable procurement plan
	1	1	traded timber	
Enabling sustainable procurement plan	1	1	traded timber Materials are sourced in accordance with a site specific sustainable procurement plan >10% (1 credit), >20% (2 credits), >30% (3 credit) of the responsible sourcing materials	
	1	0 1 3	traded timber Materials are sourced in accordance with a site specific sustainable procurement plan	Copy of the site specific sustainable procurement plan Mat 03 proforma - confirming quantities and suppliers of the major build
Enabling sustainable procurement plan	1	0	traded timber Materials are sourced in accordance with a site specific sustainable procurement plan >10% (1 credit), >20% (2 credits), >30% (3 credit) of the responsible sourcing materials	Copy of the site specific sustainable procurement plan



Typical Responsibility	Stage Due
Corstorphine & Wright	Stage 4
Typical Responsibility	Stage Due
Cudd Bentley	Stage 4
Trainel	
Typical Responsibility	Stage Due
Cudd Bentley	Stage 4
Cudd Bentley	Stage 4
Typical Responsibility	Stage Due
-	-

	Typical Responsibility	Stage Due
	QuinnRoss Energy	Concept stage
	Typical Responsibility	Stage Due
	-	-
	Typical Responsibility	Stage Due
	Contractor	At project completion
	Contractor	Prior to construction starting
building materials	Contractor	At project completion

### Materials (Mat) Continued

Mat 05: Designing for durability and resilience	Available Credits		Credit Requirements	Evidence Requirements	Typical Responsibility	Stage Due
Protecting vulnerable parts of the building from damage			Specification of suitable external and internal protection measures	Drawings/specification confirming measures included to protect the building e.g. Kick plates, corner protection, external kerbs and bollards etc.		
Protecting exposed parts from material degradation	1	1	Specification of measures to limit material degradation due to environmental factors	Drawings/specification confirming the inclusion of measures to limit material degradation effects (corrosion, swelling, fading, rotting melting abrasion etc.).	Consultant	Stage 4
Mat 06: Material efficiency	Available Credits		Credit Requirements	Evidence Requirements	Typical Responsibility	Stage Due
Material efficiency (Criteria 1-2)	1	0	Opportunities have been identified, investigated and documented to optimise the use of materials throughout the building design, procurement and refurbishment.	Documented investigation at each RIBA stage	-	-

### Waste (Wst)

Wst 01: Construction waste management	Available	Excellent	Credit	Evidence	Typical	Stage Due
Wet off. Construction Waste management	Credits	Rating	Requirements	Requirements	Responsibility	
Pre-demolition audit	0	0	Complete a pre-demolition audit which outlines which materials from the demolition process can be re-used or recycled	Copy of pre-demolition audit	-	-
			Resource Management Plan (RMP) has been developed	RMP		
Construction resource efficiency	3		Construction waste m <sup>3</sup> or tonnes meets or is lower than targets set out in table 51	Waste volume calculations & confirmation	Contractor	Prior to construction starting, then updated at
Diversion of resources from landfill	1	1	Where over 70% (volume) of non-demolition and 80% of demolition waste (tonnage) is diverted from landfill	Waste volume calculations & confirmation	Contractor	PC
	Available	Excellent	Credit	Evidence	Typical	
Wst 02: Recycled aggregates	Credits	Rating	Requirements	Requirements	Responsibility	Stage Due
Recycled aggregates	1	0	A high percentage of aggregate is recycled or secondary aggregate	Calculations demonstrating the use of recycled aggregates with percentages	-	-
	Available	Excellent	Credit	Evidence	Typical	
Wst 03: Operational waste	Credits	Rating	Requirements	Requirements	Responsibility	Stage Due
		, se g		Drawing indicating the location of the bin store provision		
Operational waste	1		Provision of a dedicated spaces for the segregation and storage of operational	Confirmation they are suitably sized and will have the necessary labelling in place	Corstorphine &	Stage 4
			recyclable waste	Drawings indicating the location of storage and manufacturers literature detailing capacity	Wright	Ū
				oupuoity		
	Available	Excellent	Credit	Evidence	Typical	
Wst 04: Speculative finishes	Credits	Rating	Requirements	Requirements	Responsibility	Stage Due
		5	Only install floor and ceiling finishes in a show area, OR	Drawings and photo of show area		
			Only install floor and ceiling finishes in line with the tenants requirements, OR	Internal finishes' drawings, meeting minutes with tenant, signed contract showing finishes' will not be changed		
Speculative floor and ceiling finishes	0	0	Only install ceiling finishes, not floors, and ensure the tenant will not alter the ceilings O	Internal finishes drawings, signed contrast showing altering osiling finishes' is not	-	-
			Don't install floor or ceiling finishes	Photos showing no finishes		
			5			
	Available	Excellent	Credit	Evidence	Typical	
Wst 05: Adaptation to climate change	Credits	Rating	Requirements	Requirements	Responsibility	Stage Due
Adaption to climate change - structural and fabric resilience	1	1	A climate change adaptation strategy appraisal for the structural and fabric resilience is	Climate change strategy appraisal	Consultant	Stage 4
Adption to omnute ondrige - official and rabito reallence			undertaken	onnate onange onategy appraida	oonsultant	Oldge 4



### Waste (Wst) Continued

Wst 06: Design for disassembly and adaptability	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements
Recommendations	1	1	Conduct a study to explore the ease of disassembly and adaptation of different design scenarios	Marked up plans detailing adaptable measures
			Achieve criteria 1-2 above	See above
Implementation	1	1	Outline how recommendations have been adapted into the design	Marked up plans detailing adaptable measures
			Produce a building adaptability and disassembly guide	Copy of building adaptability and disassembly guide

### Land Use and Ecology (LE)

LE 01: Site selection	Available	Excellent	Credit	Evidence	Typical	Stage Due
	Credits	Rating	Requirements At least 75% of the footprint is on an area of land which has previously been occupied	Requirements	Responsibility	Ŭ
Previously occupied land	1	0	by industrial, commercial or domestic buildings	Site layout drawings detailing existing and proposed buildings	-	-
Contaminated land	1	0	Site investigation confirms land is contaminated, remediation is in line with	Report from contaminated land specialist and confirmation from client that report has	-	_
		0	contaminated land specialist's report	been adhered to		
LE 02: Identifying and understanding the risks and	As an the letter	E	Or a l't	Friday	Tructural	
opportunities for the project	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements	Typical Responsibility	Stage Due
	oreans	Rating				
Determining the ecological outcomes of the site	2	2	Ecologist surveys and evaluates site and raises recommendations in a site report	Copy of ecologist's report & GN40 completed	CSA	Concept stage
LE 03: Managing negative impact on ecology	Available	Excellent	Credit	Evidence	Typical	Stage Due
	Credits	Rating	Requirements	Requirements	Responsibility	
Identifying and understanding the risks and opportunities for the project	0	0	Achieve LE 02	See above	CSA	Concept stage
			Roles and responsibilities are defined, site prep and works have been planned and	Meeting minutes with design team outlining ecologist's recommendations and		
Planning, liaison, implementation and data	1	1	project team and stakeholders have implemented solutions and measures	discussions	RPS	Concept stage
Managing negative impacts of the project	2	2	Ecologist report outlines how construction can have no impact on ecology of site	Copy of ecologist's report confirming mitigating measures on & GN40 completed	CSA	Concept stage
	Available	Excellent	Credit	Evidence	Typical	
LE 04: Change and enhancement of site ecology	Credits	Rating	Requirements	Requirements	Responsibility	Stage Due
Identifying and understanding the risks and opportunities for the project	0	0	Achieve LE 03	See above	CSA	Concept stage
······································						j-
Liaison, implementation and data collection	1	1	Using data gathered, solutions and measures selected enhance ecological value	BREEAM CEEQUAL calculator completed and drawings showing areas	CSA	Concept stage
Enhancement of ecology	3	2	Ecologist report outlines how ecology has been enhanced in line GN.36	Copy of ecologist's report outlining enhancing solutions	CSA	Concept stage
	5	2	Leologist report outlines now ceology has been enhanced in nine on so	copy of ecologist sheport outlining enhancing solutions	UUA	Concept stage
					<b>—</b>	
LE 05: Long term ecology management and maintenance	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements	Typical Responsibility	Stage Due
	orcuits	Rating				
Roles and responsibilities, implementation, statutory obligations	0	0	Achieve LE 04	See above	CSA	Concept stage
Planning, liaison, data, monitoring and review management and	1	0	The project team liaise and collaborate with representative stakeholders, taking into	Document / copy of contract showing responsibilities of management of ecology for next	DDC	
maintenance	I	0	consideration data collated and shared, on solutions and measures implemented	5 years	RPS	Concept stage
	1	0	Ecologist produces a landscape and ecology management plan to be handed over to		001	0
Landscape and ecology management plan (or similar) development	I	0	facilities management	Copy of landscape management plan	CSA	Concept stage



Typical Responsibility	Stage Due
Consultant	Stage 4

1

### Pollution (Pol)

Pol 01: Impact of refrigerants	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements
Impact of refrigerants	3	3	No refrigerants on site	HVAC drawings
OR	-	-	-	
Prerequisite	0	0	All systems comply with BS EN 378:2017	Confirmation from manufacturer
Impact of refrigerants	0	0	The direct effect life cycle CO₂ equivalent emissions (DELC) of ≤ 100 CO₂-eq/Kw	Air Conditioning schedule Datasheet for the AC system Pol 01 calculator
Leak detection system	0	0	A permanent automated refrigerant leak detection system is installed of continuously monitoring for leaks.	Schematics Manufacturer's literature Photo of it installed on site
Pol 02: Local Air Quality	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements
Plant NOx emissions	2		NOx emissions for the heating and hot water are limited to <100mg/kWh	Heating schedule datasheet
Pol 03: Surface water run-off	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements
Flood resilience	2	2	A qualified consultant performs a site specific Flood Risk Assessment (FRA) to confirm the probability of flooding is low	copy of FRA
Surface water run-off	2	2	Calculations to demonstrate the run-off rates for the site meet the BREEAM criteria/ for	Marked up site plan
	Z		one credit if there is no increase in impermeable area	Pol 03 Proforma
Minimising watercourse pollution	1	1	No discharge from the site for rainfall up to 5mm and the provision of pollution	Surface water run-off report Pol 03 Proforma

interceptors were appropriate

Pol 04: Reduction of night time light pollution External lighting	Available Credits 1	Excellent Rating 1	Credit Requirements External lighting strategy complies with the necessary standards and the circuit has a timeclock	Evidence Requirements External lighting drawing Specification/ confirmation of necessary standards
Pol 05: Reduction of noise pollution	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements
Naisa a Unitar	1		A noise impact assessment is carried out in compliance with BS 7445 and noise	Noise impact assessment
Noise pollution	I		pollution levels are restricted.	Commitment to under post completion but pre-occupancy testing

### Innovation (Inn)

Minimising watercourse pollution

Inn 01: Innovation	Available Credits	Excellent Rating	Credit Requirements	Evidence Requirements	Typical Responsibility	Stage Due
Man 03: CCS	1		Achieve all items for vehicle movement, pollution management, tidiness, health & wellbeing, security processes, training and site monitoring	CCS intermittent site reports and final certificate confirming score	Contractor	At project completion
Mat 01: LCA	1	1	Perform life cycle assessment options for 3 no. noticeably different HVAC options	LCA options output uploaded to BREEAM projects at concept stage & summary report	QuinnRoss Energy	Concept stage

Pol 03 Proforma

Drainage drawing



Typical Responsibility	Stage Due
Cudd Bentley	Stage 4
-	-
-	-

Typical	
Responsibility	
Cudd Bentley	

Stage 4
---------

Stage Due

Stage Due

### Typical Responsibility

Consultant	Stage 4
-	-
-	-
-	-
-	-
-	-

Typical Responsibility	Stage Due
Cudd Bentley	Stage 4
Typical Responsibility	Stage Due
Consultant	Recommendation report - Stage 4. Final testing at project completion