



Field of Play Lighting Report

October 2023

Confidential

This page left intentionally blank for pagination.

Mott MacDonald 4/5 Union Terrace Aberdeen AB10 1NJ United Kingdom

T +44 (0)1224 641348 mottmac.com

Oxford United Football Club

Oxford United New Stadium Development

Field of Play Lighting Report

October 2023 Confidential

Issue and Revision Record

Revision	Date	Originator	Checker	Approver	Description
P01	05/10/23	RC	DR	DR	Issue for Planning

Document reference: 100111993 | P01 | 111993-MM-XX-XX-SL-N-00001

Information class: Standard

This document is issued for the party which commissioned it and for specific purposes connected with the above-captioned project only. It should not be relied upon by any other party or used for any other purpose.

We accept no responsibility for the consequences of this document being relied upon by any other party, or being used for any other purpose, or containing any error or omission which is due to an error or omission in data supplied to us by other parties.

This document contains confidential information and proprietary intellectual property. It should not be shown to other parties without consent from us and from the party which commissioned it.

Contents

Exe	cutive	e summary	1	
1	Introduction			
	1.1	Background	2	
	1.2	Scope	2	
2	Basis of Design			
	2.1	Design Standards	3	
	2.2	Design Criteria	3	
3	Field of Play Lighting			
	3.1	Design	4	
	3.2	Luminaires	4	
Α.	Reference Design (Signify)		5	

Executive summary

This report summarises the current proposals for the Field of Play (FOP) lighting within the new proposed Oxford United Football Club stadium.

The current proposals have been developed in conjunction with Signify, representing the current stage of design (RIBA Stage 2) and are subject to further design development.

In the next stages of design, the FOP lighting will be developed to confirm exact luminaire locations, types and aiming angles to optimise the lighting within the bowl and reduce unwanted spill light.

1 Introduction

1.1 Background

Mott MacDonald Ltd. have been engaged by Oxford United Football Club (OUFC) to provide initial Field of Play (FOP) lighting design advice to inform the planning application and design of other services. FOP/sports lighting is a specialist activity, and alongside initial calculations by Mott MacDonald, Signify (Philips) have also been consulted for specialist concept input.

1.2 Scope

The current FOP lighting proposals have been developed in conjunction with Signify, representing the current stage of design (RIBA Stage 2) and are subject to further design development. The design criteria, results of initial calculations and the proposed FOP lighting concepts are included within this report.

2 Basis of Design

2.1 Design Standards

The FOP lighting shall be designed with reference to good practice and guidance as provided by the appropriate professional institutions, British Standards, Building Regulations and allied advisory bodies.

The installation shall conform to all relevant standards, legislations and guidance including the following:

- Championship Football Regulations, EFL Handbook 2023/24
- SLL Lighting Handbook
- SLL GN01 Guidance Note 1 for reduction of Obtrusive Lighting
- CIBSE LG4 Sports Lighting
- Building Regulations
- BS7671 Wiring Regulations

2.2 Design Criteria

The FOP lighting shall be designed to the following criteria:

	Championship	Class I	Class II	Class III	Setup
Criteria	EFL Regulations	SLL LG4	SLL LG4	SLL LG5	
Eh ave (average horizontal illuminance)	> 800 lux	500 lux	200 lux	75 lux	10 lux
Eh min (minimum horizontal illuminance)	500 lux				
Ehgoal min (minimum horizontal illuminance at centre point of each goal line)	750 lux				
Uniformity U1h		0.7	0.6	0.5	0.5
Colour temperature (Tk)	TBC	TBC	TBC	TBC	TBC
Colour rendering	TBC	TBC	TBC	TBC	TBC
Glare rating (GR)	< 50	< 50	< 50	< 50	< 50

3 Field of Play Lighting

3.1 Design

The roof of the stadium is asymmetric, with the west edge ranging from a height of 19m to 23m and the east edge ranging from approximately 17m to 21m.


The design of the FOP lighting has been chosen to follow the roof edges, with luminaires mounted on the underside of the roof edges on both the west and east stands.


The reference design (Refer Appendix A) consists of 36 no. luminaires along each side (72 no. total), mounted approx 2m apart. The total connected electrical load of these luminaires is approximately 72kW.

3.2 Luminaires

The exact luminaire specification to be used may vary, however the reference design produced to date is based on the Philips Arenavision LEG Gen 3.5 BVP418.







A. Reference Design (Signify)

LiAS Design Notes

This preliminary design is produced by the Lighting Application Specialist (LiAS) team of Signify UK based on information supplied by the Customer for the purpose of identifying suitable products and costing the proposal. This design cannot be used for Construction, as this design does not purport to eliminate health and safety risks as a CDM Regulation risk assessment has not been undertaken.

Depending on the level of information received, a number of assumptions may have been applied in order to create an indicative lighting proposal and costing model, according to lighting industry guidelines and incorporating industry best practice methods. These assumptions are documented below and will require confirmation by the Principal Designer (which is not Signify UK) during the detailed design phase.

Generic Assumptions (unless specifically informed differently)

- Preliminary Design proposals produced by the Signify LiAS Team are not to be used for installation purposes. It is the responsibility of the Principle Designer and/or Principle Contractor to ensure all Installation and Maintenance can be done in a safe manner, carried out by competent persons, based on their agreed Risk Assessments and Method Statements.
- The Luminaire Maintenance Factors have been based on the Environmental Zone the scheme is to be installed and the mounting height of the luminaire
- Energy consumptions have been based on the whole life of the luminaire
- The design calculations produced by Signify do not account for the effect obstructions, such as trees, will cause.
- · Signify has not been provided with utility plans showing Buried, Above Ground or Overhead utilities. Therefore, all column/luminaire locations are indicative and are subject to review/verification by the Principle Designer.
- Unless stated otherwise, Signify has not visited site. Therefore, all column/luminaire locations are indicative and are subject to an onsite verification arranged/performed by the Principle Designer.
- Signify has not produced any Private Cable Network electrical calculations or reviewed the DNO network to confirm power supplies to the proposed lighting.
- Signify has not performed any asset condition testing and therefore assumes that any existing lighting columns/wall mounted brackets are structurally capable of supporting the weight & windage of the proposed luminaire/s. This must be verified by the Principle Designer before installation works commence.
- Unless stated otherwise, Signify is not supplying the new lighting columns (including brackets etc) and therefore it is the responsibility of the Principle Designers to confirm that all proposed equipment is suitable for the intended locations (e.g. raise & lower, ground condition, foundation type, saline environment, etc).
- . Unless stated otherwise, luminaires will be supplied in their standard colour.

Project Specific Information

Design to achieve Eh 800 lux Championship level. MF 0.95 (Low Use LED) Eh 800 lux, 500 lux Min, 750 lux centre of goaline

Fittings mounted on edge of new side stand roofs at various heights Heights range from 17m to 21 m Bottom Line & 19m to 23m Top Line on sloped roof MF 0.9









Remote LED Driver for BV

Signify Lighting Contacts

Alex Rowe, Key Account Manager - 07919 395101 - alex.rowe@signify.com

Lighting Proposal Terms and Conditions of Use

These terms apply to the use of this preliminary proposal produced by Signify UK. This "Proposal" is understood to mean this document, a CAD drawing lighting calculations, written documents, verbal conversations or any medium used to demonstrate or communicate the proposed lighting characteristics from Signify's brands. A "Customer" is the person or organisation for whom the Proposal is intended: The "CDM Regulations" means The Construction, Design and Management Regulations 2015, the Safety, Health & Welfare at Work Act 2005, The Construction (Design & Management) Regulations (Worthern Ireland) 2015.

This Proposal is for guidance only and cannot be relied upon for purposes of installation or Health and Safety.

The supply and installation of this lighting scheme are subject to a contract being agreed between Customer and Signify.





			550	0.00			
Rev	DSR no.	Comment	Date	LiAS	KAM	Project Number	1
0	D-527534	Championship Eh 800 lux ave, 500 lux Min, 750 lux Goaline	19/09/23	SJ	AR	0400907626	
						0400907626	
						Scale & Sheet Size	7
_						NITC @ A2	Н
						NTS @ A3	1
						Sheet No	٦
						DWG 00	П
						DVVG 00	





Oxford United FC, New Stadium Drawing Name

LIAS DESIGN NOTES & LUMINAIRE SCHEDULE









mottmac.com