



PLANTING SCHEDULE

Proposed Hedgerow Planting
 Planted at 5 plants per linear meter, in double-staggered rows at 40cm apart

Species	Mix %	Height cm	Form	Age / Times Transplanted	Root Condition
<i>Acer campestre</i>	7.5	80-80	Transplant	1+1	B
<i>Cornus sanguinea</i>	5	60-80	Transplant	1+1	B
<i>Crataegus monogyna</i>	50	60-80	Transplant	1+1	B
<i>Fagus sylvatica</i>	5	60-80	Transplant	1+1	B
<i>Malus sylvestris</i>	5	60-80	Transplant	1+1	B
<i>Prunus spinosa</i>	20	60-80	Transplant	1+1	B
<i>Rosa canina</i>	7.5	60-80	Transplant	1+1	B

DATE	NO	REVISION NOTE
------	----	---------------

Himley Village
Bicester

DATE	SCALE	TEAM	APPRVD
15/10/2024	1:2000 @AO	IBD	RVF

P22-3093_EN_002_07