



soakaway to s.eng details; min 5 metres from buildings or retaining walls

Aco drain at threshold connected to new sw drain

Perimeter floor drain connected to new sw drain

rwp  
0

0.85ht

stone wall

	EXISTING FOUL DRAIN
	100mm STORM DRAIN
	100mm FOUL DRAIN
	STORM INSPECTION CHAMBER
	FOUL INSPECTION CHAMBER

NOTE:

- ALL I.C./ MANHOLES ARE SUBJECT TO MINOR RE-POSTIONING TO SUIT FINALISED EXTERNAL WORKS
- YARD CULLEYS MAY BE ADDED TO SW SCHEME DEPENDING ON ARRANGEMENT & CHOICE OF EXTERNAL HARD SURFACES

REV	DATE	BY	DESCRIPTION	CHK	APD
DRAWING STATUS: <b>BUILDING REGULATIONS</b>					
<b>QUAY ASSOCIATES</b>					
THE POUND SHENINGTON OXFORDSHIRE OX15 6NB					
+44 (0) 7798 525 535 ar@quaytect.com					
CLIENT  Bruce Roe Esq.					
PROJECT  NORTH ARMS HOUSE WROXTON OX15 6PY					
TITLE  UNDERGROUND DRAINAGE & SERVICES					
SCALE	DATE	DESIGN/DRAWN	CHECKED	APPROVED	SHT
1:200	OCT 2023				
JOB No.  22070					
DRAWING No.  22070/GA15 1					