



KEY:

- Site Boundary
- Existing Trees
- Existing Shrubs
- Proposed Trees
- Proposed Hedge
- Proposed Feature Shrub
- Proposed Shrubs
- Proposed Climbers



PLANTING NOTES  
All plants to be supplied in accordance with the HTA National Plant Specification and from a HTA certified nursery. All plants and trees to be planted in accordance with BS5836. Delivery and handling of all plant material to be in accordance with BS4422/JC/LC/PSE Code of Practice for Handling and Establishing Landscape Plants Parts 1, 11 and 12. All excavated areas to be backfilled with other site won topsoil or imported topsoil to be BS3882-General purpose grade. All topsoiled areas to be clear of rocks and rubble larger than 50mm diameter and any other debris that may interfere with the establishment of plants. Tree pits in soft landscape to be excavated to 1000mm depth prior to topsoiling and all shrub planting areas excavated to 450mm depth. All plants shall be planted in a random fashion matching formal regeneration lines, as detailed indicated in the schedule, unless otherwise specified. Unless otherwise specified, all hedgerows shall be planted in a double staggered rows and hedgerow mixes shall be planted in groups of 7, 9, 13 at densities indicated on the schedule. Ornamental shrub planting mixes shall be planted in groups of 5, 7, 8 and where shrub planting mixes shall be planted in groups of 9, 13 & 15x. All plants shall be watered in to field capacity immediately after planting and mulched with 50mm depth of medium grade crushed mulch. All trees to be double staked with cross bar and level, using 1.5m long, 10mm diameter rounded tree stakes 75mm brace, rubber tie and spacer spacers. Stakes not to extend more than 150mm above ground level. All trees within hardstanding/highways visibility triangles to be clear stem to 1.5m high unless otherwise specified. Planting and associated operations shall comply with BS4343, BS4328 and BS5837. Root barriers (ReRoot 1000 or equivalent) to be included adjacent to buildings and services where necessary. Unless otherwise stated planting shall be carried out during the period of 1 Nov to 31 March when the ground is not frozen or water logged. If planting is required outside this period agreement shall be sought and all bare root plants shall be substituted with container grown stock. All Fruiting species to be UK grown specimens from healthy, disease-free stock and from reputable suppliers and HTA certified nurseries.

PROTECTION OF EXISTING VEGETATION TO BE RETAINED  
Existing trees to be retained shall be protected in accordance with BS5837, from commencement to completion of all works on site.

REV	DATE	DESCRIPTION	BY
E	23.09.2014	Tree to plot 110 frontage removed	BS JC
F	03.03.2014	Updated to comments from Local Authority	KC KC
D	27.01.2014	Updated to latest comments and base	JC KC
C	27.09.2013	Updated to latest comments and base	JC KC
B	16.09.2013	Updated to latest comments and base	JC KC
REV	DATE	NOTE	Drawn Chkd



TITLE  
Longford Park, Banbury  
Phase 1 - Planting Plan 1 of 5

CLIENT  
Barratt Homes, Bovis & Taylor Wimpey Homes

SCALE	DATE	DRAWN
1:250@A1	JUL 2013	CW
DRAWING NUMBER	REVISION	
5205/ ASP 1.1	F	