




# Bicester eco development: Exemplar

## Examples of Lighting Types

Drawing no. 8023-UA001881-UP23D-01

-  BS EN 13201 Lighting class CE2 to Spine lane and village centre (8m high lighting columns)
-  Spine Lane lighting adjacent to river corridor to be low level directional lighting
-  Operational lighting to school sports pitches, village centre car parks and service area







### Examples of Luminaire Types



### Example of low level directional bridge lighting



-  BS EN 13201 Lighting class S7 to classic homezones (5m columns supplemented by building mounted luminaires and bollard type lighting).
-  BS EN 13201 Lighting class S7 to exemplar homezones (5m columns supplemented by building mounted luminaires, bollard and ground level type lighting).
-  BS EN 13201 Lighting Class S7 to Green Lanes (Building mounted luminaires and bollard lighting within the curtilage of properties)
-  BS EN 13201 Lighting class S7 to Natural Play/Recreational Areas (4m columns supplemented by bollard and ground level type lighting).



a2dominion

P3Eco Ltd

Hyder