



SURVEY INFORMATION
 MK Surveys - 01908 565561
 DRG NUMBER: 17523 - Sheets 1-12
 DATE RECEIVED: 17/12/2014

ARCHITECT SITE PLAN INFORMATION
 PRP Architects - 020 7453 3444
 DRG NUMBER: AL6157C-3000/3100
 DATE RECEIVED: April 2016

NOTES

- All dimensions and levels are in metres unless otherwise noted
- This drawing is to be read in conjunction with the relevant Architect's/Engineer's drawings, specifications and CDM documentation
- This drawings has been produced electronically and may have been photo reduced or enlarged when copied. Work to figured dimensions only (DO NOT SCALE). All dimensions to be checked on site. Any errors or omissions to be reported to the engineer immediately.
- This drawing contains coloured lines / information that may not be clear if reproduced in black and white.

Drainage Key

Sewers

- Foul water drain (private/non adoptable)
- Surface water drain (private/non adoptable)
- Foul water sewer (Adoptable)
- Surface water sewer (Adoptable)
- Existing foul water sewer (Adopted)
- Existing surface water sewer (Adopted)

Chamber Key

FW Mini access chamber (mac) - 300mmØ*
SW PPIC - 475mmØ* - CP = Catchpit
 P.C.C. units/brick*
 Adoptable demarcation manhole within 1m of boundary*
 Manhole Depth 1.25 to 1.5m*
 Depth 1.55 to 3.0m*

* General note
 (Refer to standard details & long sections for chamber sizes. Size may need to increase dependant on number of incoming pipes/size of incoming pipes)

Surface water rodding eye
 Manhole reference number
 Rain water down pipe (roddable access)
 Soil vent pipe/soil stack
 Vented soil vent pipe/soil stack (minimum)
 RWP cellular discharge/collection unit

Retaining wall

FFL XX.XX Finished Floor Level (FFL)

Block paving - Permeable
 Impermeable barrier
 Permeable paving baffle
 Service baffle
 Proposed filter drain (To cater for extreme storm events)
 Indicative location of fruit tree/bush
 Land drain adjacent to retaining wall
 Areas of proposed green roof

Sheet Arrangement (1:2500)

PPIC Invert Levels

NO	IL
1	86.20
2	85.77
3	85.25
4	85.50
5	84.35
6	83.90
7	84.70
8	86.00
9	86.15
10	86.30
11	86.60
12	86.75
13	86.90
14	85.00
15	87.00
16	84.50
17	84.25
18	84.10
19	84.05
20	84.15
21	87.45
22	87.50
23	87.35
24	87.20
25	85.95
26	85.85
27	87.85
28	88.10
29	87.75
30	88.05
31	88.20

Rain Water Harvesting Tank Schedule

RWH REF	INVERT LEVEL	COVER LEVEL
31	85.300	86.25
32	84.000	84.85
33	87.150	88.20
34	85.700	86.65
35	87.200	87.60
36	87.450	87.85
37	87.750	88.45
38	88.000	88.75
39	88.000	88.80
40	88.000	88.80
41	87.700	88.40
42	87.700	88.40
43	88.100	88.70
44	87.950	88.75
45	88.100	88.90
46	88.100	88.90
47	85.700	86.70
48	85.700	86.70

Foul Manhole Drainage Schedule

MANHOLE REF	INVERT LEVEL	COVER LEVEL	GRADE 1 in	PIPE Ø (mm)	LENGTH
F11A	82.20(1250)	86.20	18.6	100	18.0
F11-a	83.691	85.30	60	100	15.0
F11-b	83.941	84.65	60	100	12.5
F11-c	84.150	84.90	60	100	12.5
F13A	85.400	88.00	80	100	35.5
F13-c	85.843	86.73	80	100	17.0
F13-d	86.055	86.70	39.5	100	23.5
F13-e	86.650	87.83	30	100	37.5
F13-f	87.900	88.70	60	100	17.0
F13c	85.843	86.73	80	100	2.5
F13c1	85.874	86.76	60	100	27.0
F11-a	83.691(OUT)	86.30	60	100	27.0
F11-d	85.700	86.45	60	100	17.0
F13A	85.400(OUT)	88.00	6	100	3.0
F13g	87.566	88.10	60	100	17.0
F13h	87.850	88.60	60	100	17.0
F12	83.545(225)	88.30	80	100	31.5
F12a	84.043	87.25	13.9	100	23.0
F12b	85.716	86.37	60	100	17.0
F12c	86.000	86.80	60	100	17.0

To be confirmed prior to commencing works on site

NOTE: ALL UNREFERENCED SURFACE WATER PIPEWORK TO BE 100mmØ UNLESS SHOWN OTHERWISE

Soakaway Table

Key	Type	Dimension
A	Type A	2m x 2m x 0.8m deep
B	Type B	2m x 4m x 0.8m deep
C	Type C	2m x 3m x 0.8m deep
D	Type D	1.5m x 2m x 0.8m deep

Base of soakaways to puncture brush layer

Rev	Drawn by	CHK'd by	Comments	Date
P04	NJ	TST	Vented soil stacks added and impermeable barrier updated. Refer to revision clouds.	20/06/16
P03	NJ	TST	Updated in-line with revised architect and landscape information	04/05/16
P02	SNN	TST	ROAD 2A and ROAD 2A-GL amended. Proposed permeable paving updated to suit	06/04/16
P01	NJ	TST	Initial issue	03/02/16

DRAWING TITLE
Proposed Drainage Plan
 Sheet 2/4

PROJECT
 Phase 2
 Bicester Eco Village
 Bicester
 Oxon

DESIGNED BY
 TST

DRAFTED BY
 NJ

APPROVED BY
 DJ

DATE
 03/02/2016

STATUS
SUBJECT TO TECHNICAL APPROVAL

SCALE
 1:250 @ A1

CLIENT

JOB NUMBER
 15-1859

DRAWING NUMBER
 03-2

REVISION
 P04

DESIGNER'S CDM NOTE - RESIDUAL RISKS NOT IDENTIFIED

The design Engineer(s) have assessed this design as the scheme has been developed in order to identify if there are any residual risks hazards (i.e. unexpected, abnormal or difficult).

No residual risks have been identified for this scheme and therefore no entries were added to the risk register.

This statement assumes that a competent Contractor with the appropriate qualified staff will be employed for the works, and that they will be familiar with site specific construction risks and hazards that may be encountered as part of their work.