

TRIP RATE CALCULATION SELECTION PARAMETERS:

Land Use : 06 - HOTEL, FOOD & DRINK

Category : C - PUB/RESTAURANT

MULTI-MODAL VEHICLES

Selected regions and areas:

02	SOUTH EAST	
	EX ESSEX	1 days
	HC HAMPSHIRE	1 days
03	SOUTH WEST	
	CW CORNWALL	1 days
	SG SOUTH GLOUCESTERSHIRE	1 days
	WL WILTSHIRE	1 days
06	WEST MIDLANDS	
	SH SHROPSHIRE	1 days
07	YORKSHIRE & NORTH LINCOLNSHIRE	
	WY WEST YORKSHIRE	1 days
08	NORTH WEST	
	CH CHESHIRE	1 days
09	NORTH	
	DH DURHAM	1 days
11	SCOTLAND	
	AD ABERDEEN CITY	1 days

Filtering Stage 2 selection:

Parameter: Gross floor area
 Range: 270 to 1000 (units: sqm)

Public Transport Provision:

Selection by: Include all surveys

Date Range: 01/01/05 to 17/10/10

Selected survey days:

Friday	5 days
Saturday	5 days

Selected survey types:

Manual count	10 days
Directional ATC Count	0 days

Selected Locations:

Edge of Town Centre	1
Suburban Area (PPS6 Out of Centre)	3
Edge of Town	4
Neighbourhood Centre (PPS6 Local Centre)	2

Selected Location Sub Categories:

Residential Zone	2
Village	1
No Sub Category	7

Filtering Stage 3 selection:

Use Class:

A3	2 days
A4	8 days

Filtering Stage 3 selection (Cont.):

Population within 1 mile:

5,001 to 10,000	2 days
10,001 to 15,000	4 days
15,001 to 20,000	2 days
20,001 to 25,000	1 days
25,001 to 50,000	1 days

Population within 5 miles:

50,001 to 75,000	2 days
75,001 to 100,000	1 days
100,001 to 125,000	3 days
125,001 to 250,000	1 days
250,001 to 500,000	3 days

Car ownership within 5 miles:

0.6 to 1.0	3 days
1.1 to 1.5	7 days

Travel Plan:

No	10 days
----	---------

LIST OF SITES relevant to selection parameters

1	AD-06-C-01	PUB/RESTAURANT, ABERDEEN WESTBURN ROAD	ABERDEEN CITY
		ABERDEEN Edge of Town Centre No Sub Category Total Gross floor area: 315 sqm Survey date: FRIDAY 13/05/05	Survey Type: MANUAL
2	CH-06-C-01	HARVESTER, CHESTER WHITCHURCH ROAD CHRISTLETON CHESTER Neighbourhood Centre (PPS6 Local Centre) Village Total Gross floor area: 375 sqm Survey date: SATURDAY 18/10/08	CESHIRE Survey Type: MANUAL
3	CW-06-C-01	PUB/RESTAURANT, CAMBORNE FORE STREET POOL CAMBORNE Suburban Area (PPS6 Out of Centre) No Sub Category Total Gross floor area: 285 sqm Survey date: FRIDAY 21/09/07	CORNWALL Survey Type: MANUAL
4	DH-06-C-01	PUB/RESTAURANT, HARTLEPOOL WOOLER ROAD	DURHAM
		HARTLEPOOL Suburban Area (PPS6 Out of Centre) Residential Zone Total Gross floor area: 1000 sqm Survey date: SATURDAY 29/09/07	Survey Type: MANUAL
5	EX-06-C-01	HARVESTER, COLCHESTER LONDON ROAD STANWAY COLCHESTER Edge of Town No Sub Category Total Gross floor area: 450 sqm Survey date: FRIDAY 11/07/08	ESSEX Survey Type: MANUAL
6	HC-06-C-02	BEEFEATER, EASTLEIGH BOURNEMOUTH ROAD AMPFIELD EASTLEIGH Suburban Area (PPS6 Out of Centre) No Sub Category Total Gross floor area: 450 sqm Survey date: FRIDAY 16/11/07	HAMPSHIRE Survey Type: MANUAL
7	SG-06-C-02	PUB/RESTAURANT, NR BRISTOL HIGH STREET WINTERBOURNE NEAR BRISTOL Neighbourhood Centre (PPS6 Local Centre) Residential Zone Total Gross floor area: 270 sqm Survey date: SATURDAY 17/10/09	SOUTH GLOUCESTERSHIRE Survey Type: MANUAL

LIST OF SITES relevant to selection parameters (Cont.)

8	SH-06-C-01	TWO FOR ONE, SHREWSBURY	SHROPSHIRE
	WELSHPOOL ROAD		
	BICTON HEATH		
	SHREWSBURY		
	Edge of Town		
	No Sub Category		
	Total Gross floor area:	892 sqm	
	Survey date: FRIDAY	10/06/05	Survey Type: MANUAL
9	WL-06-C-01	HUNGRY HORSE, CHIPPENHAM	WILTSHIRE
	A4 ROWDEN HILL		
	CHIPPENHAM		
	Edge of Town		
	No Sub Category		
	Total Gross floor area:	375 sqm	
	Survey date: SATURDAY	07/10/06	Survey Type: MANUAL
10	WY-06-C-01	BREWERS FAYRE, HUDDERSFIELD	WEST YORKSHIRE
	BRIDGHOUSE ROAD		
	AINLEY TOP		
	HUDDERSFIELD		
	Edge of Town		
	No Sub Category		
	Total Gross floor area:	904 sqm	
	Survey date: SATURDAY	16/09/06	Survey Type: MANUAL

TRIP RATE for Land Use 06 - HOTEL, FOOD & DRINK/C - PUB/RESTAURANT

MULTI-MODAL TOTAL PEOPLE

Calculation factor: 100 sqm

BOLD print indicates peak (busiest) period

Time Range	ARRIVALS			DEPARTURES			TOTALS		
	No. Days	Ave. GFA	Trip Rate	No. Days	Ave. GFA	Trip Rate	No. Days	Ave. GFA	Trip Rate
00:00 - 01:00	0	0	0.000	0	0	0.000	0	0	0.000
01:00 - 02:00	0	0	0.000	0	0	0.000	0	0	0.000
02:00 - 03:00	0	0	0.000	0	0	0.000	0	0	0.000
03:00 - 04:00	0	0	0.000	0	0	0.000	0	0	0.000
04:00 - 05:00	0	0	0.000	0	0	0.000	0	0	0.000
05:00 - 06:00	0	0	0.000	0	0	0.000	0	0	0.000
06:00 - 07:00	0	0	0.000	0	0	0.000	0	0	0.000
07:00 - 08:00	0	0	0.000	0	0	0.000	0	0	0.000
08:00 - 09:00	0	0	0.000	0	0	0.000	0	0	0.000
09:00 - 10:00	0	0	0.000	0	0	0.000	0	0	0.000
10:00 - 11:00	10	532	1.279	10	532	0.847	10	532	2.126
11:00 - 12:00	10	532	5.493	10	532	2.784	10	532	8.277
12:00 - 13:00	10	532	9.368	10	532	4.270	10	532	13.638
13:00 - 14:00	10	532	6.828	10	532	7.487	10	532	14.315
14:00 - 15:00	10	532	6.057	10	532	7.148	10	532	13.205
15:00 - 16:00	10	532	7.713	10	532	6.396	10	532	14.109
16:00 - 17:00	10	532	6.396	10	532	5.606	10	532	12.002
17:00 - 18:00	10	532	10.835	10	532	7.017	10	532	17.852
18:00 - 19:00	10	532	10.440	10	532	8.672	10	532	19.112
19:00 - 20:00	10	532	14.184	10	532	12.002	10	532	26.186
20:00 - 21:00	10	532	10.327	10	532	9.387	10	532	19.714
21:00 - 22:00	10	532	5.530	10	532	12.716	10	532	18.246
22:00 - 23:00	9	556	2.300	9	556	6.739	9	556	9.039
23:00 - 24:00	9	556	0.680	9	556	6.499	9	556	7.179
Total Rates:			97.430			97.570			195.000

Parameter summary

Trip rate parameter range selected: 270 - 1000 (units: sqm)
Survey date range: 01/01/05 - 17/10/10
Number of weekdays (Monday-Friday): 5
Number of Saturdays: 5
Number of Sundays: 0
Surveys manually removed from selection: 1





