



**KEY**

- Parcel B1 boundary
- Soft landscape proposals  
See plant schedule for details.
- Existing trees/vegetation to be retained
- Grass  
Turf to plot frontages, amenity grass seed mix to less formal areas.
- Attenuation  
Drainage/swale. Refer to Woods Hardwick drawing: HEYF-5-600L.

**PLANT SCHEDULE**

**TREES**

REF	SPECIES	SUPPLY	SIZE(cm)	GIRTH(cm)	CTRS(m)
T3	Quercus robur	EHStd	450/650	18/20	as shown
T6	Corylus colurna	EHStd	425/600	14/16	as shown

All trees to be planted in accordance with the implementation and maintenance guidelines. The tree planting schedule and landscape proposals must be referred to by the Structural Engineer during foundation design. No tree species, size or location should be altered without prior approval from the Landscape Architect.

**SPECIMEN SHRUBS**

REF	SPECIES	SUPPLY	SIZE(cm)	HABIT	CTRS(m)
S1	Phormium 'Jester'	25L	100/125	Triple Crown	as shown
S2	Phormium 'Sundowner'	25L	100/125	Triple Crown	as shown

All feature shrubs to be planted in accordance with the implementation and maintenance guidelines. No feature shrub species, size or location should be altered without prior approval from the Landscape Architect.

**HEDGEROW S - to plots**

ABBR	SPECIES	SUPPLY	SIZE(cm)	HABIT	CTRS(m)
PRULU	Prunus lusitana	10L	80/100	Bushy	0.40

All hedgerow shrubs to be planted in accordance with the implementation and maintenance guidelines. No hedgerow shrub species, size or location should be altered without prior approval from the Landscape Architect. Hedgerow shrubs to be planted in a single row within a 50cm wide bed and mulched in accordance with implementation and maintenance guidelines.

**SHRUBS/HERBACEOUS**

ABBR	SPECIES	SUPPLY	SIZE(cm)	HABIT	CTRS(m)
BRASU	Brachyglottis 'Sunshine'	10L	40/60	Bushy	0.70
CEATHR	Ceanothus thyrsiflorus repens	10L	60/80	Bushy	0.70
CHOAP	Chosyia 'Aztec Pear'	10L	40/60	Bushy	0.70
CHOTES	Chosyia ternata 'Sundance'	10L	40/60	Bushy	0.70
CISSP	Cistus 'Silver Pink'	10L	40/60	Bushy	0.65
EUOFOEG	Euonymus fortunei 'Emerald n' Gok'	10L	30/40	Bushy	0.60
EUOFOEG	Euonymus fortunei 'Emerald n' Gok'	10L	30/40	Bushy	0.60
HEBMAR	Hebe 'Marjorie'	10L	30/40	Bushy	0.70
HEBMW	Hebe 'Mrs Winder'	10L	30/40	Bushy	0.65
HEBPIS	Hebe pingulifolia 'Sutherlandii'	10L	30/40	Bushy	0.65
HEUMIPP	Heuchera micrantha 'Palace Purple'	3L	-	Full Pot	0.40
HEUKLP	Heuchera 'Key Lime Pie'	3L	-	Full Pot	0.40
HYPHI	Hypericum 'Hidcote'	10L	40/60	Bushy	0.70
LAVANHI	Lavandula angustifolia 'Hidcote'	10L	30/40	Bushy	0.60
LONNIBG	Lonicera nitida 'Baggesen's Gold'	10L	40/60	Bushy	0.70
LONNIBG	Lonicera nitida 'May Green'	10L	40/60	Bushy	0.70
MAHAQAP	Mahonia aquifolium 'Apollo'	10L	40/60	Bushy	0.60
PRULACL	Prunus laurocerasus 'Otto Luyken'	10L	60/80	Bushy	0.70
ROSOF	Rosmarinus officinalis	10L	40/60	Bushy	0.70
SKUJARU	Skimmia japonica 'Rubella'	10L	40/60	Bushy	0.60
VIBDA	Viburnum davidii	10L	40/60	Bushy	0.70

**SHRUBS/HERBACEOUS - Mixes**

ABBR	SPECIES	SUPPLY	SIZE(cm)	HABIT	CTRS(m)
AUCJA	Aucuba japonica	5L	40/60	Bushy	0.75
CORALE	Cornus alba 'Elegantissima'	3L	80/100	Branched	0.75
ELAPUMA	Eleaagnus pungens 'Maculata'	5L	40/60	Bushy	0.75
FATJA	Fatsia japonica	5L	60/80	Bushy	0.75
PHOFRRER	Photinia x fraseri 'Red Robin'	5L	60/80	Bushy	0.75
PRULU	Prunus lusitana	5L	40/60	Bushy	0.75

All shrubs to be planted in accordance with the implementation and maintenance guidelines. No shrub species, size or location should be altered without prior approval from the Landscape Architect.

**POPPY SEED MEADOW MIXTURE**

Flanders Poppy Field Annual Seed mix, supplied by www.pictorialmeadowsonline.co.uk or similar approved. Sowing rate: 2g per m2.

Grass seed mixtures to be sourced from certified local provenance seed stock. Ground surface will be cleared of weed growth either removed by hand or through the application of an approved Glyphosate based herbicide (all herbicides should only be handled by certified users and in accordance with the COSHH Regulations 2002). The ground will then be ploughed and raked to produce a medium till. Sowing operation will be carried out in Spring or late Autumn at a rate indicated. The grass will be allowed to establish over the first growing season with a single mowing operation in the Autumn to top out any weed growth. On-going mowing operations will be carried out either once annually in the Spring, or twice annually in Spring and Autumn if grass species become dominant. Grass will not be cut during late Spring and Summer months to allow flower and herb species time to germinate.

**BULBS**

SPECIES	No./m <sup>2</sup>
Crocus Dutch Collection (50% of area)	
'Queen of the Blues'	10
'Golden Yellow'	10
'Jeanne D'Arc'	10
Dwarf Daffodils (50% of area)	
'February Gold'	10
'Jet Fire'	10
'Carnaticulatus'	10

All bulbs to be planted in accordance with the implementation and maintenance guidelines. No bulb species or location should be altered without prior approval from the Landscape Architect. Crocus and Daffodil bulbs to alternate every 2 linear metres.

**NOTES**

- All landscape proposals must be referred to by the Structural Engineer during foundation design.
- Soiling operations to be carried out in accordance with the implementation and maintenance guidelines.
- All planting to be in accordance with the implementation and maintenance guidelines.
- No species, variety, size or position to be amended without the Landscape Architects prior approval.
- Before trees are planted, the Landscape Contractor shall ascertain the location of drains from the site manager, and shall if necessary make minor adjustments to tree positions to ensure that they are planted at least 1.5m from drains. They should however be planted no closer to houses/garages than is shown on the drawing, and if shown located in shrub beds, the shape of the latter should be adjusted if necessary to accommodate the revised tree position.
- All planting must be mulched in accordance with the implementation and maintenance guidelines.
- If planting is required outside the October-March season, bare root shrubs will be replaced by 3L pot grown plants, and trees will be replaced by a containerised equivalent to be approved by the project landscape architect.

Trees are to be placed into the pits and backfilled with topsoil incorporating slow release fertilizer and Tree Planting and Mulching Compost as specified. Firm trees in well and secure with proprietary rubber tree ties and spacers.

Water in all trees and shrubs at the end of each day of planting.  
Spread ornamental pine bark mulch to a depth of 75mm across all new planting areas, ensuring groundcover plants are not buried.

**2.3 Maintenance**  
The landscape contractor shall maintain all areas of new planting for a period of 12 months following practical completion. All stock deemed to be dead, dying or diseased within the defects period shall be replaced by the contractor at his own cost.

The site is to be visited monthly throughout the year to undertake the following operations:  
Weed clearance: All planting areas are to be kept weed free by hand weeding or herbicide treatment.  
Litter clearance: All litter is to be removed from planting beds.  
Watering: Planting areas are to be brought up to field capacity at each visit and each tree is to receive 20 gallons.  
Checking trees: All tree ties and stakes are to be checked and adjusted if too loose, too tight or if chaffing is occurring. Any broken stakes are to be replaced.  
Formative pruning: Any damaged shoots/branches are to be pruned back to healthy wood. Plants are to be pruned in accordance with good horticultural practice to maintain healthy well-shaped specimens.

**3.0 GRASS**

**3.1 Preparation**  
The area to be turfed or seeded shall be sprayed out with a glyphosate herbicide and cultivated to a depth of 100mm removing all weeds, debris and stones over 25mm diameter. The surface shall be raked to smooth flowing contours with a fine tith, incorporating pre-seeding fertiliser at 70 gm/2.

**3.2 Delivery and Storage**  
Turf shall be supplied in accordance with BS3936.  
Turf shall be Medallion as supplied by Rowfam. It shall be close textured and green in colour and be sufficiently fibrous to withstand handling. Turves shall be regular in shape, 300mm wide and of uniform thickness (minimum 25mm). The grass shall be closely mown and shall not exceed 25mm in height.

Turf shall be stacked in piles of up to 1 metre. It shall not be laid in frosty or waterlogged conditions and shall not be stacked in rolls for more than three days.

**3.3 Turf**

Turfing operations shall be in accordance with BS 4428.  
Whole turves shall be laid around the perimeter of the area to be turfed. The central area shall be laid in rows with staggered joints, well butted together, working from planks positioned on turves already laid. The turf shall be watered on completion. Any unevenness shall be made good by lifting the turf and adjusting the levels. Should shrinkage occur, fine topsoil shall be brushed into the joints.

**3.4 Seeding**

Grass seed shall be sown in April during calm weather and not when the ground is frost bound or waterlogged. Seed shall be sown in two equal sowings in transverse directions at 35 gm/2. After sowing the contractor shall lightly rake the seed into intimate contact with the soil.

**3.5 Initial cut**

When newly seeded and turfed areas reach 50mm they should be lightly rolled and cut to a height of 30mm. All arisings shall be removed. Any bare patches shall be made good at this time. Seeded areas shall be cut for a second time when the sward reaches 50mm high.

**IMPLEMENTATION AND MAINTENANCE GUIDELINES**

**1.0 GENERAL**

All plants shall conform to BS 3936 and be in accordance with the National Plant Specification. Supplying nurseries shall be registered under the HTA Nursery Certification Scheme. All plants shall be packed and transported in accordance with the Code of Practice for Plant Handling as produced by CPSE. Planting shall not be carried out when the ground is waterlogged, frostbound or during periods of cold drying winds. All bare root stock shall be root dipped in an approved water-retaining polymer.

If the formation level is compacted it should be ripped through before topsoiling.  
Recommended topsoil depths are 300mm for shrubs and 150mm for grass.

**2.0 ORNAMENTAL SHRUBS AND TREES**

**2.1 Ground Preparation**  
Where necessary treat existing weeds with a glyphosate based herbicide and allow a suitable period as recommended by the manufacturer for this to take effect. A general purpose slow release fertiliser at the rate of 75gm/2 and Tree Planting and Mulching Compost at the rate of 20litres/m2 are to be incorporated into the top 150mm of topsoil during final cultivations. All extraneous matter such as plastic, wood, metal and stones greater than 50mm in any dimension shall be removed from site.

Tree pits to the specified size are to be excavated and the base broken up a further 150mm with the sides well scarified to prevent smothering. Oak trees to site frontage to stabilised with a platypus anchor and guying system, and not staked. All trees up to and including selected standards are to be supported with single 75mm diameter stakes. All rootball, container grown and trees over heavy standard size shall be double staked. Stakes should be driven 500mm into undisturbed ground before planting the tree, taking care to avoid underground services and cables etc.

**2.2 Planting**

Shrubs and hedges are to be set out as shown on the drawing and pit planted into the prepared soil at the specified centres with minimal disturbance to the rootball and well firmed in.



Rev	Description	Date	Team
C.	Visitor parking removed to plot 6.	31/01/14	LM
B.	Visitor parking and general boundary updates.	07/01/14	LM
A.	Amended following client comment.	29/11/13	AP

**Heyford Park, Parcel B1**

**Soft Landscape Proposals**

Client:  
Bovis Homes Central Region

www.pegasuspg.co.uk  
Team HJ/AP  
31/10/2013  
Scale: 1:200 @A1

Bir.4372\_05C

