NOTES:
Based upon the Ordnance Survey map with permission of The Controller of Her Majesty's Stationery Office, © Crown Copyright.
Aspect Landscape Planning Ltd, West Court, Hardwick Business Park, Noral Way, Banbury OX16 2AF. Licence 100045345

Copyright reserved

No Dimensions to be scaled from this drawing.

0m 2m 4m 10m

KEY:

- Site Boundary
- Existing Trees
- Existing Shrubs
- Proposed Trees
- Proposed Hedge
- Proposed Feature Shrub
- Proposed Shrubs
- Proposed Climbers

PLANTING NOTES
All plants to be supplied in accordance with the HTA "National Plant Specification" and from a HTA certified nursery. All plants and trees to be planted in accordance with BS3936. Delivery and handling of all plant material to be in accordance with BS4428/JCLI/CPSE Code of Practice for 'Handling and Establishing Landscape Plants' Parts I, II and III. All excavated areas to be backfilled with either site won topsoil or imported topsoil to be BS3882-General purpose grade. All topsoiled areas to be clear of rocks and rubble larger than 50mm diameter and any other debris that may interfere with the establishment of plants. Tree pits in soft landscape to be excavated to 1mx1mx1m depth prior to topsoiling and all shrub planting areas excavated to 450mm depth. All plants shall be planted in a random fashion avoiding formal replmented lines at densities indicated in the schedule, unless otherwise specified. Unless otherwise specified, all hedgerows shall be planted in a double staggered rows and hedgerow mixes shall be planted in groups of 7, 9 & 13s at densities indicated on the schedule. Ornamental shrub planting mixes shall be planted in groups of 5, 7 & 11s and native shrub planting mixes shall be planted in groups of 9, 13 & 15s. All plants shall be watered in to field capacity immediately after planting and mulched with 50mm depth of medium grade crushed mulch. All trees to be double staked with cross bar and tied, using 1.5m long, 75mm diameter rounded tree stakes 75mm brace, rubber tie and spacer block. Stakes not to extend more than 650mm above ground level. All trees within hardstanding/highways visibility splays to be clear stem to 1.5m high unless otherwise specified. Planting and associated operations shall comply with BS4043, BS4428 and BS5837. Root barriers (ReRoot 1000 or equivalent) to be included adjacent to buildings and services where necessary. Unless otherwise stated planting shall be carried out during the period of 1 Nov to 31 March when the ground is not frozen or water logged. If planting is required outside this period agreement shall be sought and all bare root plants shall be substituted with container grown stock. All Fraxinus species to be UK-grown specimens from healthy, disease-free stock and from reputable suppliers and HTA certified nurseries.

PROTECTION OF EXISTING VEGETATION TO BE RETAINED
Existing trees to be retained shall be protected in accordance with BS5837, from commencement to completion of all works on site.

| REV | DATE | NOTE | Drawn | Chk'd |
|---|---|---|---|---|
| F | 23.09.2014 | Tree to plot 110 frontage removed | BS | KC |
| E | 03.03.2014 | Updated to comments from Local Authority received 20.02.14 | JC | KC |
| D | 27.01.2014 | Updated to latest comments and base | JC | KC |
| C | 27.09.2013 | Updated to latest comments and base | JC | KC |
| B | 16.09.2013 | Updated to latest comments and base | JC | KC |

REVISIONS

aspect landscape planning

TITLE
# Longford Park, Banbury
## Phase 1 - Planting Plan 5 of 5

CLIENT
Barratt Homes, Bovis & Taylor Wimpey Homes

| SCALE | DATE | DRAWN |
|---|---|---|
| 1:250@A1 | JUL 2013 | CW |

| DRAWING NUMBER | REVISION |
|---|---|
| 5205/ ASP 1.5 | F |

Based on Architects drawing C1618 P001 D