| SURVEY CONTROL | | | |
|---|---|---|---|
| STN | EASTINGS | NORTHINGS | LEVEL |
| NJC1 | 458545.533 | 224921.350 | 85.821 |
| NJC1A | 458531.348 | 224911.658 | 85.718 |
| NJC2 | 458462.192 | 224975.578 | 85.671 |
| NJC2A | 458496.374 | 225075.653 | 86.705 |
| NJC3 | 458465.184 | 225075.765 | 86.673 |
| NJC4 | 458455.554 | 225074.741 | 86.673 |
| NJC5 | 458602.540 | 225023.003 | 86.463 |
| NJC7 | 458628.034 | 225101.052 | 87.160 |
| NJC8 | 458490.005 | 224929.416 | 85.503 |
| NJC9 | 458338.764 | 224913.403 | 86.556 |
| NJC10A | 458316.764 | 225044.748 | 86.806 |
| NJC10B | 458316.764 | 225046.748 | 86.806 |
| NJC13 | 458442.348 | 225108.776 | 87.355 |
| NJC14 | 458449.660 | 225100.972 | 87.098 |
| NJC14A | 458460.560 | 225101.877 | 87.143 |
| NJC15 | 458437.151 | 225079.837 | 87.008 |
| NJC16 | 458431.826 | 225049.508 | 86.905 |
| NJC16A | 458431.826 | 225049.508 | 86.905 |
| NJC17 | 458439.960 | 225063.044 | 86.931 |
| NJC18 | 458397.856 | 225004.947 | 86.311 |
| NJC19 | 458317.514 | 225077.452 | 87.055 |
| NJC19A | 458315.930 | 225200.017 | 87.735 |
| NJC20 | 458294.602 | 225077.903 | 87.579 |

Tree Survey Key

Extent of Tree Canopy
Theoretical Root Protection Area (BS5837)
BS 5837 Category (See Below)
Tree Survey Number
Tree Name

BS 5837 Category

(See Tree Survey for further details)

Category U Red Stem Disc
Those in such a condition that any existing value would be lost within 10 years and which should in the current context, be removed for reasons of sound arboricultural management.

Category A Green Stem Disc
Those of high quality and value: -
in such a condition as to be able to make a substantial contribution (a minimum of 40 years is suggested).

Category B Blue Stem Disc
Those of moderate quality and value: -
those in such a condition as to make a significant contribution (a minimum of 20 years is suggested)

Category C Grey Stem Disc
Those of low quality and value: - currently in adequate condition to remain until new planting could be established (a minimum of 10 years is suggested), or young trees with a stem diameter below 150 mm.

South Lodge
Fringford Road
Caversfield Lane

Tree Survey Plan
For
CALA Homes (Midlands) Ltd

Ruskins Group Consultancy
Arboricultural Consultants
01277 849990 info@ruskins.co.uk
www.ruskins.co.uk

| | | | |
|---|---|---|---|
| Scale | 1:500 @ A0 | Drawn by | PW |
| Date | 17/04/2013 | Checked by | * |
| Project No. | 0313-1210 | | |
| Dwg. No. | TSP 1 Rev 1 | | |