

Total :98 No

PLANTING NOTES

All plants to be supplied in accordance with the HTA 'National Plant Specification' and from a HTA certified nursery. All plants and trees to be planted in accordance with BS3936 and BS8545. Delivery and handling of all plant material to be in accordance with BS4428/JCLI/CPSE Code of Practice for 'Handling and Establishing Landscape Plants' Parts, I, I and III and BS8545.

Planting Pit and Trench Preparation
Tree pits in soft landscape to be excavated to 1mx1mx1m depth prior to topsoiling and all shrub planting areas excavated to 450mm depth. All proposed hedge planting trenches to be excavated to 600mm depth. Unless otherwise specified, all tree pits in hard landscape to be Zmx2mx1m, backfilled with compacted Urban Tree Soil.

The preparation of planting nits hed or trenches shall comply with the approaches Patitib

The preparation of planting pits, bed or trenches shall comply with the appropriate British Standards, namely BS4043, BS4428, BS5837 and BS8545.

Excavation of planting pits, beds or trenches shall not take place when the ground is frozen or waterlogged such that damage may occur to the structure of the soil. All excavated areas to be

waterlogged such that damage may occur to the structure of the soil. All excavated areas to be backfilled with either site won topsoil or imported topsoil to be BS382-General purpose grade. All topsoiled areas to be clear of rocks and rubble larger than 50mm diameter and any other debris that may interfere with the establishment of plants. The Contractor shall break up and cultivate at the base of the trenches or planting pits. The sides of the trenches or planting pits shall be loosened with a fork or other similar implement. All stones and the like over 75mm in any dimension, deletenious matter, weeds and weed roots brought to the surface by any cultivation or excavation shall be removed off site. The Contractor shall remove off site the excavated subsoil/fill material when preparing planting pits. The imported topsoil should make up any deficiencies caused by the removal of the subsoil/fill material. Trenches and pits shall have the topsoil and any subsoil/fill material throroughly broken up and mixed prior to backfilling. All trees shall be supplied not bailed, unless otherwise stated. Root balled trees shall be well grown, healthy and with a compact, contained rootball. They shall be nursery grown and have been regularly watered. Prior to planting, all plant material shall be stored and sorted at in accordance with best practice.

Planting

Planting
All plants shall be planted in a random fashion avoiding formal regimented lines at densities All plants shall be planted in a random fashion avoiding formal regimented lines at densities indicated in the schedule, unless otherwise specified. Unless otherwise specified, all hedgerows shall be planted in a double staggered rows and hedgerow mixes shall be planted in groups of 7, 9 & 15 at densities indicated on the schedule. Omamental shrub planting mixes shall be planted in groups of 9, 13 & 15s. The selection, procurement, handling, storage and planting operations of all proposed trees shall be in accordance with BS8452014 - Trees: from nursery to independence in the landscape, recommendations. Planting and associated operations shall comply with BS4043, BS4428, BS5837 and BS8545. Unless otherwise stated planting shall be carried out during the period of 1 Nov to 31 March when the ground is not frozen or water logged. If planting is required outside this period agreement shall be sought and all bare root plants shall be substituted with container grown stock.

Watering

Watering
All plants shall be watered in to field capacity immediately after planting and mulched with 50mm

An plant-distance or whether and the complete interface of the planting area induced with objects of depth of medium grade crushed mulch. The Contractor shall water the trees, shrubs and hedges once planted so that the entire tree pir or planted area is moistened to field capacity, i.e. 'the amount of water retained by previously saturated soil once full drainage has ceased'. Watering to amount of water retained by previously saturated soil once full drainage has ceased". Watering to field capacity shall continue frequently and on a regular basis as considered necessary by the landscape contractor and as necessary to ensure the successful establishment and continued thriving of all planting. Additional watering shall be undertaken during summer months and/or periods of drought. Post planting management and maintenance specifically for new tree planting shall include ongoing imgation and formative purining as outlined in BSS445. The period over which regular imgation required for transplanted trees is likely to be at least two full growing seasons to ensure successful establishment. As the root system develops the frequency of imgation can be reduced.

Staking


imgation can be reduced.

Staking

All trees within soft landscape areas to be double staked with cross bar and tied, using 1.5m long,
75mm diameter rounded tree stakes 75mm brace, rubber lie and spacer block. Stakes not to
extend more than 650mm above ground level. All trees within hardstanding/highways visibility
splays to be clear stem to 1.5m high unless otherwise specified. Trees within hardstanding /
specific pits to be underground guyed unless otherwise specified.

Based upon the Ordnance Survey map with permission of The Controller of Her Majesty's Stationery Office, © Crown Copyright.

Aspect Landscape Planning Ltd, West Court, Hardwick Business Park, Noral Way, Banbury OX16 2AI Licence 100046346



Proposed Trees



Proposed Hedge



Proposed Shrubs





Bankside, Longford Park Community Park NEAP

Planting Plan

Taylor Wimpey, Bovis Homes,

Barrall Homes			
SCALE	DATE	DRAWN	CHK'D
1:200 @ A3	JULY 2016	BS	
DRAWING NUMBER		REVISION	
5205/ CP / ASP4.7		F	