

Staffordshire Blue Pavers Specification Sheet



Performance Standard: BS EN 1344:2002

Ketley Staffordshire Blue Pavers are produced at our works located in the heart of the Black Country. They have been made from our own Etruria Marl since Victorian times. Their unrivalled physical properties include their strength, durability and permanence of colour.

Work Size mm	Pattern	Pack Weight	No per pallet	Units/m ²	
				Rigid with 10mm joint	Flexible butt jointed
215x102.5x50	Square Edged	1300kg	500	40	46
215x102.5x65	Square Edged	1320kg	400	40	46
200x100x50	Square Edged	1150kg	500	43	50
200x100x65	Square Edged	1200kg	400	43	50
200x100x50	Chamfered	1150kg	500	43	50
200x100x65	Chamfered	1200kg	400	43	50

Colour	Staffordshire Blue
Raw Material	Etruria Marl Clay
Manufacture	Extruded, Wirecut and fired above 1130°C
Bulk Density	2,300kg/m ³
Texture	Dragfaced
Size, Tolerance	BS EN 1344: 2002
Size Range	R1
Mean Transverse Breaking Load	T4
Unpolished Slip/Skid Resistance	U3
Abrasion Resistance	A3
Freeze/Thaw Resistance	FP100

Ketley Brick Company Ltd
Dreadnought Works, Pensnett, Brierley Hill, West Midlands, DY5 4TH, UK.
Tel: 01384 78361 Fax: 01384 74553 Email: info@ketley-brick.co.uk Web: www.ketley-brick.co.uk
Ketley Brick Company Ltd. is a company registered in England and Wales with Reg number 699040.