



NOTES:
 Based upon the Ordnance Survey map with permission of The Controller of Her Majesty's Stationery Office, © Crown Copyright.
 Aspect Landscape Planning Ltd, West Court, Hardwick Business Park, North Way, Banbury OX16 2AF.
 License 100040465
 Copyright reserved
 No Dimensions to be scaled from this drawing.

- KEY:
- Site Boundary
 - Existing Trees
 - Existing Shrubs
 - Proposed Trees
 - Proposed Hedge
 - Proposed Feature Shrub
 - Proposed Shrubs
 - Proposed Climbers

PLANTING NOTES:
 All plants to be supplied in accordance with the HTA 'National Plant Specification' and from a HTA certified nursery. All plants and trees to be planted in accordance with BS5306. Delivery and handling of all plant material to be in accordance with BS4422/JULIAC/ISE Code of Practice for Handling and Establishing Landscape Plants Parts 1 & 2. All excavated areas to be backfilled with either the won topsoil or imported topsoil to be BS3882-General purpose grade. All topsoiled areas to be clear of rocks and rubble larger than 50mm diameter and any other debris that may interfere with the establishment of plants. Tree pits in soft landscape to be excavated to 100mm depth below topsoiling and all shrub planting areas excavated to 450mm depth. All plants shall be planted in a random fashion avoiding formal regimented lines at densities indicated in the schedule, unless otherwise specified. Unless otherwise specified, all hedgerows shall be planted in a double staggered rows and hedgerow mixes shall be planted in groups of 7, 9 & 13s at densities indicated on the schedule. Ornamental shrub planting mixes shall be planted in groups of 9, 13 & 15s and native shrub planting mixes shall be planted in groups of 9, 13 & 15s. All plants shall be watered in to 80% capacity immediately after planting and mulched with 50mm depth of medium grade crushed mulch. All trees to be double staked with cross bar and fixed using 1.5m long, 30mm diameter rounded tree stakes 75mm brace, rubber tie and spacer block. Stakes not to extend more than 600mm above ground level. All trees within hardstanding/highways visibility triangles to be clear stem to 1.5m high unless otherwise specified. Planting and associated operations shall comply with BS4543, BS4428 and BS5637. Root barriers (RiRoot 1000 or equivalent) to be included adjacent to buildings and services where necessary. Unless otherwise stated planting shall be carried out during the period of 1 Nov to 31 March when the ground is not frozen or water logged. If planting is required outside this period agreement shall be sought and all bare root plants shall be substituted with container grown stock. All Fuchsia species to be UK-grown specimens from healthy, disease-free stock and from reputable suppliers and HTA certified nurseries.

PROTECTION OF EXISTING VEGETATION TO BE RETAINED
 Existing trees to be retained shall be protected in accordance with BS5637, from commencement to completion of all works on site.

REV	DATE	NOTE	BY	CHKD
F	23.09.2014	Tree to plot 110 frontage removed	BS	KC
F	03.03.2014	Updated to comments from Local Authority received 20.02.14	JC	KC
D	27.01.2014	Updated to latest comments and base	JC	KC
C	27.09.2013	Updated to latest comments and base	JC	KC
B	16.09.2013	Updated to latest comments and base	JC	KC
REV	DATE	NOTE	BY	CHKD
REVISIONS				

aspect landscape planning

TITLE
**Longford Park, Banbury
 Phase 1 - Planting Plan 5 of 5**

CLIENT
Barratt Homes, Bovis & Taylor Wimpey Homes

SCALE	DATE	DRAWN
1:250@A1	JUL 2013	CW
DRAWING NUMBER	REVISION	
5205/ ASP 1.5	F	

Based on Architects drawing C1618 P001 D