



NB. All kerb foundations and backing to be shuttered and constructed in ST4 concrete, poker vibrated in widths of 375mm x 150mm ST4 min. 50mm slump concrete foundations and haunch.

NB. Use 255BN when adjacent to gully.



NOTE:
PVCu PLASTIC GULLY POTS (BBA APPROVED) MAYBE UTILISED WITH THE ENGINEERS WRITTEN CONSENT. A 150mm BED AND SURROUND OF ST4 CONCRETE MUST BE UTILISED. CARE MUST BE TAKEN TO PREVENT THE POT FROM DISTORTING OR FLOATING WHEN THE CONCRETE BED AND SURROUND IS PLACED AND COMPACTED.

SPECIFICALLY DESIGNED IRONWORK WHICH ALLOWS BLOCKWORK TO BE LAID DIRECTLY UP TO THE FRAME OF THE GULLY TO BE USED IN BLOCK PAVED CARRIAGEWAYS.

AECOM