



FOR CONTINUATION REFER LLA DWG 1619 A3 04

FOR CONTINUATION REFER LLA DWG 1619 A3 02

Planting schedule

Number	Plant Name	Height	Girth	Specification
22 No.	Amelanchier x grandiflora 'Robin Hill'	450-650cm	18-20cm	Extra Heavy Standard: 3x: RB: Clear Stem min. 200cm
19 No.	Betula pendula 'Fastigiata'	400-450cm	16-18cm	Extra Heavy Standard: 3x: RB: Clear Stem min. 200cm
13 No.	Pyrus calleryana 'Chanticleer'	400-450cm	16-18cm	Extra Heavy Standard: 3x: RB: Clear Stem min. 200cm
5 No.	Quercus robur	500-550cm	20-25cm	Semi-Mature: 3x: RB: Clear Stem min. 200cm
20 No.	Acer campestre 'Streetwise'	500-550cm	20-25cm	Semi-Mature: 3x: RB: Clear Stem min. 200cm
1 No.	Quercus robur	650-600cm	25-30cm	Semi-Mature: 4x: RB: Clear Stem min. 200cm
12 No.	Malus trilobata	450-500cm	18-20cm	Extra Heavy Standard: 3x: RB: Clear Stem min. 200cm
2 No.	Malus sylvestris	400-450cm	16-18cm	Extra Heavy Standard: 3x: RB: Clear Stem min. 200cm
1 No.	Tilia cordata 'Greenspire'	600-550cm	20-25cm	Semi-Mature: 3x: RB: Clear Stem min. 200cm
31 No.	Pyrus calleryana 'Chanticleer'	600-550cm	20-25cm	Semi-Mature: 3x: RB: Clear Stem min. 200cm

Number	Plant Name	Height	Container	Specification	Density
842 No.	Buxus sempervirens	30-40cm	5L	Bushy: 8 brks: C	5/m
1232 No.	Carpinus betulus	100-125cm	5L	Branched: 5 brks: C	5/m
3781 No.	Escallonia 'Donard Seedling'	40-60cm	5L	Bushy: 5 brks: C	5/m

Number	Plant Name	Height	Container	Specification	Density
42 No.	Aucuba japonica 'Crotonifolia'	40-60cm	5L	Bushy: 3 brks: C	2/m ²
9 No.	Ceanothus 'Blue Mound'	30-40cm	5L	Bushy: 6 brks: C	2/m ²
58 No.	Choisya 'Aztec Pearl'	30-40cm	5L	Bushy: 6 brks: C	2/m ²
146 No.	Cornus alba 'Spaethii'	60-80cm	5L	Branched: 4 brks: C	2/m ²
25 No.	Euonymus fortunei 'Emerald 'n' Gold'	25-30cm	5-7.5L	Bushy: 9 brks: C	2/m ²
16 No.	Euonymus fortunei 'Emerald Gaiety'	25-30cm	5-7.5L	Bushy: 9 brks: C	2/m ²
163 No.	Euonymus fortunei 'Silver Queen'	20-30cm	5L	Bushy: 7 brks: C	3/m ²
15 No.	Hebe 'Autumn Glory'	30-40cm	5L	Bushy: 7 brks: C	2/m ²
60 No.	Hebe 'Red Edge'	30-40cm	5L	Bushy: 7 brks: C	2/m ²
82 No.	Hebe rakaiensis	5-7.5L	5L	Bushy: 7 brks: C	2/m ²
255 No.	Hypericum moserianum 'Tricolor'	5-7.5L	5L	Bushy: 7 brks: C	3/m ²
115 No.	Lavandula angustifolia 'Hidcote'	20-30cm	5L	Bushy: 7 brks: C	2/m ²
233 No.	Lavandula angustifolia 'Hidcote'	20-30cm	5L	Bushy: 7 brks: C	3/m ²
11 No.	Magnolia stellata	100-125cm	25L	Branched: 5 brks: C	Counted
36 No.	Nandina domestica 'Harbor Dwarf'	5L	5L	Bushy: 6 brks: C	3/m ²
47 No.	Pachysandra terminalis 'Green Carpet'	5L	5L	Several Shoots: 11 brks: C	3/m ²
50 No.	Phlox fruticosa	30-40cm	5L	Branched: 5 brks: C	2/m ²
93 No.	Rosmarinus officinalis 'Severn Sea'	40-60cm	5L	Bushy: 5 brks: C	2/m ²
127 No.	Ruscus aculeatus	30-40cm	3L	Several Shoots: 3 brks: C	4/m ²
238 No.	Santolina chamaecyparissus	30-40cm	5L	Bushy: 8 brks: C	3/m ²
57 No.	Santolina chamaecyparissus	30-40cm	5L	Bushy: 8 brks: C	2/m ²
233 No.	Sarcococca confusa	25-30cm	5-7.5L	Bushy: 9 brks: C	3/m ²
116 No.	Skimmia japonica 'Kew White'	30-40cm	5L	Bushy: 4 brks: C	3/m ²
203 No.	Viburnum davidii	30-40cm	5-7.5L	Bushy: 4 brks: C	2/m ²
147 No.	Vinca minor	5-7.5L	5L	Several Shoots: 5 brks: C	2/m ²

Number	Plant Name	Container	Specification	Density
89 No.	Ajuga reptans 'Atropurpurea'	2L	Full Pot: C	6/m ²
24 No.	Anemone hepensis 'Prinz Heinrich'	3L	Full Pot: C	4/m ²
83 No.	Bergenia 'Bressingham Ruby'	3L	Full Pot: C	5/m ²
100 No.	Bergenia 'Silberlicht'	3L	Full Pot: C	5/m ²
62 No.	Echinacea purpurea 'White Swan'	3L	Full Pot: C	4/m ²
9 No.	Geranium macrorrhizum 'Album'	3L	Full Pot: C	4/m ²
58 No.	Helium 'Moerheim Beauty'	3L	Full Pot: C	3/m ²
48 No.	Helium hoopesii 'The Bishop'	3L	Full Pot: C	4/m ²
42 No.	Heliborus niger	3L	Full Pot: C	4/m ²
26 No.	Hemerocallis 'Crimson Pirate'	3L	Full Pot: C	3/m ²
15 No.	Hemerocallis 'Golden Chimes'	3L	Full Pot: C	3/m ²
12 No.	Hemerocallis 'Stafford'	3L	Full Pot: C	4/m ²
57 No.	Heuchera 'Chocolate Ruffles'	3L	Full Pot: C	4/m ²
68 No.	Heuchera 'Green Ivory'	3L	Full Pot: C	4/m ²
47 No.	Heuchera 'Key Lime Pie'	3L	Full Pot: C	4/m ²
10 No.	Heuchera micrantha 'Palace Purple'	3L	Full Pot: C	4/m ²
189 No.	Iris 'Black Swan'	3L	Full Pot: C	3/m ²
85 No.	Rudbeckia fulgida sultivantii 'Goldsturm'	3L	Full Pot: C	3/m ²
28 No.	Rudbeckia fulgida sultivantii 'Goldsturm'	3L	Full Pot: C	4/m ²
56 No.	Salvia officinalis 'Tricolor'	3L	Full Pot: C	4/m ²
100 No.	Stachys byzantina 'Silver Carpet'	3L	Full Pot: C	5/m ²
51 No.	Thymus x citriodorus 'Silver Queen'	3L	Full Pot: C	4/m ²

Number	Plant Name	Height	Container	Specification	Density
22 No.	Cupressocyparissus leylandii	250-300cm		Single Leader: Furnished to base: 4x: RB	Counted

Number	Plant Name	Specification	Density
135 No.	Allium 'Purple Sensation'	Full Pot: C	3/m ²
2152 No.	Narcissus pseudonarcissus	Grade 5/6	10/m ²

Number	Plant Name	Container	Specification	Density
64 No.	Dryopteris filix-mas	3L	Full Pot: C	2/m ²

Number	Plant Name	Height	Container	Specification	Density
7 No.	Laurus nobilis	150-175cm	30-35L	Ball on Stem: Topiary Half Standard: Ball diameter 50-60cm: C: Clear Stem 90-120cm: Neatly Clipped	Counted

Number	Plant Name	Height	Container	Specification	Density
453 No.	Carex buchananii	40-60cm	5L	Full Pot: C	5/m ²

Number	Species	Mix Species Contribution	Specification	Density
116 No.	Ilex aquifolium	10%	Leader with Laterals: C	3/m ²
171 No.	Cornus alba	15%	Branched: 3 brks: C	3/m ²
228 No.	Acer campestre	20%	1+1: Transplant - seed raised: C	3/m ²
228 No.	Ligustrum vulgare	20%	Branched: 4 brks: C	3/m ²
397 No.	Crataegus monogyna	35%	1+1: Transplant - seed raised: Branched: 4 brks: C	3/m ²

Number	Species	Specification	Density	Mix Species Contribution
21 No.	Phragmites australis	2/m ²	50%	
21 No.	Typha latifolia	2/m ²	50%	

LEGEND

- Existing Vegetation
- Proposed root barrier (Green Blue Urban Refect 2000 or similar approved)
- Proposed Trees in hard landscape
- Proposed Trees in soft landscape
- Proposed Specimens
- Hedging
- Shrub/herbaceous planting
- Bulbous planting
- Grass: Wildflower
- Grass:Mown

GENERAL NOTES

This drawing is to be used for planting information only, and is subject to alteration through changes to the site layout or until approved by the area designer.

Any species substitution by the contractor must be verified with the Landscape Architect through the Job Architect.

This layout must be checked in accordance with NHC Standards 2013 (Chapter 4.2 - Building Near Trees & Chapter 9.2 - Drives, Paths and Landscaping) by the Regional Engineer prior to implementation.

Excavations: Contractors must ensure that they have full information relating to service and drainage positions before undertaking any excavations.

Root barriers to be used in association with tree planting adjacent to kerbs / services / footpaths etc. (Greenleaf Refroot products or similar application in accordance with manufacturer's instructions).

NOTES: Please note all planting mixes should be planted as follows: Shrubs/Grasses to be planted in groups of 3-5 with herbaceous to be planted randomly throughout mix area.

REV

Rev	Date	Description
A	03.08.15	Initial layout / planting schedule
B	07.08.15	New layout / planting amendments
C	20.08.15	Updated plant schedule

TITLE

1619 A3 01 C

LIZ LAKE ASSOCIATES