



Key

- Glazing
- SG Safety glazing
- Obs Obscured glazing
- Hinged opening (Points to hinge slide)
- Sliding door unit
- Tricke vent Min 3050mm2 area

NOTE -
U value windows 1.4 w/m2K
U value windows 1.8 w/m2K
Window handles to incorporate ventilation latch
Bedroom windows to have min 450x450mm fire escape opening, max 1100mm above FFL.
All glazed doors and windows below 800mm, above FFL and exposed areas to be safety glazed.
FOR DOOR HANDINGS REFER TO PLAN DRAWINGS

P5	Type H amended	07/04/17
P4	Type H amended	07/04/17
P3	Type H amended	06/04/17
P2	For conditions	05/04/17
Rev	Description	Date

Partner	Drawn	Date
BWD	NCF	April 2017

Project
The Lion, Wendlebury New Accommodation
Title
Door & Window Schedule

Drawing Reference 16030		
Drawing No 061	Revision P4	Status S0
Scale 1:50 @ A3		

OXFORDARCHITECTS
Bagley Croft, Hinksey Hill, Oxford, OX1 5BS
T. 01865 329100 F. 01865 326822 oxford-architects.com
The Workshop, 254 Southmead Road, Bristol, BS10 5EN
T. 0117 9581500 F. 0117 9581501 oxford-architects.com

External Doors/Windows