

Subject to Statutory Approvals.

All dimensions to be checked on site prior to commencement of work.



**Key**

- Vehicular areas and security yards in concrete
- Car parks in permeable concrete block pavings
- Block paving footpaths
- Reinforced gravel footpaths
- Breendon gravel footpaths
- Soft landscape
- Weldmesh division service yard fence - 2m high (1.8m to pumping station)
- Timber post and rail fence
- Site Boundary
- Retaining Wall
- Painted steel protection bollards (150mm diameter, 1.5m/1.3m high)
- Polyurethane (PU) bollard (160mm diameter, 1.2m high)
- Thermoplastic white line demarcation

A	Retaining structure to unit D amended. Weldmesh fencing to units A and D yards amended and fire access gates added. Sliding gates to units A and D replaced with swing gates. Bollard locations within yards have been altered to suit use. Unit B footprint altered, area remains the same. Fire escape paths to the rear of units G-F changed from concrete block to self-binding Breendon gravel. Low timber retaining walls to substation and unit D yard corner. External condensers added to units A & D. Post and rail fence added to the swale perimeter. Weldmesh fence added to the pumping station to create secure compound.	RC	10.04.18
---	--	----	----------

Rev	Description	Chkd	Date
-----	-------------	------	------

Peer House  
8 -14 Verulam Street  
London WC1X 8LZ  
tel +44(0)20 7400 2120  
enquiries@cornisharchitects.com  
www.cornisharchitects.com

cornisharchitects

Project  
**LINK 9 - SKIMMINGDISH LANE  
BICESTER  
PLOT 2**

Drwg Title  
**External Finishes - Site Plan  
Zone 02**

Status  
**PLANNING**

Scale  
1:500 @ A1

Date  
09/08/2017

Drwg No  
17007 / TP / 2016

Rev  
A