SPECIFICATION NOTES

SPECIFICATION NOTES - REFER ALSO TO THE MEASURED WORKS SCHEDULE.

A) Setting out

1. Planting shall be set out exactly as shown on the drawing, and measured from existing fixed points. Curved beds shall be set out using radii scribed on the ground using two pointed stakes and a line between, or with site marker paint. The junction between convex and concave curves shall be cut to form a smooth and even flowing line. Check that all setting out conforms to the plan before cultivation and planting works are carried out. Failure to do so may result in rejection of the work by the landscape architect and may require amendment at the contractor's expense.

2. All planting beds shall be a minimum of 1 metre wide, except where there is insufficient space, due to the constraints of walls and path edgings and their foundations. With narrow beds between walls/ fences and path edgings, ensure that the bed has space free from concrete footings before planting. If the bed is sealed with concrete, then the landscape contractor shall contact the site manager or landscape architect to determine if footings are excessive and can be reduced or else, the bed can be paved. The width of all beds will be checked by the inspecting landscape architect and where the width is not as drawn, the contractor shall re-cultivate them to the specified width at his own expense.

B) Ground preparation

1. Pre-planting herbicide application: - Apply by suitable spraying aparatus, an approved translocated systemic herbicide to the manufacturers instructions and to 1997 Control of Pesticides Regulations and 2003 COSHH regulations on all beds, except those which are both weed free and are to receive agrotextile sheet mulch. Spray immediately if any weeds are present. If none are showing, but there may be a delay before planting, or the area is to be seeded, spray after one month following cultivation, to allow dormant seed to germinate. All spraying shall be carried out by skilled and qualified operatives, using protective clothing, in suitable weather (no wind) and any damage caused by spray drift, from incorrect usage or spillage, shall be rectified at the contractor's own cost. Repeat as necessary to ensure complete kill and rake off all dead material from site.

2. Carry out the following works to the existing topsoil on site to ensure it Conforms to BS 3882:2007, being free from rocks larger than 50m diameter, concrete, all roots, wire, brick, and have less than 20% clay. Allow for pre-application of herbicide as above. Fertilise with 100g per meter square of Fisons 'Neutrocote' slow release fertilizer, in accordance with the manufacturers instructions. For beds less than 5 meters in width, fork over thoroughly or machine rotovate soil to a depth of 300mm, ensuring that the subgrade and topsoil are completely broken up and free draining, relieving any compaction. For beds greater than 5 metres in width, break up the subgrade and topsoil using a tractor mounted subsoiler or ripper at 500mm centres to a depth of 500mm,except where there are services, or within 10 meters of tree stems or 3 meters of existing hedges. Do not rip areas where roots greater than 10mm diameter are encountered.

3. Determine before submitting a tender, the extent of support from the site manager with ground preparation: ensure soil of all planting beds is graded to a level 65mm below adjacent grass or paved surfaces, (90mm below where agro-textile set mulch is not specified), within 400-600mm of edges to ensure bark or wood chip mulches are retained. Where grass is proposed, then the soil level shall be flush (maximum 10mm below - but never proud) of adjacent paved surfaces, to receive rain water run off. The landscape contractor is responsible for ensuring that the final product conforms to the specification even where the developer and/or main contractor have failed to supply and spread topsoil to the recessed level. The landscape contractor shall allow for adjustment of levels, as specified above, including for re-grading subsoil and topsoil. Where beds are sloping, ensure that topsoil is graded to the specified levels below pavement & grass surfaces within 400mm of the edges of the bed. This is to allow for sheet mulch and bark or wood chip mulch so that mulch does not spill out on to pavements and also to allow surface water to drain from paths on to planted areas.

4. For sloping areas to be turfed adjacent to paved areas, topsoil levels shall be graded flush with the Finished pavement level (or up to 10mm below), to allow surface water to drain from pavements to soft areas. Soil of grass areas should therefore never be proud of paved areas. Soil levels more than 10 mm below pavement edges will cause mower damage on cutting.

5. Imported topsoil (where specified and sanctioned by the employer) for making up ground, shall conform to BS 3882: 2007, and be free from rocks (over 50mm diameter), concrete, roots, wire and brick, and have less than greater than 20% clay. Such soil shall be cultivated as set out above. Representative samples shall first be approved by the landscape architect before being supplied to site. No imported soil shall be supplied to site without a written instruction.

C) Planting

1. All planting must be carried out in accordance to the specification and schedule of quantities accompanying these drawings. Refer to the specification for the preparation of existing topsoil and required depths for planting, turfing, and standard trees, and also for maintenance requirements.

2. No substitutions will be accepted without the prior agreement of the inspecting landscape architect. The contractor shall replace at once at his own cost any stock size, species or variety of plant which has not been specified on the planting plan and schedule, unless prior agreement to a substitution by the landscape architect has been received. All plants shall be true to size specified in the schedule of plants and associated notes, (3L pots are 19cm diameter and 15cm deep). All shrubs, (other than ground cover), shall be 400-600mm height and spread, or otherwise specified for the pot size by the HTA National Plant Specification and be bushy, healthy, disease free stock, not pot bound, leggy or spindly. There should be a minimum of 5 breaks per shrub. This specification is the minimum standard required and any stock falling below this standard, in the sole opinion of the inspecting landscape architect, shall be lifted and replaced at the contractor's expense.

3. All shrubs, herbaceous plants, whips and transplants shall be watered in on planting with 20 litres per square metre. Trees shall be watered in with 25 litres per tree position. Water thereafter during the contract period at weekly intervals with 30 litres of water.

4. Proposed large feathered or standard trees to be true to the species, variety and size as specified on the planting plan, to include 1.6m chestnut stake (600mm above ground and 1000mm below ground) and 1No. tie with spacing device positioned 25mm maximum from the top of the post.

5. Turf to be of cultivated grade such as Rowlawn 'Medalion', or other of similar quality and source, approved by the landscape architect. The contractor shall replace at once any turf rejected by the landscape architect at his own cost.

6. Self clinging climbing shrubs or wall shrubs, with 'S' drawn after the climber name, shall be trained to the wall/fence with heavy duty, plastic coated garden wire. Training wires shall be attached vertically to the wall/fence by means of 125mm long stainless steel eye screw fittings. Position 1No. at 250mm from ground, and 1No. 250mm from top of the wall/fence, and string the wire tightly between the Fixings. Train the climber to the wire with plastic coated garden wire tags.

7. Twining varieties of climber, with 'T' drawn after the climber's name (in specially prepared pits or general shrub beds) shall be trained to walls/ fences by mounting ready-made trellis panels 1.8 x 1.8m generally (but 1.8 x 0.6m for corners or where space is restricted). Include for adapting any panels for locations where walls or Fences are lower than 1.8m. Fix trellis panels to the walls/ fences using non rusting screws 125mm long (to be approved), incorporating 50mm cube wood spacing blocks to ensure that the panel is mounted sufficiently far from the wall/ fence to allow twining of stems. Ensure that all timber is pressure impregnated with a non phyto-toxic preservative and then painted with a dark brown non phyto-toxix preservative wood stain such as Sadolin 'Classic' walnut or similar and approved. Ensure that the trellis is not in contact with the ground. Train the climbing shrub to the trellis with plastic coated garden wire tags.

8. Climbers specified outside proposed shrub beds shall have specially prepared climber pits. Climber pits shall be 400mm x 400mm and 600mm deep (minimum size), and be backfilled with topsoil (from site - unless otherwise agreed). Ensure the base of the pit is thoroughly broken up and free draining before back filling with topsoil.Ensure no damage to foundations and services, and make good all structures and surfaces disturbed. Fertilise with 50g of Fisons 'Neutrocote' slow release Fertilizer. Water with 15 litres of water per climber pit.

D) Mulch

1. When specified by the additional specification notes on this plan, supply and spread agrotextile 'Weedstop Fabric' sheet mulch over planting beds, previously, cultivated, graded and Fertilized topsoil before planting, and peg down with Weedstop pegs at a minimum of 500mm centres, (300mm at edges) and beds less than 1m wide. Pegging this densely is essential to prevent flaps of material becoming exposed. Refer to the specification for 'Weedstop Fabric' sheet mulch on plan.

2. Following planting supply and spread evenly Melcourt Industries 'Rustic Bionulch' to a depth of 50mm, (75mm if no sheet mulch specified),over all planted areas. Finished mulch levels shall be no higher than 15mm below pavement or grass levels to avoid any spillage onto pavements or lawns. N.B. no substitution of mulch type will be acceptable. It is essential to have a no-fines, large particled, brown wood chip to reduce weed growth, reduce wind blow and prevent rapid break down.

E) BS codes

1. All workmanship and materials shall conform to the following codes:- A) General landscape operations (excluding hard surfaces) - BS 4428: 1989. B) Trees in relation to construction- BS 5837: 2012 and BS 6549:1990. BS 3998:2012 (recommendations for tree works) unless otherwise specified. Arboricultural Association - Standard Conditions of Contract and BS 8545: 2014 From nursery to independence in the landscape. Specifications of Tree Works 1996. C) Nursery stock in accordance with latest horticultural trade association nursery stock specification entitled 'National Plant Specification 2001 '. Plants shall conform to: -BS 3936-1 : 1992 Nursery Stock - Specification for trees and shrubs. -BS 3936-2 : 1990 Nursery Stock- Specification for roses + AMD 6628. -BS 3936-4 : 1984 Nursery stock- Specification for forest trees. -BS 3936-5 : 1985 Nursery stock- Specification for poplars and willows. -BS 3936-9 : 1998 Nursery stock- Specification forbulbs,corms and tubers. -BS 3936-10 : 1990 Nursery stock- Specification for ground cover shrubs. -EPSE-Committee for Plant Establishment, Handling and establishing landscape plants 1996, Part 3, paragraphs 6.2 to 6.6. D) Glossary for Landscape Works BS 3975 Pt 4: 1966. E) Turf - BS 3969:1998- recommendations for turf for general purposes. F) Seeding - EEC Regulations 1974. Use blue labelled certified varieties to EC purity and germination regulations . When requested, submit an official seed Testing Station Certificate of germination,purity and composition. G) Topsoil - BS 3882: 2015 H) Pesticides- Control of Pesticides Regulations 1997;The Health and Safety at Work Act 1974; the COSHH Regulation 2003, the product COSHH sheet Water Supply (Water Quality) Regulations amended 1991; Control of Pollution Act 1974; Hedgerow ACT 1997; Wildlife and Countryside Act 1981.

GENERAL NOTES FOR THE DEVELOPER.

A) Tree protection

1. Any existing trees to be retained, are the responsibility of the main contractor on site who shall take all necessary protective measures set out in BS 5837:2012 to ensure no damage to stems or roots, to prevent compaction from vehicles or storage of materials, contamination of soil from spilages, scorching from fires and instability or stress from changes of soil level. The landscape contractor is however responsible for ensuring that neither plant, materials or labour are cause of any damage to existing trees, and like the employer, the landscape contractor shall replace at once any tree damaged on site, supplying and planting a tree of the same species and size, at his own cost.

B) Ground work

1. Soil levels: soil levels for shrub beds and grass areas should have any compacted subgrade thoroughly broken up by machine before instructing the ground worker to spread topsoil or the landscape contractor to commence work or the beds will become waterlogged in wet weather and the plants and turf will die.

2. Top soil spread from on site should be to the following minimum depths: - Shrub beds: 350mm. Grass areas 150mm. allow for excavation of 415mm of the subgrade for shrub beds to leave beds 65mm below finished pavement or grass areas in order to receive sheet and bark mulch, (90mm below where sheet mulch is not to be used). Tree pits will be dug by the landscape contractor. Top soil shall be spread for grass areas flush with any areas of paving and after settlement, the soil level should be no greater than 10mm below paved areas to allow for turf. For areas to be grass seeded, the soil level shall be flush with any finished paved surfaces after settlement (or to a maximum of 5mm below) to allow for rain water to drain onto soft surfaces. Settlement shall be no greater than the tolerances given or problems will be encountered with mowing (the blades in danger of touching concrete edgings) or where soil is proud of pavements, then drainage problems will be encountered.

3. Existing topsoil and imported soil shall conform to BS 3882:2007, and be free from compaction, rocks/bricks greater than 50mm diameter, concrete, wire, roots, debris, oil, cement and builders rubble. Soil shall have a clay content of less than 20%.

C) Hardworks

1. Hard works, unless otherwise agreed, shall be carried out by the developer or main contractor, and all materials and workmanship shall be in accordance with the construction details and the layout plan.

2. All paths and edgings shall be set out properly to lines and radii, with all curves scribed on the ground using pointed pegs and string or site marker paint, achieving flowing natural arcs. Setting out shall be agreed with the landscape contractor and subsequently the landscape architect.

3. Hard surfaces shall be constructed after suitable base courses have been laid, taking full account of local site conditions, soft spots and substrate. The indicative depths of base courses are minimum depths assuming suitable substrate conditions.

4. All metalwork shall be finished hot dipped galvanized in accordance with BS EN ISO1461:2009. The galvanizer shall be responsible for the thorough removal of all galvanizing smuts (fettling) to the complete satisfaction of the Landscape Architect. The decorating contractor shall prepare the galvanized surface by washing with detergent and water and scrubbing with a scouring pad until all dirt, grease, white rust & sulphates have been removed & then allowed to dry thoroughly. Supply and paint Dri mit 6630' from Sika Ltd (tel. 01707 374444) applied with a turkhead brush strictly in accordance with the manufacturers instructions, COSHH regulations and the product COSHH sheet. Apply 2No. coats of paint with a dry film thickness of 100 microns per coat. Apply paint only when galvanized surface is thoroughly dry at temperatures above five degrees celsius and in any event above the current dew point temperature. Paint work will be subject to inspection by experts and if Found wanting, shall be stripped off, re-prepared and applied entirely at the decorating contractors own cost.

5. All wood work to use ACQ water based wood preservative applied by vacuum pressure by Permawood or other similar and approved company. The timber shall then be stained with 3No. coats of Sadolin 'Classic,' colour 'Walnut' strictly in accordance with the manufacturers instructions, COSHH Regulations 2003 and product COSHH sheet.

SCHEDULE OF PLANTS

SPECIMEN PLANTS IN BEDS, GRASS OR GRAVEL

QTY	CODE	PLANT NAME	STOCK	SIZE
5No.	ACE ATR	Acer palmatum 'Atropurpurea'	C.G.	10L
3No.	PHO PUR	Phormium tenax 'Purpureum'	C.G.	10L
3No.	PHO TEN	Phormium tenax	C.G.	10L
4No.	PHO YEL	Phormium 'Yellow Wave '	C.G.	10L
12No.	PIN MOP	Pinus mugo 'Mops'	C.G.	10L

TOPIARY SPECIMEN SHRUBS/TREES PLANTED IN BEDS, GRASS OR GRAVEL

QTY	CODE	PLANT NAME	STOCK	SIZE
19No.	TOP YEW	Topiary Yew (Taxus baccata)	C.G.	25L

CLIMBERS

QTY	CODE	PLANT NAME	STOCK	SIZE	SPACING
4No.	Hed can	Hedera canariensis 'Gloire de Marengo'	'S' C.G.	15L	1/m
9No.	Par tri	Parthenocissus tricuspidata 'Veitchii'	'S' C.G.	15L	1/m

FEATHERED TREES

QTY	CODE	PLANT NAME	STOCK	SIZE	DFB	MAX Ht	WD
9No.	Bet jac	Betula jacquenontii	C.G. 15L	FTH 180-210cm		6m 12m	L

STANDARD TREES

QTY	CODE	PLANT NAME	STOCK	SIZE	DFB	MAX Ht	WD
3No.	ACE NEG	Acer negundo 'Kellys Gold'	D.G.	STD 10-12cm	6m	7m	M
32No.	AME ROB	Amelanchier lamarckii 'Robin Hill'	C.G.	STD 10-12cm	7m	8m	M
6No.	BET PEN	Betula pendula	C.G. 25L	STD 10-12cm	7m	14m	L
6No.	MES GER	Mespilus Germanica'Medlar'	D.G.	STD 10-12cm			
5No.	MAL SYL	Malus sylvestris	D.G.	STD 10-12cm			
2No.	PRU AVI	Prunus avium	D.G.	STD 10-12cm	13m	17m	M
1No.	PYR CHA	Pyrus calleryana 'Chanticleer'	D.G.	STD 10-12cm	6m	8m	M
31No.	SOR COM	Sorbus x commixta 'Embley'	D.G.	STD 10-12cm	12m	15m	M
6No.	SOR SHE	Sorbus aucuparia 'Sheerwater Seedling'	D.G.	STD 10-12cm	9m	11m	M

HEAVY STANDARD TREES

QTY	CODE	PLANT NAME	STOCK	SIZE	DFB	MAX Ht	WD
6No.	ACE CAM+	Acer campestre	R.B.	HVYSTD 12-14cm	17m	22m	M
1No.	LIQ STY+	Liquidamber styraciflua	R.B.	HVYSTD 12-14cm	12m	16m	M

MULTI-STEM TREES

QTY	CODE	PLANT NAME	STOCK	SIZE	DFB	MAX Ht	WD
3No.	BET JAC+	Betula utilis 'Jaquenontii'	R.B.	MUL 200-250cm	6m	18m	L

ORNAMENTAL HEDGE PLANTING

QTY	CODE	PLANT NAME	STOCK	SPACING
93No.	Vib Tin	Viburnun Tinus 'Eve Price'	C.G.	10L 3/m
529No.	Pru Lus	Prunus lusitanica	C.G.	10L 3/m
1002No.	Ele ebb	Elaeagnus x ebbingei' Limelight'	C.G.	10L 3/m

NATIVE HEDGE MIXES

QTY	%	PLANT NAME	STOCK	SPACING	SIZE
77m	Native hedge mix 1: double staggered row				
92No.	20%	Corylus avellana	D.G.	WHP 6/m	60-90cm
231No.	50%	Crataegus monogyna	D.G.	WHP 6/m	60-90cm
92No.	20%	Viburnum opulus	D.G.	WHP 6/m	60-90cm
46No.	10%	Cornus sanguinea	D.G.	WHP 6/m	60-90cm

PLANT MIXES

QTY	%	PLANT NAME	STOCK	SIZE	SPACING
165m2	Plant mix A (individual species to be planted in groups of 3 or 5)				
124No.	25%	Heuchera micrantha 'Palace Purple'	C.G.	5L	3/m2
124No.	25%	Choisya ternata 'Sundance'	C.G.	5L	3/m2
124No.	25%	Viburnum tinus 'Eve Price'	C.G.	10L	3/m2
124No.	25%	Cornus alba 'Sibirica'	C.G.	5L	3/m2
57m2	Plant mix B (individual species to be planted in groups of 3 or 5)				
56No.	33%	Hebe salicifolia	C.G.	5L	3/m2
56No.	33%	Choisya ternata 'Sundance'	C.G.	5L	3/m2
57No.	34%	Pittosporum tenuifolium 'Purpureum'	C.G.	5L	3/m2
100m2	Plant mix C (individual species to be planted in groups of 3 or 5)				
99No.	33%	Euonymus fortunii 'Emerald Gaiety'	C.G.	10L	3/m2
99No.	33%	Festuca glauca 'Elijah Blue'	C.G.	5L	3/m2
100No.	34%	Heuchera micrantha 'Marmalade'	C.G.	5L	3/m2
57m2	Plant mix D (individual species to be planted in groups of 3 or 5)				
35No.	20%	Daphne laureola 'Spurge Laurel'	C.G.	5L	3/m2
35No.	20%	Skimmia japonica 'Rubella'	C.G.	10L	3/m2
35No.	20%	Choisya 'Aztec Pearl'	C.G.	5L	3/m2
35No.	20%	Hypericum x hidcoteense 'St Johns Wort Hidcote'	C.G.	5L	3/m2
35No.	20%	Euonymus 'Emerald and Gold'	C.G.	5L	3/m2
37m2	Plant mix E (individual species to be planted in groups of 3 or 5)				
28No.	25%	Prunus laurosus 'Otto Luyken'	C.G.	10L	3/m2
28No.	25%	Lonicera nitida 'May Green'	C.G.	10L	3/m2
28No.	25%	Hypericum 'Hidcote'	C.G.	5L	3/m2
28No.	25%	Bergenia cordifolia 'Purpurea'	C.G.	5L	3/m2
75m2	Plant mix F (individual species to be planted in groups of 3 or 5)				
56No.	25%	Pachysandra terminalis 'Green Carpet'	C.G.	5L	3/m2
56No.	25%	Bergenia cordifolia 'Purpurea'	C.G.	5L	3/m2
56No.	25%	Prunus luscitanica	C.G.	10L	3/m2
56No.	25%	Euonymus Fortunei 'Emerald n Gold'	C.G.	5L	3/m2
54m2	Plant mix G (individual species to be planted in groups of 3 or 5)				
32No.	20%	Berberis thunbergii 'Atropurpurea Nana'	C.G.	10L	3/m2
32No.	20%	Choisya ternata 'Sundance'	C.G.	10L	3/m2
32No.	20%	Photinia x fraseri 'Red Robin'	C.G.	5L	3/m2
32No.	20%	Cornus alba	C.G.	5L	3/m2
37No.	20%	Aucuba japonica	C.G.	5L	3/m2
68m2	Plant mix J (individual species to be planted in groups of 3 or 5)				
51No.	25%	Hebe 'Silver Dolar'	C.G.	5L	3/m2
51No.	25%	Stachys byzanthina	C.G.	5L	3/m2
51No.	25%	Lavandula angustifolia 'hidcote'	C.G.	10L	3/m2
51No.	25%	Molina caerulea subsp. caerulea 'Moorhexe'	C.G.	10L	3/m2

ORNAMENTAL MIXES

QTY	%	PLANT NAME	SIZE	SPACING
20m2	Ornamental mix A			
12No.	20%	Alchemilla mollis 'Ladys Mantle'	10L	3/m
12No.	20%	Lavendula Hidcote	10L	3/m
12No.	20%	Choisya ternata 'Sundance'	10L	3/m
12No.	20%	Rosmarinus 'Miss Jessops Upright'	10L	3/m
12No.	20%	Hebe 'Midsummer Beauty'	10L	3/m
53m2	Ground cover mix D			
159No.	100%	Symphoricapos chenaultii 'Hancock'	C.G 10L	3/m2

SEED MIXES

AREA	SEED MIX NAME
2195m2	Area to be turfed ('Medallion' by Rowlawn Ltd, refer to Measured Works Schedule)

NOTES AND ABBREVIATIONS:

R.B. = Root-balled stock
C.G. = Container grown stock
O.G. = Open ground stock, to be planted Nov 1st - March 1st
FTH = Feathered tree
STD = Standard tree
HVYSTD = Heavy Standard tree
XHVYSTD = Extra Heavy standard tree
BLE = Broad Leaf Evergreen
CON = Conifer
L = Litre container
DFB = 'Distance from Buildings' based on minimum building foundation depths
Max Ht = 'Maximun Height' of tree
WD = 'Water Demand' of tree
SHC = Shrub Height Classification
A = (600mm mature height
B = 600mm - 1.8m mature height
C =) 1.8m mature height with low water demand and slow growth
D = 1.8m - 3m mature height
E = 3m - 5m mature height
F = >5m mature height
Note: Plants not classified within the JBA SHC are NOT designated as shrubs. JBA understand shrubs to be defined as those plants of perennial habit with woody stems.

-Girth size is given for standard trees, otherwise all sizes refer to height. All sizes are the minimums acceptable.
-Shrubs specified as 3 litre size shall be 400-600mm minimun height and spread and 2 litre stock shall be 300-400mm minimum height and spread. These heights and spreads in relation to pot size are just a guide and the 'National Plant Specification' sizes will be accepted (but will be seen as the absolute minimun acceptable). Any shrub supplied which are smaller than this will be rejected at once.
-Cornus varieties shall be twice transplanted and pruned to form bushy rounded plants. Leggy plants with few branches will be rejected, as will leggy plants which have been pruned hard.
-Plants shall be completely hardened off, any plants which show signs of scorching after planting will be rejected.

REFER TO THE ACCOMPANYING MEASURED WORKS SCHEDULE DOCUMENT FOR MORE INFORMATION
CHANGES TO SUPPLIERS/MANUFACTURERS ARE TO BE EQUAL AND APPROVED.
SUBSTITUTIONS TO SHRUB/TREE VARIETIES ARE TO BE AGREED WITH JAMES BLAKE ASSOCIATES.
DO NOT SCALE FROM THIS DRAWING
ALL DIMENSIONS TO BE CHECKED ON SITE

(C) JAMES BLAKE ASSOCIATES 2016

Rev	Date	Details	By
C	21.9.17	LANDSCAPING AMENDED IN LINE WITH NEW LAYOUT AND TREE LINE ADDED BEHIND PLOTS 226-242, BAT BRICK POSITIONS HAVE BEEN REVIEWED	AU
B	27.04.2017	LANDSCAPING AMENDED IN LINE WITH NEW LAYOUT AND COMMENTS FROM LPA ON 24.04.2017.	AU
A	22.12.2016	LANDSCAPING AMENDED IN LINE WITH NEW LAYOUT AND COMMENTS FROM LPA ON 28.04.2016.	AU

Drainage Authority Approval Date __-__-__

Highway Authority Approval Date __-__-__

Do not scale from this drawing. Use written dimensions only. When shown relationships between slab levels and ground levels are to be checked on site. Any discrepancy or suggested modification to be reported to Design and Engineering Director.
Note : This drawing is the copyright of Bovis Homes Ltd.

BOVIS HOMES
Bovis Homes Central Region
Bromwich Court
Highway Point
Gorsey Lane
Coleshill
B46 1JU
Tel: 01675 437 000
Fax: 01675 437 094
DX: 728340 Coleshill 2

SITE
Upper Heyford
Phase B3

DRAWING TITLE
Landscape Proposals
Plant Schedule

DRAWN BY	DATE	DRAWING NO.	REV
DW/AU	26.06.15	HEYB3-03-101	C
SCALE: n/a	CHECKED/DATE		