





Civil Engineering Consultants

SuDS Maintenance Regime for Phase 8 off Camp Road, Upper Heyford June 2016

Stormwater Maintenance Regime

This Maintenance Regime defines the scope of inspections and maintenance that are to be carried out on surface water drainage elements such as pipes, manholes/catchpits, flow controls, storage crates, ponds, permeable paving and headwalls.

This plan provides a methodology for maintaining the above and includes:

- Guidance on the scope of inspection and maintenance requirements, including suitable personnel and frequency of inspections.
- Guidance on recommended actions that arise from the inspections.

Scope of Inspections and Maintenance

- Type of Inspections

During and following construction, regular inspections are required in order to assess their performance and to schedule any required maintenance.

Inspections are divided into two categories:

- Routine Inspections for Maintenance which are to be carried out by any responsible person (with no professional engineering knowledge).
- Engineering Inspections for Maintenance which are to be carried out by professional/qualified civil engineering personnel.

Item	Routine Inspections				Engineering Inspections	
	Inspection	Min. Frequency	Action	Min. Frequency	Inspections & Action over the life of the development	
Pipes / Manholes / Catchpits	Inspect surface access points to underground storage crates, manholes and catchpits as well as the surrounding area. Particular attention should be paid to damage or blockage. To be visually inspected after heavy rainfall events to ensure they are free of debris and litter.	6 monthly As required	Clear accumulated sediment and debris	6 monthly	All manholes/catchpits will require to be inspected externally and internally. External inspections will determine the overall condition of the access points, and should record deterioration of exposed concrete, access lids, restricted access due to overgrown vegetation/debris.	
Flow Control Device	Inspect flow control devices for blockages, damage and general condition.	6 monthly	Clear accumulated sedimentation	6 monthly	Inspections will determine the overall condition of the flow control device to ensure it is working efficiently and effectively.	Flow
	To be visually inspected after heavy rainfall events to ensure they are free of debris and litter.	As required	Repair/replace damaged pit covers and grates	As required		the m
Storage Crates	Inspect storage crates via upstream/downstream manholes for silt/debris build-up and general condition. To be visually inspected after heavy rainfall events to ensure they are free of debris and litter.	6 monthly As required	Clear accumulated sedimentation via jetting & CCTV	As required	Inspections via inspection chambers/accesses and upstream/downstream manholes will determine the overall condition of the storage crates to ensure they are free from silt/debris build-up and should record any defects/deterioration.	50 ye Crate manu
Permeable Pavement	Inspect catchpit/silt traps for silt build-up, blockages, damage and general condition	6 monthly	Surface to be brushed/vacuumed to prevent vegetation from growing in the joints.	6 monthly (Spring & Autumn) 6 monthly	Inspections will determine the overall condition of the permeable pavement and associated catchpit/silt traps to ensure they are free from silt build-up and it is working efficiently and effectively.	Wher - Ren a larg - Ren - Ren
	To be visually inspected after heavy rainfall events to ensure organic matter hasn't settled on the surface.	As required	Outfall and catchpit/silt traps to be inspected and cleared of sedimentation Weeding of joints through use of approved weed killers	As required when weeds are actively growing		- Nem - Was - Rela the m

ow control to be replaced by a competent Contractor to
e manufacturers specification

- year design life
- ates to be replaced by a competent Contractor to the anufacturers specification
- nen water starts to run-off the pavement:
- Remove a suitable block along the perimeter or one with arger joint width surround it to
- Remove the remaining blocks and stack neatly nearby emove the laying course and aggregate onto suitable embranes to be stockpiled
- Vash the aggregate and/or replace if necessary
- elay the aggregate, laying course and block paving to manufacturers specification