

Date: 2012, 20.03.15, 15.06.16		Site: Upper Heyford										Surveyor: MR/MGP		Client:		Dorchester Group						Job no:		D.0358		
Number	Species	Height	Estimate	Stem dia	Estimate	Spread					Crown clearance height					Life stage	General observations	Structural condition	Physiological condition	ULE	Quality grading	RPA radius	RPA area			
						N	Estimate	S	Estimate	E	Estimate	W	Estimate	1st branch	Estimate									1st branch direction	Canopy	Estimate
T61	Maple	11	-	460	-	5	-	3	-	6	-	4	-	2	-	East	2	-	M	Exposed girdling roots. Weak fork at 2.5m. Fire hydrant at base to east.	Medium	Low	10+	C1	5.5	95.7
T62	Whitebeam	6	-	410	-	4	-	3	-	4	-	4	-	2	-	West	2	-	M	Minor bark damage at base.	High	High	10+	C1	4.9	76.1
T63	Sycamore	12	-	600	-	7	-	6.5	-	6	-	6	-	3	-	North east	3	-	M	Small wet cavity at 2m west. Pruning wounds well occluded.	High	High	20+	B1	7.2	162.9
T64	Ash (Common)	14	-	620	-	6	-	7	-	6.5	-	7.5	-	4	-	West	4	-	M	Several pruning wounds and branch damage associated with lighting columns. Cavity at 2.5m north west. Exposed roots.	Medium	Medium	20+	C1	7.4	173.9
T65	Whitebeam	10	-	620	-	5	-	5	-	5	-	5	-	2	-	South	1.5	-	M	Notable in terms size for species.	High	High	20+	B1	7.4	173.9
T66	Whitebeam	8	-	570	-	5	-	5	-	5	-	5	-	2	-	South	1.5	-	M	Notable in terms size for species.	High	High	20+	B1	6.8	147.0
T67	Ash (Common)	11	-	570	-	6	-	5	-	7.5	-	4.5	-	2.5	-	East	2	-	M	Exposed roots. Pruning wound and cavity at 1m west. Moderate amounts minor deadwood. Longitudinal crack at 2m north east.	Medium	Medium	10+	C1	6.8	147.0
T68	Ash (Common)	14	-	650	-	6	-	6	-	7	-	7	-	2.5	-	West	2	-	M	Minor amounts minor deadwood.	Medium	Medium	20+	B1	7.8	191.2
T69	Chestnut (Horse)	14	-	780	-	6	-	6	-	6	-	4	-	2	-	All round	3	-	M	Indication of bacterial wet wood. Weak forks observed with included bark. Elder growing within fork at 1.8m, indication of decay. Decay at union west side with crack forming - potential failure point.	High	Medium	20+	B1	9.4	275.3
T70	Ash (Common)	17	-	720	-	4	-	6	-	4	-	7	-	4	-	West	3	-	M	Wet cavity at 1.8m north east. Minor amounts minor deadwood. Potential hazard beam observed at 4m west.	Medium	Medium	10+	C1	8.6	234.5
T74	Lawson cypress	11	-	354	-	2.5	-	2	-	2	-	2	-	N/A	-	N/A	0.5	-	M	Slightly suppressed to north by security fence. Lighting column obstructing growth north.	High	High	40+	C1	4.2	56.6
T75	Maple	12	-	520	-	5	-	5	-	6	-	6	-	2	-	West	1.5	-	M	Exposed roots. Pruning wounds well occluded.	High	High	20+	B1	6.2	122.3
T76	Sycamore	12	-	540	-	6	-	4.5	-	6	-	5	-	3	-	East	2	-	M	Exposed roots. Pruning wounds well occluded. Cavity on north side next to fence.	High	Medium	20+	B1	6.5	131.9
T77	Maple	12	-	620	-	5	-	6	-	4	-	7	-	2.5	-	West	2	-	M	Dead ivy into canopy. Moderate minor deadwood.	Medium	Medium	10+	C1	7.4	173.9
T78	Maple	11	-	550	-	6.5	-	5	-	5.5	-	5	-	1.5	-	East	2	-	M	Previous pruning wound with decay at 1.5m east. Moderate amounts minor deadwood, minor cavities.	Medium	Medium	10+	C1	6.6	136.9
T79	Maple	12	-	630	-	6	-	5	-	5	-	6	-	3	-	West	3	-	M	Cavity on south at 1.5m. Exposed roots. Minor amounts minor deadwood.	Medium	Medium	10+	C1	7.6	179.6
T80	Sorb us, white beam	9	-	290	-	4	-	3.5	-	3	-	2.5	-	N/A	-	N/A	2	-	EM	Weak fork at 1m. Generally suppressed.	Medium	High	20+	C1	3.5	38.1
T81	Maple	12	-	650	-	7	-	6	-	6	-	8	-	2.5	-	West	2.5	-	M	Three main stems, forks at 2m. Bark wound with decay on north west side. Exposed damaged roots. Broken branches roadside to north.	Medium	Medium	20+	C1	7.8	191.2
G82	Whitebeam	9	-	520	-	4	-	5	-	5	-	5	-	N/A	-	N/A	2	-	M	Fruiting body on centre tree, with decay. Eastern tree has longitudinal crack, western tree better tree. Central and eastern tree c category, western tree b category.	Medium	Medium	10+	C2	6.2	122.3
G83	Whitebeam	9	-	500	-	4	-	5	-	3.5	-	4	-	N/A	-	N/A	2	-	M	Third tree from west has fruiting body. Girdling roots observed generally. Minor amounts of minor deadwood. Splits in bark. Rpas taken individually	Medium	Medium	20+	B2	6.0	113.1
G362	Maple (Norway)	8	-	250	-	0	-	0	-	4	-	4	-	N/A	-	N/A	2	-	M	6 trees. All have minor pruning wounds, some with minor bark damage at base.	Medium	Medium	20+	C2	3.0	28.3
G363	Maple (Norway)	8	-	350	-	0	-	0	-	5.5	-	5	-	N/A	-	N/A	1.5	-	M	5 trees. Minor deadwood throughout. Three trees very sparse canopy.	High	Medium	20+	C2	4.2	55.4
G390	Mixed maples	12	-	360	-	As on plan					N/A	-	N/A	2	-	M	Slightly suppressing each other. Bark damage at base.	Medium	Medium	20+	C2	4.3	58.6			
G392	Maple (Norway)	11	-	400	-	As on plan					N/A	-	N/A	2.5	-	M	3 trees. Pruning wounds. Potential hazard beam at 2m east on southern tree, crossing branches.	Medium	Medium	20+	C2	4.8	72.4			
T393	Maple (Norway)	11	-	350	-	4	-	5	-	4	-	4	-	2.5	-	South	2	-	M	Good shape.	High	High	20+	B1	4.2	55.4
G394	Maple (Norway)	12	-	440	-	5	-	5	-	5	-	4	-	N/A	-	N/A	2	-	M	Good shape. Slightly suppressed to west by adjacent tree.	High	High	20+	B1	5.3	87.6

Date: 2012, 20.03.15, 15.06.16		Site: Upper Heyford										Surveyor: MR/MGP		Client:		Dorchester Group						Job no:		D.0358		
Number	Species	Height	Estimate	Stem dia	Estimate	Spread					Crown clearance height					Life stage	General observations	Structural condition	Physiological condition	ULE	Quality grading	RPA radius	RPA area			
						N	Estimate	S	Estimate	E	Estimate	W	Estimate	1st branch	Estimate									1st branch direction	Canopy	Estimate
T1121	Lawson cypress	9	-	450	-	3	-	3	-	3	-	3	-	N/A	-	N/A	1	-	M	Open grown tree, neighbouring trees recently removed, twin stemmed at 2.5m.	Fair	Fair	10+	C1	4.0	49.3
G1122	Leyland Cypress	18	-	660	-	0	-	0	-	5	-	5	-	N/A	-	N/A	2.5	-	M	Two mature trees, minor bark damage, minor broken hung up branches.	Fair	Fair	10+	C2	7.9	197.1
G1123	Birch, cherry, elder	5	-	100	#	As on plan					N/A	-	N/A	0	-	EM	Group of scrubby trees adjacent to building, low value.	Fair	Fair	10+	C2	1.2	4.5			
T1124	Lawson cypress	9	-	340	-	2	-	3	-	3	-	3	-	1	-	West	0	-	EM	Unbalanced crown, minor broken limbs.	Fair	Fair	10+	C1	4.1	52.3
T1125	Weeping willow	9	-	410	-	7	-	6	-	5	-	5	-	2.5	-	West	0.5	-	M	Dieback in crown, some moderate hung up branches, moderate deadwood.	Fair	Fair	10+	C1	4.9	76.1
T1126	Swedish whitebeam	8	-	510	-	2.5	-	3	-	3	-	3	-	0	-	-	2	-	M	Minor deadwood, good form	Good	Fair	10+	C1	6.1	117.7
T1127	Norway maple "crimson king"	10	-	340	-	5	-	5	-	4	-	5	-	2.5	-	South	1.5	-	M	Suppressed by neighbouring trees, saplings beneath crown, minor deadwood.	Fair	Fair	10+	C1	4.1	52.3
G1128	Lawson cypress	8	-	300	#	0	-	0	-	2.5	-	2.5	-	0	-	-	0	-	M	Two trees in group, minor dieback, self set elder growing through crowns.	Fair	Fair	10+	C2	3.6	40.7
G1129	Norway maple, cypress	11	-	300	#	As on plan					0	-	-	0	-	M	Group of trees adjacent to buildings, included unions, suppressed form.	Fair	Fair	10+	C2	3.6	40.7			
T1130	Leyland Cypress	11	-	565.69	-	3.5	-	3.5	-	3.5	-	3.5	-	N/A	-	N/A	0.5	-	M	Twin stemmed tree, Lv power line through crown, adjacent to buildings.	Good	Fair	10+	C1	6.8	144.8
T1131	Norway spruce	11	-	400	#	3	-	3	-	3	-	3	-	N/A	-	N/A	0.5	-	M	Twin stemmed tree, open crown.	Good	Fair	10+	C1	4.8	72.4
T1132	Fir	11	-	346.41	-	2.5	-	2	-	2.5	-	2	-	N/A	-	N/A	N/A	-	EM	Multi stemmed tree, included unions at base, self set elder growing through crown.	Fair	Fair	10+	C1	4.2	54.3
T1133	Cherry	5	-	300	#	5	-	4	-	4	-	4	-	N/A	-	N/A	0.5	-	M	Multi stemmed tree, large areas of bark damage with small cavities, included unions at base	Fair	Poor	<10	C1	3.6	40.7
T1134	Swedish whitebeam	8	-	480	-	5	-	5	-	4	-	4	-	2	-	North	1	-	M	Pruned in the past, minor deadwood	Fair	Fair	10+	C1	5.2	83.7
T1135	Cherry	8	-	400	#	5	-	6	-	0	-	0	-	2	-	North-west	1	-	M	Two trees in group, open crowns.	Fair	Fair	<10	C2	4.8	72.4
G1136	Cherry	8	-	250	#	4	-	4	-	0	-	0	-	N/A	-	N/A	1	-	EM	Two trees, low crowns to east, one tree multi-stemmed.	Fair	Fair	10+	C2	3.0	28.3
G1138	Elder, ash	5	-	100	#	As on plan					N/A	-	N/A	N/A	-	SM	Area of self set trees, adjacent building recently demolished.	Fair	Fair	<10	C2	1.2	4.5			
T1139	Norway maple "crimson king"	7	-	120	-	2.5	-	2.5	-	2.5	-	2.5	-	2	-	South	1.5	-	EM	Good firm, no obvious defects.	Good	Good	20+	C1	1.4	6.5
T1140	Apple	5	-	125	#	4	-	4	-	4	-	5	-	N/A	-	N/A	N/A	-	EM	Low canopy, poor form	Fair	Fair	10+	C1	1.5	7.1
T1141	Leyland Cypress	15	-	606.22	-	5	-	5	-	5	-	5	-	N/A	-	N/A	1	-	M	Mature tree adjacent to building, multi stemmed, included unions at base.	Fair	Fair	<10	C1	7.3	166.3
T1142	Cherry	8	-	350	#	3.5	-	3.5	-	3.5	-	3.5	-	N/A	-	N/A	N/A	-	M	Situated adjacent to building., suppressed	Fair	Fair	<10	C1	4.2	55.4
T1143	Lawson cypress, goat willow, elder	9	-	200	#	As on plan					N/A	-	N/A	N/A	-	EM	Group of self set trees, no access to stems.	Fair	Fair	<10	C2	2.4	18.1			
T1144	Elm	12	-	660	-	6.5	-	7	-	8	-	7	-	1.5	-	South west	0.5	-	M	Tree on edge of hard standing, epicormic growth at base and on stem. Self set trees at base and under crown.	Good	Good	20+	B1	7.9	197.1
T1145	Elder	8	-	200	-	2	-	2	-	3	-	3	-	0	-	-	0.5	-	M	Self set tree.	Fair	Fair	<10	C1	2.4	18.1
T1146	Norway maple	10	-	300	-	4.5	-	5	-	5	-	5	-	2.5	-	West	2.5	-	EM	Good form, minor epicormic growth on stem.	Good	Good	20+	B1	3.6	40.7
G1149	Birch, hawthorn	8	-	200	-	3	-	3	-	2	-	3	-	N/A	-	N/A	0.5	-	EM	Self set trees adjacent to building, no obvious defects, largest values recorded.	Good	Good	10+	C1	2.4	18.1
T1150	Weeping willow	7.5	-	350	-	4	-	4	-	5	-	4	-	2.5	-	North	N/A	-	EM	Individual tree, minor deadwood.	Fair	Fair	10+	C1	4.2	55.4
T1151	Weeping willow, Cherry	10	-	500	-	As on plan					N/A	-	N/A	N/A	-	M	Three trees in row, no access to stems-overrun with bramble. Largest dbh estimated.	Fair	Fair	10+	C2	6.0	113.1			
G1152	Ash, sycamore, willow, hawthorn, birch, elder	7	-	150	#	As on plan					N/A	-	N/A	N/A	-	EM	Area of self set trees located between buildings.	Fair	Fair	10+	C2	1.8	10.2			

Date: 2012, 20.03.15, 15.06.16				Site: Upper Heyford								Surveyor: MR/MGP			Client:		Dorchester Group						Job no:		D.0358	
Number	Species	Height	Estimate	Stem dia	Estimate	Spread					Crown clearance height					Life stage	General observations	Structural condition	Physiological condition	ULE	Quality grading	RPA radius	RPA area			
						N	Estimate	S	Estimate	E	Estimate	W	Estimate	1st branch	Estimate									1st branch direction	Canopy	Estimate
T1153	Sycamore	9	-	400	#	5	-	5	-	5	-	5	-	N/A	-	N/A	1.5	-	EM	Tree located adjacent to road, no access to stem due to bramble.	Good	Good	20+	B1	4.8	72.4
T1154	Birch	9	-	350	-	5.5	-	4	-	4.5	-	4	-	2.5	-	West	1	-	M	Tree part of line adjacent to road, good form minor deadwood.	Good	Fair	10+	C1	4.1	52.3
T1155	Birch	12	-	510	-	6.5	-	6.5	-	6	-	6	-	2	-	South	N/A	-	M	Tree part of line adjacent to road, good form minor deadwood.	Good	Fair	10+	C1	5.6	99.9
T1156	Birch	12	-	470	-	6	-	5.5	-	5	-	7	-	1.5	-	North	0.5	-	M	Tree part of line adjacent to road, good form minor deadwood and branch stubs	Fair	Fair	10+	C1	5.6	97.8
T1157	Birch	12	-	440	-	7	-	6	-	8	-	5.5	-	2.5	-	South west	0.5	-	M	Tree part of line adjacent to road, good form minor deadwood and witches brooms, slight lean to the east.	Fair	Fair	10+	C1	4.8	72.4
T1158	Birch	12	-	520	-	5.5	-	4.5	-	6	-	4	-	2	-	South	0.5	-	M	Tree part of line, slight lean to the east. Minor deadwood.	Fair	Good	10+	C1	5.6	99.9
H1159	Hawthorn	4	-	150	#	0	-	0	-	1.5	-	1.5	-	N/A	-	N/A	N/A	-	M	Managed boundary hedgerow, good screen	Fair	Fair	20+	B2	1.8	10.2
T1160	Swedish whitebeam	7.5	-	425	#	4	-	5	-	5	-	4	-	1.5	-	North east	1	-	EM	Tree situated adjacent to hedgerow, stem obscured by ivy, some deadwood in crown.	Fair	Good	10+	B1	5.1	81.7
T1161	Horse chestnut	14	-	780	-	6	-	7	-	6	-	7	-	2	-	South	0.5	-	M	Twin stemmed, bleeding canker east side and loose bark to stem, leaf minor infection, stem partially obscured by ivy.	Fair	Fair	<10	C2	9.4	275.3
T1162	Ash	14	-	580	-	7	-	4	-	8	-	7	-	2	-	South	2	-	M	Mature tree located in group, minor deadwood, tree suppressed.	Fair	Good	10+	B2	6.7	141.9
T1163	Swedish white beam	9	-	440	-	3	-	4	-	4	-	4	-	1.5	-	West	1	-	M	Tree located in group, some deadwood in crown, suppressed.	Fair	Fair	10+	B2	5.0	79.8
T1164	Horse chestnut	12	-	650	-	5	-	7	-	6	-	6	-	2	-	North west	1	-	M	Tree located in group, minor deadwood, leaf minor infection, suppressed	Good	Fair	20+	B2	7.3	168.4
T1165	Ash	13	-	470	-	4	-	3	-	5	-	5	-	3	-	West	1	-	M	Tree located in group, some deadwood in crown, suppressed. Ivy obscuring stem.	Fair	Fair	20+	B2	5.6	99.9
T1166	Swedish white beam	9	-	520	#	4	-	3	-	4.5	-	4	-	2	-	South	1.5	-	M	Tree located in group, some deadwood in crown, suppressed. Ivy obscuring stem.	Fair	Fair	10+	B2	6.2	122.3
T1167	Birch	7.5	-	310	-	4	-	3.5	-	4	-	3.5	-	2	-	North west	1.5	-	EM	Poor form some dieback in crown, pruned in the part	Fair	Fair	<10	C1	3.6	40.7
T1168	Birch	15	-	600	-	7	-	7	-	8	-	8	-	3	-	West	2	-	M	Wide crown with over extended limbs, small cavities at branch collars, poor form	Fair	Fair	10+	C1	6.7	141.9
T1169	Birch, sycamore	10	-	250	#	4	-	4	-	0	-	0	-	N/A	-	N/A	N/A	-	EM	Self set trees adjacent to buildings.	Fair	Good	10+	C2	3.0	28.3
T1170	Weeping willow	10	-	450	-	5	-	5	-	5	-	5	-	N/A	-	N/A	N/A	-	M	Estimated values-no access, stem obscured by ivy	Fair	Fair	10+	C1	5.4	91.6
G1171	Rowan, oak, cypress, privet, cherry, hawthorn	7.5	-	200	-	As on plan					N/A	-	N/A	N/A	-	EM	Group of scrubby trees adjacent to existing buildings			Fair	Fair	<10	C2	2.4	18.1	
T1172	Lawson cypress	7.5	-	300	#	3	-	3	-	3	-	3	-	N/A	-	N/A	N/A	-	M	Tre locate adjacent to access road, some branches subsiding	Fair	Fair	<10	C1	3.6	40.7
T1173	Lawson cypress	9	-	400	#	3	-	3	-	3	-	3	-	N/A	-	N/A	N/A	-	M	Good form, multi stemmed.	Fair	Good	10+	C1	4.8	72.4
G1174	Hawthorn, privet	5.5	-	150	#	2	-	2	-	0	-	0	-	N/A	-	N/A	N/A	-	M	Planted hedge grown up, ivy obscuring stems.	Fair	Fair	<10	C2	1.8	10.2
T1175	Lawson cypress	9	-	346.41	-	4	-	4	-	4	-	4	-	N/A	-	N/A	N/A	-	M	Multi stemmed tree, no access to stems, good form	Fair	Good	10+	C1	4.2	54.3
G1176	White pine	9	-	440	-	6	-	6	-	0	-	0	-	N/A	-	N/A	N/A	-	M	Group of two trees, branches on floor.	Good	Good	20+	B2	5.3	87.6
T1177	Lawson cypress	9.5	-	450	-	3	-	3	-	4	-	4	-	N/A	-	N/A	N/A	-	M	Multi stemmed tree, good form	Fair	Good	10+	C1	5.4	91.6
G1178	Cherry, crab	5.5	-	350	-	As on plan					N/A	-	N/A	N/A	-	EM	Group of small trees, largest dbh recorded., some dieback and minor dead trees.			Fair	Fair	<10	C2	4.2	55.4	
T1179	Lawson cypress	7.5	-	200	#	2	-	2	-	2	-	2	-	N/A	-	N/A	N/A	-	M	Multi-stemmed tree, deadwood within.	Fair	Fair	<10	C1	2.4	18.1
G1180	Cherry laurel cherry, elder.	5.5	-	125	#	As on plan					N/A	-	N/A	N/A	-	EM	Scrubby group, overgrown			Fair	Fair	<10	C2	1.5	7.1	
T1181	Wild cherry	8.5	-	460	-	7	-	6	-	5	-	5	-	2	-	North	N/A	-	M	Poor form, unbalanced crown, canopy on ground.	Fair	Fair	10+	C1	5.5	95.7
G1182	Leyland cypress	17	-	606.22	-	6	-	6	-	0	-	0	-	N/A	-	N/A	N/A	-	M	Group of multi stemmed trees adjacent to building.	Fair	Fair	10+	C2	7.3	166.3

Date: 2012, 20.03.15, 15.06.16		Site: Upper Heyford										Surveyor: MR/MGP		Client: Dorchester Group		Job no:		D.0358								
Number	Species	Height	Estimate	Stem dia	Estimate	Spread				Crown clearance height				Life stage	General observations	Structural condition	Physiological condition	ULE	Quality grading	RPA radius	RPA area					
						N	Estimate	S	Estimate	E	Estimate	W	Estimate									1st branch	Estimate	1st branch direction	Canopy	Estimate
T1184	Spruce	15	-	450	-	4.5	-	4.5	-	4.5	-	4.5	-	N/A	-	N/A	N/A	-	M	Mature tree adjacent to access road, low canopy, no obvious defects.	Fair	Fair	10+	C1	5.4	91.6
T1185	Yew	5	-	150	-	3	-	3	-	3	-	3	-	N/A	-	N/A	N/A	-	EM	Shrubby and multi stemmed., self set elder though out	Good	Good	20+	B1	1.8	10.2
SM1186	Elder cherry	5.5	-	100	-	As on plan				N/A	-	N/A	N/A	-	EM	Scrubby vegetation adjacent building	Fair	Fair	<10	C2	1.2	4.5				
T1187	Fir	10.5	-	200	-	2.5	-	2.5	-	2.5	-	2.5	-	N/A	-	N/A	0.5	-	EM	Good form, adjacent tree felled	Good	Good	20+	B1	2.4	18.1
G1494	Elder, hawthorn	4.0	-	150	#	2.0	-	2.0	-	0.0	-	0.0	-	N/A	-	N/A	N/A	-	EM	Shrubby self set trees located on boundary, overrun with bramble.	Fair	Fair	<10	C2	1.8	10
T1495	Plum (Purple)	5.5	-	225	-	2.0	-	3.0	-	3.0	-	2.5	-	0.5	-	East	0.5	-	M	Good form, low canopy	Good	Good	10+	C1	2.7	23
T1516	Cypress	17.0	-	600	-	4.0	-	3.0	-	5.0	-	5.0	-	N/A	-	N/A	N/A	-	M	Three trees adjacent building, dense canopy	Good	Good	10+	C1	7.2	163