


SPECIFICATION
All works generally, to comply with the written Soft Landscape Specification.

NOTE: DO NOT SCALE FROM DRAWING



4 3 2 1 0 2 4 6m

Rev	Date	Details	Drawn
A	12.07.17	LPA comments - amend specie	JS



HEAD OFFICE
Rodbourne Rail Business Centre, Grange Lane,
Malmesbury, SN16 0ES
Tel: 01666 825646

Courtyard House, Mill Lane, Godalming, GU7 1EY
Tel: 01483 425714

Suite 6, Crescent House, Yonge Close, Eastleigh, SO50 9SX
Tel: 02382 026300

9 Brownlow Road, Cambridge, CB4 3NG
Tel: 07825 868654

email: mail@acdenv.co.uk
www.acdenvironmental.co.uk



scheme: Cotefield Road,
Bodicote - Red Bed
Application
client: Cala Homes
drawing: Landscape Proposals
date: March 2017
scale: 1:200@A2
drawing no: CALA18397-12A
drawn: JS checked: DW

Copyright of ACD Environmental Ltd. All rights described in Chapter IV of the Copyright, Designs and Patents Act 1988 have been generally asserted: 2011. Copyright of this plan remains with ACD until all fees have been paid in full.

Outfall into proposed ditch to be lined with stone pitching to ensure direction of fall towards existing ditch and to prevent ditch from being overgrown

Swale Laid At 1:500 From 89.946 To Existing Ditch 89.830 Base Of Swale 1m Wide With 1:3 Banks To Existing


Marginal Reed Mix
21 No. Iris pseudacorus 15%
14 No. Phalaris arundinacea 10%
41 No. Phragmites australis 30%
21 No. Sparganium emersum 15%
41 No. Typha latifolia 30%

Marginal Reed Mix
154 No. Iris pseudacorus 15%
103 No. Phalaris arundinacea 10%
308 No. Phragmites australis 30%
154 No. Sparganium emersum 15%
308 No. Typha latifolia 30%


Legend



Existing trees and hedges to be retained and protected during construction



Proposed Marginal Reed Bed mix. To be planted in groups of 5-7no. of each species



Proposed banks of ditch to be seeded with a wildflower grass seed. To be seeded with 'WFG9 Wetland and Pond Area' seed mix as supplied by Germinal and sown at 5 grams per msq, or similar and approved

Plant Schedule

Herbaceous					
Species Name	Height	Pot Size	Specification	Density	No.
Phalaris arundinacea		3L	C	3/m ²	117 No.

Marginal / Aquatics					
Species Name	Pot Size	Specification	Density	No.	
Iris pseudacorus	3-3.5L	C	3/m ²	175 No.	
Phragmites australis	3-3.5L	C	3/m ²	349 No.	
Sparganium emersum	3-3.5L	C	3/m ²	175 No.	
Typha latifolia	3-3.5L	C	3/m ²	349 No.	

