

STREET LIGHTING KEY:



NB: Preliminary lighting design. OCC Street Lighting Department to be commissioned to undertake detailed design as an extra to their Section 38 review.

Preliminary design based on 5m tubular steel column and LED Roadway lighting NXT series small, 12W LED 525mA 4000K Colour temperature, Nema 7 pin switch pre-set to dim to 50% between 10:00pm to 6:am


Reality Outdoor Lighting Reports available upon request.

NB: Adoptable – Preliminary design to Lighting Class C4 (in accordance with adjacent Cala Homes development), however, we feel that this may be overlit for this rural residential setting and will further discuss requirements with OCC.

NB: POS, foot/cycle link and private areas designed to P5.

-  – Proposed adoptable 5m column position
-  – Existing column on adjacent Cala Homes development (S38 Agreement status TBC)
-  – Proposed Private 5m column position

PRELIMINARY - FOR PLANNING

REV. No.	DATE	DESCRIPTION	INITIALS
Client		CREST NICHOLSON	MJA CONSULTING CIVIL AND STRUCTURAL ENGINEERS Monarch House, Barton Lane, Abingdon, Oxon, OX14 3NB Tel: 01235 555173 Fax: 01235 523226
Project		Bodicote, Banbury	
Title	Scale	Date	Drawing No.
Site-Wide Lighting Design	1:500 @A1	Sept' 2018	5692:P07
Checked	Drawn	Rev	
KTG	AJW	–	

SECTION 104 - NOT APPROVED
SECTION 38 - NOT APPROVED

© This drawing is the copyright of Michael A Jennings Associates Limited and may not be copied, altered or reproduced in any way without their permission.