

**APPENDIX 9.1(A): CULTURAL HERITAGE GAZETTEER
BUILT HERITAGE WITHIN THE AIRBASE**

Explanation of References used within this Gazetteer:

In examples where information about a building has been crossed through, this shows a building which has been demolished.

A5

ACTA, Oxford Archaeology and The Tourism Company *Former RAF Upper Heyford Conservation Plan* (2005)

(3) Volume 3: Gazetteer and Appendices

(Oax) OA reference number within Gazetteer

ACTA 2005

ACTA *Former RAF Upper Heyford Airbase: Landscape South of the Cold War Zone* (2006)

The number following the reference indicates the Character Area within the 2006 report, which has been changed for the purposes of this Assessment (i.e - 4C).

RE6

Roger Evans Associates Ltd. *Heyford Park Building Appraisal* (2006)

The number followed by a hash and a further number refers to the area and building number within this report (i.e 9/234 is Area 9, building 234)

NOC

Documents held by NOC within Heyford Park House

u/d

Undetermined

OA Ref.	Scheduled/ Listed	Building Number	Function	Date	Building Description	Reference
COLD WAR LANDSCAPE						
OA1 CHARACTER AREA 1: CENTRAL AIRBASE						
OA1A Character Area 1A: Central Runway						
	Runway	N/A	Runway, taxiway, and hardstanding	1940s- 1980s	Concrete runway	A5(3) OA14
OA1B Character Area 1B: Central Plateau						
OA1B.1	Listed Grade II (no. 1392509)	234	55th Squadron Headquarters	1953	'Soft' area at front is single storey red brick, and 'hard' area at rear of hardened concrete	A5(3) OA6. RE6 9/234
OA1B.2		3015 - 3021, 3023, 3028 - 3032 & 3035	Hardened aircraft shelters	1979	Barrel vault with large sliding doors, constructed from corrugated arches and covered with reinforced concrete. Designed to hold a single aircraft.	A5 (3) OA9. RE6.9/3015, 3016, 3017, 3018, 3019, 3020, 3021, 3023, 3028, 3029, 3030, 3031, 3032, 3035
OA1B.3		1372	Hush House (Engine testing)	1984	Stainless steel with sound absorbent lined walls, with silencer for jet efflux to rear. Sliding doors and arch roof.	A5(3) OA13. RE6, 9/1372
OA1B.4		249	Munitions storage building	1973	Steel frame hangers with profile metal sheet cladding. Three bay with eight sliding doors in each bay.	A5(3) OA15. RE6, 9/249
OA1B.5		221	Aircraft storage building	1973	Steel frame hangers with profile metal sheet cladding. Three bay with eight sliding doors in each bay.	A5(3) OA15. RE6, 9/221
		238	Storage or administration (part of the 55th squadron complex)	1940	Concrete panelled building	A5(3) OA6. RE6, 9/238
		309	Store	1981	Concrete walls	RE6, 9/309
		UH55	unknown	u/d	u/d	
		306	Tower	1981	Brick, tiled roof	NOC

Archaeology and Cultural Heritage, Appendix 9.1 (A)

		391, 397	Small structure adjacent runway/radar	1981	Brick, tiled roof	RE6, 8/391, 397. NOC
		3109a, 3109b	Emergency barriers	u/d	Not accessible	RE6, 8/3109a, 3109b
		338, 225, 253, 307	Generator	1959, 1959, 1973, 1981	Brick walls with asphalt flat roof	RE6, 8/338, RE6 9/225, RE6, 9/253, RE6, 9/307
		UH79	u/d	u/d	u/d	
		UH62	Storage tank	u/d	Steel tanks set within a high concrete enclosure	RE6, 9/UH62
		247, 248, 262, 1388, 1405	Substation	1940, 1940, 1973, 1984, 1973	Concrete walled enclosure with chain link fence	RE6, 9/247, RE6, 9/248, RE6, 9/262, RE6, 9/1388, RE6, 9/1405
		239	55th Amu Equipment storage building (part of the 55th squadron complex)	1971	Steel frame and cladding on a concrete plinth, with double sliding doors	A5(3) OA6. RE6, 9/239
		3208	Workshop	1986	Brick walls with metal pitched roof	RE6, 8/3208
		233	Reconnaissance (part of the 55th squadron complex)	1957	Flat roof breeze block, surrounded by concrete blast walls housing four aerals	A5(3) OA 6. RE6, 9/233
		UH63	EWS tank		High enclosure of metal chain fence	RE6, 9/UH63
		231, 255	Boiler house	1940, 1973	Brick with steel windows and asphalt roof	RE6, 9/231, RE6, 9/255
		237	Storage or administration (associated with 55 th Squadron Headquarters)	1950	Steel frame, metal cladding with apex roof	A5 OA6. RE6, 9/237
		3102, 3200 - 3203	Tanker bay (house petrol vehicles)	1980, 1985	Concrete walls, large steel double doors, flat roof (3203- 1985)	A5(3) OA18. RE6, 9/3102, 3200,3201, 3202,3203
		3209	Squadron Administration Office	1985	Red brick bungalow	A5(3) OA15
		226	Tanker bay	1980	Concrete walls, flat roof and large steel doors.	RE6, 9/226
		POL 13	Petrol storage tank	1950s-1970s	Petrol Mounds consisting of large grassed over bank	A5(3) OA18
		219 POL 10, 229, 283, 284 POL 14, 274 POL 3	Fuel storage tank/ Petrol oil and lubricant	1961, 1969,	Concrete enclosure / Concrete wall surrounding fuel tanks	RE6, 9/229, RE6, 9/283, RE6, 9/284 POL14, RE6, 8/274

			site	1961, 1961, 1961		
		UH65	Pump	u/d	Blockwork surrounding wall enclosing pumps	RE6, 9/UH65
		3206	Squadron Administration Office	1986	Brick bungalow, metal pitched roof and windows	A5(3) OA15
		198	Fuel storage tank	1981	Concrete wall only	NOC
		POL 22	Petrol storage tank	u/d	Petrol Mounds consisting of large grassed over banks	RE6, 9/POL22
		395, 3218	Sewage pumping station & tank	1986	Brick flat concrete roof, semi circular tank in plastic or fibre glass housing	RE6, 9/395, RE6, 8/3218
		UH70	u/d	u/d	u/d	
		227	Store	1945	Brick walls with metal windows. Asphalt flat roof.	RE6, 9/227
		182, 186	Pill Box	1988	Concrete structure	RE6, 8/182,186
		330	Car store (fire training)	1973	Concrete fire practice tower	RE6, 8/330
		UH26	u/d	u/d	u/d	
		275	Electric sub-station	1940	Surrounded by concrete walls	RE6, 8/275
OA1C Character Area 1C: Quick Reaction Alert Area						
OA1C.1	Area 1C is a Scheduled Monument (no. 30906-01).	3001-3009	Hardened aircraft shelters	1979	Barrel vault with large sliding doors, constructed from corrugated arches and covered with reinforced concrete. Designed to hold a single aircraft.	A5(3) OA9 OA2. RE6.9/3001-3009
OA1C.2		2010	Hardened crew quarters	1979	Single storey, flat roof including two taller sections with blast proof vents. Includes a bunkroom and burger car	A5(3) OA9. RE6.9/2010. NOC
OA1C.3		UH25,UH 76, 3103	Substation	u/d	Metal profiled sheet enclosure	RE6, 9/3103, RE6, 9/UH25
OA1C.4		3104	Reserved Fire Truck Facility (RFTF)	1979	Hardened, flat roofed concrete with blast wall and gun turrets	A5(3) OA2
OA1C.5		3105	Brunswick watch tower	1979	Steel	A5(3) OA 2. RE6, 9/3105. NOC
OA1C.6		UH24	Access hatch	u/d	Metal cylinder with hatch	RE6, 9/UH24
OA1C.7		UH22	Observation tower	u/d	Steel framed tower with flat roofed metal clad observation room	RE6, 9/UH22
OA1C.8		281 POL 23b, 285 POL 23a	Fuel storage tank	1974	Low level structures next to earth mound	RE6, 9/281 POL 23b, 285 POL 23a
		3100	Entry Control Point	1979	Single storey concrete, rectangular in plan with a flat roof housing a monitoring area	A5(3) OA2
		UH23	Gatehouse*	u/d	Concrete walls and asphalt roofing	RE6, 9/UH23

OA1D Character Area 1D: The South Aircraft Shelters						
OA1D.1		2001 - 2009	Victoria Alert Complex	1972	Steel frame, corrugated metal cladding to walls and roof is corrugated white asbestos sheeting. Structures are open at both ends	A5 (3) OA11. RE6, 8/2001, 2002, 2003, 2004, 2005, 2006, 2007, 2008, 2009
OA1D.2	Listed Grade II (no. 495960)	340	Control tower	1953	Red brick, two storey with crittal windows and a central bay	A5 (3) OA10 RE6, 8/340
OA1D.3		335	Nose dock	1959	Aluminium girder wall frames supporting a cantilever roof framework, with support main hangar doors (in 14 divisions)	A5 (3) OA4 RE6, 8/335
OA1D.4		357	Operation building for Victoria Alert Complex	1972	Large two storey brick building with a tiled roof and wooden framed windows. Houses office and sleeping quarters	A5 (3) OA11 RE6, 8/357
OA1D.5		336	Aircraft hangar (washing)	1973	Metal clad with brick base and concrete floor	A5 (3) OA16
OA1D.6		337	Flight Line Fire Station	1953	Large building with metal cladding	RE6, 8/337. NOC
OA1D.7		1368	Hush House	1982	Steel frame with sheet metal cladding, and metal pitched roof. Silencer for jet efflux at rear	A5 (3) OA13. RE6, 8/1443, 1368
OA1D.8		1443	Engine Test Cell	1980s	Single storey, rectangular in plan, metal clad elevations, concrete floor and galvanised trusses	A5 (3) OA12
OA1D.9		366	Fuel Storage and Maintenance	1960s	Two bay, metal clad, front sliding doors with eight doors to each bay	A5 (3) OA16
		351	Water tank	1967	Sunken concrete tank	RE6, 8/351
		UH30	Water tank	u/d	Steel pressed panels on tank on 1 beams on the top of brick walls	RE6, 8/UH30
		UH31, UH32	Store	u/d	Metal clad steel frame on concrete slab	RE6, 8/UH31, UH32
		311	Office	1981	Brick structure	RE6, 8/311
		341	Office	1939	Prefabricated unit	RE6, 8/341
		368W	Office	1968	Single storey brick building	RE6, 8/368W
		3205	Squadron admin	1986	Brick walls with metal pitched roof	A5 (3) OA 15. RE6, 8/3205
		314	Radar bunker	1981	Fibre glass and metal box, wall only, no roof.	RE6, 8/314. NOC
		310	Substation	1981	Small brick structure/flat roof	RE6, 8/310. NOC
		332	Electricity substation	1939	u/d	NOC
		342	Operations building	1950s	Single storey, red brick, crittal windows and painted white	A5 (3) OA16. RE6, 8/342
		358	Office/admin	1968	Brick/flat roof	NOC

		5022	Aeroclub structure	1970	Prefabricated single storey unit with asphalt roof	A5 (3) OA11. RE6, 8/5022
		359	ECP for the Victoria Alert Complex	1972	Red bricks on a concrete plinth with a flat concrete roof	A5 (3) OA11. RE6, 8/359
		360	Brunswick Watch Tower	1970	Steel	A5 (3) OA11
		UH18	u/d	u/d	u/d	u/d
		UH19	Sub-station		Enclosed by fence	RE6, 8/UH19
OA1E Character Area 1E: Southwest HASs						
OA1E.1		3043 - 3047	Hardened aircraft shelters	1979	Barrel vault with large sliding doors, constructed from corrugated arches and covered with reinforced concrete. Designed to hold a single aircraft.	A5 (3) OA9. RE6, 8/3043, 3044, 3045, 3046, 3047
		181	Pillbox	1983	Concrete structure	RE6, 8/181
		UH29	Store	u/d	Concrete block walls and metal sheet pitched roof	RE6, 8/UH29
		1848	Bunker	u/d	Sunken into the ground	RE6, 8/1848
		1440	Substation	1979	Concrete walled enclosure	RE6, 8/1440
		3210	Squadron Administration	1985	Single storey red brick bungalow	A5 (3) OA 16. RE6, 8/3210
		UH27	Tank	u/d	Poured concrete holding tank for water	RE6, 8/UH27
		UH28	Store	u/d	Steel frame with metal cladding on a concrete slab.	RE6, 8/UH28
OA2 CHARACTER AREA 2: RUNWAY WEST TERMINAL						
OA2.1		NA	Runway	1950	Hardstanding	A5 OA14
OA2.2			Perimeter road and trackway	u/d	Hardstanding	
		270, 269 POL 24	Fuel storage tank	1961, 1974	Earth mounds over tanks, concrete enclosures	RE6, 8/269, 270
		POL 1	Petrol oil and lubricant site	1961	Fuel storage tanker	A5(3), OA18
		9347	u/d	u/d	u/d	
		252	Miss.	1989	Concrete	NOC
OA3 CHARACTER AREA 3: RUNWAY EAST TERMINAL						
OA3.1		NA	Runway	1950s	Hardstanding	A5 OA14
OA3.2		NA	North taxiway	1980s	Hardstanding	A5 OA14
OA3.3		NA	South taxiway	1950s	Hardstanding	A5 OA14
		927	Workshop	1988	Prefab/portable	NOC
		204	Miss.	1964	Brick/tiled roof	NOC
		1813	Concrete		Sunken into ground	RE6.9/1813

			pillbox/bunker			
		1827	Bunker		Sunken into the ground	RE6, 8/1827
		203	Technical equipment and housing	1989	Metal cabinet	RE6, 8/203
		3127A, 3127B	Runway barriers	1970s	Small huts used as emergency barriers	A5(3), OA16
		388	Wall (No roof)	1981	Concrete	NOC
		UH54				
		201	Generator and substation	1959	Brick walls, timber doors, metal window and concrete roof	RE6, 9/201
		928	Store	1988	Brick/tile roof	NOC
		1398, 1399	EWS	1979, 1975	Chain link fence and concrete post enclosure	RE6, 9/1398, RE6, 9/1399
		187	Pillbox	1988	Concrete walls with metal windows	RE6, 9/187
OA4 CHARACTER AREA 4: SOUTHERN CONVENTIONAL ARMS STORE						
		1109	Office	1982	Prefabricated building	RE6, 8/1109
		385	Fuel storage tank	1961	Concrete walls surround machinery and pumps	RE6, 8/385, 386
		UH53	WC portakabin	u/d	Portakabin	RE6, 8/UH53
		1111	Store	1977	Large metal clad building	RE6, 8/1111
		186	Pillbox	1988	Concrete walls with metal windows	RE6, 9/186
		1110	u/d	u/d	u/d	
		1102, 1103, 1105, 1106, 1113, 1114	Store (Less explosive ammunition)	1955, 1940, 1955, 1995, 1955, 1977	Single storey rendered brick buildings	RE6, 8/1102, 1103, 1105, 1106, 1113
		1107	EWS Tank	1950	18,000 gallon capacity tank	RE6, 8/1107
		1108	Maintenance building (repair munitions)	1972	Large metal clad building	RE6, 8/1108
		386	Fuel storage tank	1961	Concrete walls surround machinery and pumps	RE6, 8/385, 386
		1119	Generator	1991	Small concrete structure	RE6, 8/1119
		387	Sub-station	1940	Sub-station surrounded by concrete walls	RE6, 8/387
		1112	Store	1955	Rendered brick arched end	RE6, 8/1112
		1140	Shelter	1986	Earth mound over concrete walls	RE6, 8/1140
		UH51, UH52	EWS tank	u/d	Brick walls around pit, surrounded by concrete post	RE6, 8/UH51, UH52
		166 CAS		u/d		

		1158, 1159, 1160, 1161, 1162, 1163, 1164, 1165, 1166, 1167, 1168, 1169, 1170, 1171, 1172, 1173, 1174, 1175, 1176, 1177, 1178, 1179, 1180, 1181, 1182, 1183, 1184, 1185, 1186.	Southern Conventional Arms Store	1950s-1991	Concrete end wall with large double sliding steel doors, and an earth mound over the top	A5(3) OA17
		1601, 1602, 1603, 1604, 1605, 1606, 1607, 1608, 1609, 1610, 1611, 1612, 1613, 1614, 1615, 1616, 1617, 1618, 1619, 1620, 1621, 1622, 1623, 1624, 1625	Southern Conventional Arms Store	1991	Concrete end wall with large double sliding steel doors, and an earth mound over the top	A5 (3) OA17
		UH73	Blast/screening wall	u/d	Metal baffle wall to rear of fireworks store	RE6, 8/UH73
		1150	Water tank	1988	Concrete	NOC
		1141	Shelter	1986	Earth mound over concrete walls	RE6, 8/1141
		1153	Water tank	1967	Concrete	NOC
		1154	Water tank	1978	Concrete	NOC
		1115	Pallet store	1950	Concrete walled building	RE6, 8/1115
		1118	Water tank	1991	Concrete	NOC
OA5 CHARACTER AREA 5: NORTH EDGE						
OA5A Character Area 5A: Northern Bomb Store and Special Weapons Area						
OA5A.1		209	77th Squadron Headquarters	1954	1950s 'soft' section to front and late 1970s 'hardened' section to rear. Designed to be self sufficient and contains generating plant and air filters	A5 (3) OA6. RE6, 9/209
		UH 49, UH50	Observation tower	u/d	Concrete supports with observation room over	RE6, 9/UH49,50
		1007	Trigger store	1973	Concrete building, thought to be unique in England	A5(3) OA5
		1027	13- cell igloo	1971	Concrete retaining wall, metal double doors, covered in earth	RE6, 9/1027
		1038	8-cell igloo	1971	Concrete retaining wall, metal double doors, covered in earth	RE6 9/1038
	The Northern Bomb Store complex is a	212, 1007, 1008, 1023, 1026, 1028, 1029, 1030, 1031, 1032, 1033, 1034,	Northern Bomb Store	1953-1979	Metal clad roof and walls covered with earth	A5(3) OA5. RE6, 9/212, RE6, 9/1026- 1048, RE6, 9/1050

	Scheduled Monument (no. 30906-02)	1035, 1036, 1037, 1039, 1040, 1041, 1042, 1043, 1044, 1045, 1046, 1047, 1048, 1050				
		1001,1002, 1003, 1004, 1005	Special Weapons Area/Store	1953	Concrete grassed over structure with a blast wall	A5(3) OA5
		1870	u/d	u/d	Concrete enclosure with concrete roof on steel supports	A5(3) OA5. RE6, 8/1870
		214, 1061	u/d	1945, 1979	Small brick structure, Concrete enclosure with roof	RE6, 9/1061, RE6.9/1870.
		UH56, 1059, 1065	Substation	1977, 1979	Concrete walled enclosure	RE6, 9/UH56, RE6, 9/1059, RE6, 9/1065
		1060	Gatehouse	1979	Concrete walls and tower	A5(3) OA5. RE6, 9/1060
		1006	Detached igloo (Special weapons store)	1953	Concrete structure, grassed over with thick sliding doors and a blast wall	A5(3), OA5
		211, 1011	Workshop	1950s	Metal frame with metal cladding	A5(3) OA5. RE6, 9/211, 1006, 1011
		1010, 1080	Water tank	1952, 1978	Metal structure with large metal tank, metal railings attached to concrete	RE6, 9/1010, RE6, 9/1080
		1867, 1868, 1869, 1871	Turret		Concrete roof on steel supports. Sunken into munitions store mound	RE6.9/1867-69, 1871
		1009	Boiler room	1953	Brick walls and metal windows. Flat concrete roof	RE6, 9/1009
		208, 1025	EWS tank	1950, 1964	High enclosure of metal mesh fencing	RE6, 9/208, 1025
		207	Boiler house	1959	Brick with steel windows.	RE6, 9/207
		210	Office	1949	Metal cladding to walls and roof	RE6, 9/210
OA5B Character Area 5B: Plateau Edge						
OA5B.1		3013, 3014, 3022, 3024, 3025, 3026, 3027, 3033, 3034, 3056	Hardened aircraft shelters	1974/ 1979	Barrel vault with large sliding doors, constructed from corrugated arches and covered with reinforced concrete. Designed to hold a single aircraft.	A5 (3) OA9. RE6. 9/3013, 3014, 3022, 3024, 3025, 3026, 3027, 3033, 3034, 3056
OA5B.2		1319	Engine test cell	1959	Steel framed with metal clad walls and roof	RE6, 9/1319
		UH66	u/d	u/d	u/d	
		UH64, 220, 240	Substation	1973, 1940	Brick walls and concrete roof	RE6, 9/220, RE6, 9/UH64
		UH59	Storage tank	u/d	Steel tank on concrete supports	RE6, 9/UH59
		241 POL 15, 242 POL 16	Fuel storage tank	1961	Steel framed structure	RE6, 9/241 POL15, 242 POL 16

		3136	Tanker bay	1987	Concrete walls, large steel double doors and hatch, flat roof.	RE6, 9/3136
		UH60	Substation	u/d	Concrete walled enclosure	RE6, 9/UH60
		UH61	Store	u/d	Concrete block walls with metal roof	RE6, 9/UH61
		183	Pill box	1988	Concrete walls with metal windows	RE6, 9/183
OA 5C Character Area 5C: North Fringe						
OA5C.1		383	42nd Squadron headquarters	1984	1950s 'soft' section to front and late 1970s 'hardened' section to rear. Designed to be self sufficient and contains generating plant and air filters	A5 (3) OA6. RE6, 9/383
OA5C.2		216	Administrative building for the 77th Squadron	1964	Brick walls with metal cladding and blockwork.	RE6, 9/216
		UH57	EWS	u/d	High enclosure of metal chain link fence	RE6, 9/UH57
		215 POL 9	Fuel storage tank	1961	Concrete enclosure	RE6, 9/215 POL 9
		UH58, 1409	Substation	1973	Concrete walled enclosure	RE6, 9/UH58, RE6, 9/1409
		213	Store	1971	Brick walls, metal windows, timber doors and a flat asphalt roof	RE6, 9/213
		217	Electricity sub station	1964	Brick walls with pitched metal roof	RE6, 9/217. NOC
		202	Substation	1960	Chain link fence enclosure	RE6, 9/202
		421	Sewage pumping station	1988	Semi circular arched tank	RE6, 9/421
		321	Miss.	1981	Concrete	NOC
		185	Pill box	1988	Concrete walls with metal windows	RE6, 9/185
		3207	Bungalows used for administration by squadron	1985	Brick walls, metal windows. Metal pitched roof.	A5(3), OA15
		1808, 5066	Bunker	u/d	Sunken into ground	RE6.9/1808, 5066
		UH67	EWS tank	u/d	High enclosure of chain link fence on concrete posts	RE6, 9/UH67
		3055	Hardened aircraft shelter	1984	Barrel vault with large sliding doors, constructed from corrugated arches and covered with reinforced concrete. Designed to hold a single aircraft.	A5(.3) OA9, ARP96, P.56. NOC.
OA 5D Character Area 5D: Northwest Fringe						
OA5D.1		3052, 3053, 3054, 3055	Hardened aircraft shelters	1984	Barrel vault with large sliding doors, constructed from corrugated arches and covered with reinforced concrete. Designed to hold a single aircraft.	A5(3) OA9. RE6, 9/3052, 3053, 3055,
OA5D.2		3135	Warehouse	1986	Large rectangular warehouse, concrete blocks and metal clad	A5(3)OA15

		3101	Substation	1984	Concrete walled enclosure	RE6, 9/3101
		184	Pill box	1988	Concrete walls with metal windows	RE6, 9/184
		3145	Sewage pumping station	1984	Chain link fence enclosure, with internal pit	RE6, 9/3145
		3140	Workshop	1984	Brick walls with steel windows	RE6, 9/3140, RE6, 9/3145
		POL 17	Petrol oil and lubricant site	1950s - 1970s	Fenced enclosure	A5(3) OA18
		245a, 245b, 245c, 245d	Fuel storage tank	1961	Low level structures with brick walls and asphalt roofs	RE6, 9/245a, 245b, 245c, 245d
		251, 1439	Substation	1972, 1979	Brick walls with concrete roof	RE6, 9/251, RE6, 9/1439
		1865,1866	Bunker		Sunken into ground	RE6.9/1865, 1866
		3010, 3011, 3012	Hardened aircraft shelters	1974	Steel ribbed arches filled with reinforced concrete	ARP96, P.56. RE6 9/3010, 3011, 3012
		1802, 1803, 1804, 1807	Bunker	u/d	Sunken into ground	RE6, 9/1802, RE6,9/1803, RE6. 9/1804, RE6. 9/1807
OA6 CHARACTER AREA 6: SOUTHEAST HASs						
OA6.1		3036-3042	Hardened aircraft shelters	1978	Barrel vault with large sliding doors, constructed from corrugated arches and covered with reinforced concrete. Designed to hold a single aircraft.	A5 (3) OA9. RE6, 8/3038, 3040
OA6.2		370	79th Squadron Headquarters	1953	1950s 'soft' section to front and late 1970s 'hardened' section to rear. Designed to be self sufficient and contains generating plant and air filters	A5 (3) OA6. RE6, 8/370
OA6.3		3204	Bungalow used for administration by squadron	1986	Brick walls with metal pitched roof	RE6, 8/3204
		369	Office	1940	Steel frame with metal cladding to walls and metal pitched roof	RE6, 8/369
		368K	Workshop	1940	Single storey building with rendered walls. Brick/tiled roof.	RE6, 8/368k. NOC.
		362, 379	Substation	1940	Area surrounded by concrete walls	RE6, 8/362, 379
		375A POL 20, 375B POL 20, 375C POL 20, 375D POL 20	Petrol oil and lubricant site	1961	Fuel storage tank	RE6, 8/375,A,B,C&D/POL 20 . NOC
		372	Pit	1948	Sunken pit	RE6, 8/372. NOC
		1840	Administration structure	u/d	Single storey structure clad in wood	A5(3), OA15
		1841	Petrol oil and lubricant site	1950s-1970s	u/d	A5(3) OA18

		197	Sewage pump station	1945	Small brick structure	RE6, 8/197
		371	Administrative store (part of the 79th Squadron complex)	1935	Single storey timber building	RE6, 8/371
		367	Water tank	1950	Concrete	NOC
		UH75	u/d	u/d	u/d	
		399	Store	1940	Small building with blockwork walls	RE6, 8/399
		365 POL 5	Fuel storage tank	1961	Concrete wall surrounding fuel tanks	A5(3) OA18
		3036, 3037, 3039, 3041, 3042	Hardened Aircraft hanger	1978	Barrel vault with large sliding doors, constructed from corrugated arches and covered with reinforced concrete. Designed to hold a single aircraft.	A5(3) OA9, RE6, 8/3036, 3037, 3039, 3041, 3042
		376 POL25a, 377 POL25b	POL Grass petrol mound/ fuel storage tank	1974	Earth mound covering tanks	RE6, 8/376, 377
		1832	Bunker	u/d	Sunken into the ground	RE6, 8/1832
		UH17	Store	u/d	Blockwork, metal fasica and metal pitched roof.	RE6, 8/UH17
		UH20	u/d	u/d	u/d	
		382	POL structure	1961	Fuel storage tank	RE6, 8/382
		389	Electricity sub-station	1940	Sub-station surrounded by concrete walls.	RE6, 9/389
		1104	Store	1971	Single storey metal clad building	RE6, 8/1104
		180	u/d	u/d	u/d	
		3214	Sewage tank	1986	Semi circular tank in plastic or fibre glass housing	RE6, 8/3214
OA7 CHARACTER AREA 7: TANKER AREA						
		354	QEK Global Solutions workshop	1940	Steel industrial shed	RE6, 6/354
		381	Tanker garage	1980	Concrete walls with flat roof	RE6, 6/381
		POL 19	Petrol oil and lubricant site	1950s-1970s	u/d	A5(3), OA18
		352	Office	1980	Brick building with flat roof	RE6, 6/352
		385	Fuel storage tank	1961	Small metal structure	RE6, 6/385
		360	Control tower (Victoria alert complex)	1973	Brunswick steel watch tower	RE6, 8/360, A5(3)OA11
		361	Substation	1940	Surrounded by blockwork walls	
		424	Store		Large building with blockworth walls and metal clad	RE6, 8/424
		353	Administration structure	1935	Concrete with flat roof	A5(3), OA15

		88	Workshop	1986	Brick/tiled roof	NOC
OAS CHARACTER AREA 8: SOUTHWEST EDGE						
OAS8 Character Area 8A: Built up Edge						
OAS8.1	Listed Grade II (nos. 490616, 490929 & 490931)	325, 327 & 328	Nose docking sheds	1959	Constructed from 10 aluminium girder wall frames supporting cantilever roof framework, which support main hangar doors.	A5(3) OA16. RE6, 8/325, 327, 328
		292	Aircraft maintenance (Jet Engine Repair)	1971	Large brick and metal building	A5(3) OA16. RE6, 8/292
		293	Workshop (Flight Simulator Building)	1971	Concrete frame with concrete slabs and piers exposed. Metal clad roof.	A5(3) OA16. RE6, 7/293
		294	Office (Used by 20th Fighter Wing Operations Group)	1971	Brick walls with shallow pitched metal roof.	A5(3) OA16. RE6, 7/294
		300	Collaboration and administration	1953	A series of interlinking buildings including the ECM (Electronic Counter Measure)	A5(3) OA16
		300B, 300C	workshop	1953	Brick plinth with render panels above. Metal pitched roof.	RE6, 7/300B, 300C. NOC
		300A, 300D	Office	1953	Brick plinth with render panels above. Metal pitched roof.	RE6, 7/300A,300D
		300E	Plant	1953	Blockwork walls, timber weather boarding	RE6, 7/300E. NOC
		301	Generator	1953	Rendered brick walls with flat asphalt roof	RE6, 7/301
		301a	Storage tank	1953	Metal on concrete plinth	RE6, 7/301a. NOC
		271, 276, 329	Substation	1940, 1962	Concrete walled enclosure, Small structure	RE6, 8/271, 276, 329
		297, 296	Kennels and housing, Dog training compound	1971	Brick building	RE6, 8/297, 296
		195	Pillbox/ Main Gatehouse	1988	Red brick building with pitched roof	RE6, 8/195
		286	Gas chamber	1967	Red brick building	RE6, 8/286
		UH68	Entry guard box	u/d	Small building with brick walls and tiled roof	RE6, 8/UH68
		268	Office/admin (DEB building)	1988	Brick structure	RE6, 8/268
		416	Mast	1988	Steel framed mast	RE6, 8/416
		344	Water tank	1967	Sunken concrete tank	RE6, 8/344

		1403	Water tank	1959	Bricked enclosure with steel tank	RE6, 8/1403
		POL 2	Storage tank/ Grass bunker	u/d	Various small buildings - metal shed, metal structure, concrete bunker	RE6, 8/POL 2
		279	Tanker bay	1980	Concrete walls and flat roof	RE6, 8/279
		UH34	u/d	u/d	u/d	
		205	Office	1983	Brick structure	RE6, 8/205
		323	Office	1962	Brick structure in poor condition	RE6, 8/323
		324	Administrative structure	1971	Large brick structure	RE6, 8/324
		295	Boiler house	1971	Corrugated metal clad building	RE6, 8/295
		UH35	Store		Concrete frame and panelled building	RE6, 8/UH35
		UH36	u/d	u/d	u/d	
		POL 21A 392	Petrol and oil lubricant site	1961	Earth mound covering concrete tanks	RE6, 8/392
		POL 21B 394, POL 21C 393	Petrol and oil lubricant site	1950s-1970s	u/d	A5(3) OA18
		293a	Gatehouse	u/d	Brick walls with pitched, tiled roof	RE6, 7/293a
		UH33	Electric substation	u/d	Corrugated metal baffle walls	RE6, 7/UH33
OA8B Character Area 8B: Avionics and HASS						
OA8B.1	Scheduled Monument (no. 30906-03)	299	Avionics Maintenance Facility	1980	A hardened concrete semi-sunken structure with two blast doors protected by a sunken, open walkway. Extended in 1982/3.	A5 (3) OA3. RE6, 8/299
OA8B.2		3048 - 3051	Hardened aircraft shelters (HASS)	1979	Barrel vault with large sliding doors, constructed from corrugated arches and covered with reinforced concrete. Designed to hold a single aircraft	A5(3) OA9, RE6, 8/3048, 3049, 3050, 3051
		259, 260	79th Combat Airfight Group Storage	1935	Portakabin and metal industrial sheds	RE6, 8/259,260
		UH21	Fuel pumps	n/d	Plastic booth next to pumps	RE6, 8/UH21
		1880	m/d	u/d	u/d	
		1859, 1860	Bunker	u/d	Sunken into the ground	RE6, 8/1859, 1860
		289	Sewage pump station	1980	Small brick structure	RE6, 8/289
		UH69	Substation	u/d	Enclosure of high chain link fence	RE6, 8/UH69
LANDSCAPE SOUTH OF THE COLD WAR ZONE						
OA9 CHARACTER AREA 9 SCHOOL HUTS						
		804-815	Classroom units	1939	Rendered brick with pitched asbestos roofs, and metal windows.	ACTA 2006 1. p.13. RE6 4/804, 810, 811, 815,
		821, 822, 827, 828,	Classroom units	1939	Rendered brick with pitched asbestos	ACTA 2006 1. p.13. RE6 4/821,

		832, 833, 837, 846, 850, 852, 856, 858, 859, 861, 866, 868, 873, 874, 879, 880, 885, 891, 892, 894, 898, 900, 904, 905.			roofs, and metal windows.	822, 827, 828, 832, 833, 837, 846, 850, 852, 856, 858, 859, 861, 866, 868, 873, 874, 879, 880, 885, 891, 892, 894, 898, 900, 904, 905
		826	Miss.	1973	Buff brick walls with monopitch asbestos roof.	ACTA 2006 1. p.13. RE6 4/826. NOC
		886	Gymnasium	1971	Brick gable ends and corrugated side walls and roof	ACTA 2006 1. p.13. RE6 4/886
		867	Former school/training	1939	Red brick walls with pitched asbestos roof.	ACTA 2006 1. p.13. RE6 4/867
		UH6	Sub station	u/d	Brick walls with asphalt roof	ACTA 2006 1. p.13. RE6 4/UH6
		UH74	Water Tower	1972	Metal support tower to metal tank over	RE6 4/UH74
OA10 CHARACTER AREA 10: SPORTS FIELDS AND LARGE BUILDINGS						
OA10A Character Area 10: Sports Fields						
OA10A.1		583	Gymnasium	1976	Pebble dash concrete walls with flat roof.	ACTA 2006 2A. p. 13. RE6 3/583
		515	Former leisure	1983	Timber frame with walls removed. Tiled roof.	ACTA 2006 2A. p. 13. RE6 3/515
		527	Electrical sub station	1976	Timber panels with concrete posts.	ACTA 2006 2A. p. 13. RE6 3/527
		528	Store	1982	Pebbled dashed walls and corrugated roof.	ACTA 2006 2A. p. 13. RE6 3/528
		570	Former store	u/d	Blockwork walls and metal monopitch roof.	ACTA 2006 2A. p. 13. RE6 3/570
		567, 577, 595, 599	Baseball dugouts	1977, 1982, 1977, 1980	Blockwork walls with monopitch roof.	ACTA 2006 2A. p. 13. RE6 3/567, 577, 595, 599.
		578	Fuel inlet	1955	Brick with concrete roof	ACTA 2006 2A. p. 13. RE6 3/578. NOC.
		584	Store	1982	Pebble dash concrete walls with flat roof.	ACTA 2006 2A. p. 13. RE6 3/584
		590	Waste disposal pit	1940	Pit surrounded by 1.8m high fence.	ACTA 2006 2A. p. 13. RE6 3/590
		597	Waste disposal pit	1940	Pit surrounded by 1.8m high fence.	ACTA 2006 2A. p. 13. RE6 3/597
		UH3	Sub station	u/d	Timber panel fencing supported by	ACTA 2006 2A. p. 13. RE6

					concrete posts.	3/UH3
		UH5	Former viewing tower	u/d	Blockwork walls with asphalt roof.	ACTA 2006 2A. p. 13. RE6 3/UH5
		592	Tennis courts	1980	Asphalt	ACTA 2006 2A. p. 13. NOC
		UH15	Office	u/d	Blockwork walls with metal pitched roof.	ACTA 2006 2B. p.14. RE6 3/UH15
		579	B-house	1980	Steel frame, metal cladding to walls	ACTA 2006 2B. p.14
OA 10B Character Area 10B: Superstore/ Hospital						
		581	Former supermarket	1975	Blockwork walls with flat roof.	ACTA 2006 2B. p.14. RE6 3/581
		582	Former hospital 60 bed	1982	Pebble dash panel walls with flat roof.	ACTA 2006 2B. p.14. RE6 3/582
		566	Former store	1989	Blockwork walls with metal monopitch roof.	ACTA 2006 2B. p.14. RE6 3/566
OA11 CHARACTER AREA 11: SOUTH RESIDENTIAL BUILDINGS						
OA11A Character Area 11A: South Bungalows						
		640, 649, 677, 733, 742,	Semi-detached single story housing	1957	Concrete panel walls with tiled roof.	ACTA 2006 3A. p.14. RE6 2/640, 649, 677, 733, 742
		642, 644, 655,656, 657, 659, 661, 663, 664, 670, 671, 674, 675, 682, 684, 868, 688, 692, 700, 701,710, 714, 718, 730, 731, 732, 735, 740, 744, 750, 751, 752, 753, 754, 755, 756, 757, 759, 765, 767, 768, 769, 770, 771	Semi-detached single story housing	1957	Concrete panel wall construction with tiled roof.	ACTA 2006 3A. p.14. RE6 2/642, 644, 655,656, 657, 659, 661, 663, 664, 670, 671, 674, 675, 682, 684, 868, 688, 692, 700, 701,710, 714, 718, 730, 731, 732, 735, 740, 744, 750, 751, 752, 753, 754, 755, 756, 757, 759, 765, 767, 768, 769, 770, 771
		712	Semi-detached single story housing	1957	Concrete panel wall construction with tiled roof.	ACTA 2006 3A. p.14. RE6 2/712
		646, 648, 650, 651, 652, 653, 662, 665, 666, 667, 668, 669, 681, 683, 685, 687, 690, 691, 702, 703, 704, 705, 706, 707, 709, 711, 713, 715, 716, 717, 720, 721,	Semi-detached single story housing	1957	Concrete panel wall construction with tiled roof.	ACTA 2006 3A. p.14. RE6 2/646, 648, 650, 651, 652, 653, 662, 665, 666, 667, 668, 669, 681, 683, 685, 687, 690, 691, 702, 703, 704, 705, 706, 707, 709, 711, 713, 715, 716, 717, 720, 721, 722, 723, 724, 725, 726, 728, 736, 745, 746,

		722, 723, 724, 725, 726, 728, 736, 745, 746, 747, 760, 761, 762, 763, 764, 766, 772, 773, 774, 775, 776, 778, 780				747, 760, 761, 762, 763, 764, 766, 772, 773, 774, 775, 776, 778, 780
		673, 738	Electric sub-station	1950	Enclosure constructed from timber fence panels.	ACTA 2006 3A. p.14. RE6 2/673, 738
		779	Sewage pump	1989	Rendered brick with timber, tiled roof.	ACTA 2006 3A. p.14. RE6 2/779
OA11B Character Area 11B: Mixed Use Area						
OA11B.1		572	Chapel	1961	Beige brindled brick walls with flat asphalt roof.	ACTA 2006 3B. p.15. RE6 2/572
OA11B.2		549	Community centre (ancillary building)	1945	Steel frame with brick piers and pebble dash. Metal clad roof and gable ends.	ACTA 2006 3B. p.15. RE6 2/549
OA11B.3		543	Housing (Warrant Officers)	1925	Brick walls, and tiled roof.	ACTA 2006 3B. p.15. RE6 2/543, 544
		544	Housing	1925?	Brick walls, and tiled roof.	ACTA 2006 3B. p.15. RE6 2/543, 544
		547	Former launderette/store	1935	Red brick with timber/tiled pitched roof	ACTA 2006 3B. p.15. RE6 2/547
		546	Former credit union	1977	Blockwork walls with asphalt roof.	ACTA 2006 3B. p.15. RE6 2/546
		291	Water tower	1972	Metal frame supporting metal tank	ACTA 2006 3B. p.15. RE6 2/291
		548	Electric sub station	1940	Enclosure of timber fence panels	ACTA 2006 3B. p.15. RE6 2/548
		542	Electric sub station	1940	Enclosure of timber fence panels	ACTA 2006 3B. p.15. RE6 2/542
		546X	Housing	1930	Red brick walls with pitched, tiled roof	ACTA 2006 3B. p.15. RE6 2/546X
		551	Water pump	1935	Brick construction with flat asphalt roof	ACTA 2006 3B. p.15. RE6 2/551
		552	Water tanks (2 no.)	1952	Metal containers with brick plinth	ACTA 2006 3B. p.15. RE6 2/552
		565, 573	Water tank	1979, 1987	Poured concrete construction with concrete panels.	ACTA 2006 3B. p.15. RE6 2/565, 573
		568	Former waste disposal	1945	Poured concrete pits.	ACTA 2006 3B. p.15. RE6 2/568
		588	Store	1975	Concrete blockwork walls with asbestos roof.	ACTA 2006 3B. p.15. RE6 2/588.
		UH2	Sub-stations	n/d	2-structures with brick walls and asphalt roof.	ACTA 2006 3B. p.15. RE6 2/UH2
OA 11C Character Area 11C: Semi-Detached Houses						
		553-562	Semi-detached housing	1953	Brown brindled brick with timber, tiled pitched roof.	ACTA 2006 3B. p.15. RE6 2/553-562
OA11D Character Area 11D: Carswell Circle North						
		535- 540	Terraced housing	1925	Terraced units of rendered brick and	ACTA 2006 3D. p.15. RE6

			(Married Airmen)		tiled roof.	2/535-540
OA11E Character Area 11E: Carswell Circle South						
		530, 531, 533, 534	Terraced housing	1925	Terraced red brick housing with tiled roofs	ACTA 2006 3E. p.16. RE6 2/530, 531, 533, 534
		532	Electric sub-station	1949	Part brick, part timber enclosure.	ACTA 2006 3E. p.16. RE6 2/532
OA12 CHARACTER AREA 12: BARRACKS AND INSTITUTIONS						
OA12A Character Area 12A Store/ Petrol Station						
		459	Single Sergeants Quarters	1925	Red bricked with tiled roof.	ACTA 2006 4B. p.17. RE6 1/459.
		492	Store	1985	Brown brick walls and flat metal roof.	ACTA 2006 4B. p.17. RE6 1/492
		493	Former petrol station	1985	Metal canopy and brick booth	ACTA 2006 4B. p.17. RE6 1/493
		460	Bus shelter	1939	Brick with tiled roof	ACTA 2006 4B. p.17
OA12B Character Area 12B: Parade Ground Buildings						
OA12B.1		457 (partially demolished)	Sergeants' Mess	1925	Red bricked with tiled roof	ACTA 2006 4B. p.17. RE6 1/457
OA12B.2		455 (partially demolished)	The Institute	1925	Red bricked with tiled roof.	ACTA 2006 4B. p.17. RE6 1/455.
		474	Dining room and Cookhouse	1925	Red brick walls with tiled roof.	ACTA 2006 4B. p.17. RE6 1/474
		475	Ration store and shop	1925	Red brick walls with tiled roof.	ACTA 2006 4B. p.17. RE6 1/475
		450, 466, 471, 480, 483, 440	Barracks Blocks (Barrack block type C)	1925	Red bricked buildings with concrete floors and tiled roof.	ACTA 2006 4B. p.17. RE6 1/466,471,480, 483
		485	Type B barrack block	1925	Red brick walls with tiled roof.	ACTA 2006 4B. p.17. RE6 1/485
		465	Decontamination Building	1935	Red brick	ACTA 2006 4B. p.17. RE6 1/465
		467	Boiler house (Central Heating Station)	1925	Red brick with concrete roof.	ACTA 2006 4B. p.17. RE6 1/467.
		472A	Mess Complex	1939	Concrete block walls with metal doors and windows, and a flat roof.	ACTA 2006 4B. p.17. RE6 1/472A
		440b	Boiler room	u/d	Brick on concrete plinth with flat roof	ACTA 2006 4B. p.17
		442	Child care centre	1984	Red brick walls with timber and tiled roof	ACTA 2006 4B. p.17
		449, 484, 485, 470	Disused building	1940/ 1977	Metal clad walls over timber construction.	ACTA 2006 4B. p.17. RE6 1/449, 484
		454	Water tank	1950	Timber fence enclosure	ACTA 2006 4B. p.17. RE6 1/454
		486	Offices	1976	Timber prefabricated unit with flat asphalt roof.	ACTA 2006 4B. p.17. RE6 1/486
		461	Pre-fabricated cabin and metal sheds	1939	Prefabricated cabin and metal sheds.	ACTA 2006 4B. p.17. RE6 1/461.

		468	Office/store	1940	Prefabricated unit with metal clad walls and metal roof.	ACTA 2006 4B. p.17. RE6 1/468.
		472B	Recreation centre	1939	Concrete plinth with panel cladding to walls.	ACTA 2006 4B. p.17. RE6 1/472B
		476	Electric sub station	1950	Red bricked enclosure	ACTA 2006 4B. p.17. RE6 1/476
		481	Thrift shop	1973	Timber cladding panels to walls. Flat roof.	ACTA 2006 4B. p.17. RE6 1/481
		529	Former Leisure unit	1935	Metal clad walls, flat concrete roof.	ACTA 2006 4B. p.17. RE6 1/529
		UH8	u/d	u/d	Mixed brick construction with flat roof.	ACTA 2006 4B. p.17. RE6 1/UH8
		UH11	Portakabin		Portakabin	ACTA 2006 4B. p.17. RE6 1/UH11
OA12C Character Area 12C: West Barracks						
		445, 593, 594, 596, 598	Barracks blocks	1970, 1972	Red brick and blockwork walls with flat roof.	ACTA 2006 4C. p.17. RE6 1/445, 446, 593, 594, 596, 598
		441	Boiler house	1970	Brown brick walls, partially metal clad	ACTA 2006 4C. p.17. RE6 1/441
		500	Barracks blocks (Type H Barrack)	1926	Barrack accommodation, brick walls. Tiled roof.	ACTA 2006 4C. p.17. NOC
		502	Offices	1939	Building clad in clay chip rendered panels, concrete tiles on roof.	ACTA 2006 4C. p.17. RE6 1/502
		UH10	Sub station	u/d	Timber fence panels supported by concrete posts.	ACTA 2006 4C. p.17. RE6 1/UH10
OA12D Character Area 12D: 1930s Area						
		488	The Institute – Lamplighter Inn/Dining facility	1935	Red brick walls with flat concrete roof.	ACTA 2006 4D. p.18. RE6 1/488
		489, 498 & 500	Barracks blocks (Type H Barrack)	1926	Red bricked building with tiled roof.	ACTA 2006 4D. p.18. RE6 1/489, 498.
		443	Store	1971	Brown brick building with flat roof	ACTA 2006 4D. p.18. RE6 1/443
		444	Building	1982	Prefabricated timber unit	ACTA 2006 4D. p.18. RE6 1/444
		487	Electric sub station	1940	Enclosure with metal fence	ACTA 2006 4D. p.18. RE6 1/487
		446	Barracks block	1970, 1972	Red brick and blockwork walls with flat roof.	ACTA 2006 4C. p.17. RE6 1/446
		491	Store	1935	Brown brick walls with timber gables and timber pitched roof	ACTA 2006 4D. p.18. RE6 1/491
		UH9	Generator		Brick walls with flat roof.	ACTA 2006 4D. p.18. RE6 1/UH9
OA13 Character Area 13: Eastern Huts						
		400-405, 407-409	Office	1939	Prefabricated units/Part brick walls with corrugated roof	ACTA 2006 5. p.18. RE6 1/400-405, 407-409

		406	Incinerator	1982	Concrete slab, high brick wall enclosure	ACTA 2006 5. p.18
		410	Boiler house	1939	Brick walls with sheet metal roof	ACTA 2006 5. p.18. RE6 1/410
		425	Electrical sub-station	1952	Brick walls with metal vents	ACTA 2006 5. p.18 RE6 1/425
		UH12	Tank	u/d	Metal tank surrounded by timber boards and chicken wire	ACTA 2006 5. p.18. RE6 1/UH12
		UH13	Office	u/d	Corrugated metal clad walls with pitched metal roof.	ACTA 2006 5. p.18. RE6 1/UH13
OA14 CHARACTER AREA 14: TECHNICAL AREA						
OA14A Character Area 14A Aircraft Sheds						
OA14A.1		172, 345, 350, 151, 315, 320	Type A Aircraft sheds	1925	Steel frame, concrete infill, asbestos multi pitched roof.	ACTA 2006 6A,6B. p.19. RE6, 7/172, 345, 350
OA14A.2		158	Night Flying Equipment Store	1935	Painted brick walls with parapet to flat roof.	ACTA 2006 6A,6B. p.19. RE6, 7/158
OA14A.3	Scheduled Monument (no.30906-05)	126	Battle Command Centre	1980	Hardened concrete, single storey with a flat roof and blast walls. Designed to be self sufficient and contains a generating plant and air filters	A5 (3) OA7. ACTA 2006 6A,6B. p.19. RE6, 7/126. NOC
		130	Main Workshop	1940	Brickwork with pitched metal roofs	ACTA 2006 6A,6B. p.19. RE6, 7/130
		171	Petrol Tanker Sheds	1935, 1948	Brick walls with parapet to flat roof	ACTA 2006 6A,6B. p.19. RE6, 7/171
		316	Petrol Tanker Sheds	1948	Brick walls with parapet to flat roof	ACTA 2006 6A,6B. p.19. RE6, 7/316
		89B	Blast separation wall	1939	Brick wall with concrete buttresses	RE6, 6/89B. NOC
		89C	Containers (2 no)	1939	Metal transport containers	RE6, 6/89C. NOC
		89	u/d	1939	Brick structure	RE6, 6/89
		81	u/d	1940	Concrete structure	RE6, 6/81
		318	Office	1950s	Rendered walls with flat roof/ metal clad industrial shed	ACTA 2006 6A,6B. p.19. RE6, 7/123, 318
		156	Store	1940, 1935	Rendered walls with flat roof.	ACTA 2006 6A,6B. p.19. RE6, 7/156
		131	Boiler house	1965	Brick walls with flat asphalt roof	ACTA 2006 6A,6B. p.19. RE6, 7/131
		157	Community - scouts building (Engine Test House)	1935	Brick walls with pitched metal roof	ACTA 2006 6A,6B. p.19. RE6, 7/157
		1483	Store	u/d	Metal cladding to walls, metal roof	ACTA 2006 6A,6B. p.19. RE6,

						7/1483
		UH40, 170	Electric sub-station	1940	Painted brick walls with metal gate at entry/fenced enclosure	ACTA 2006 6A,6B. p.19. RE6, 7/UH40, 170, 312
		312	Electric sub-station	1940	Painted brick walls with metal gate at entry/fenced enclosure	ACTA 2006 6A,6B. p.19. RE6, 7/UH40, 170, 312
		313	Pavillion	1950	Steel frame with metal cladding and metal pitched roof	ACTA 2006 6A,6B. p.19. RE6, 7/313
		317	Workshop	1950	Rendered walls with pitched corrugated asbestos roof	ACTA 2006 6A,6B. p.19. RE6, 7/317
		317a	Canopy	1950	Remains of brick chimney, covered by metal canopy on metal posts	ACTA 2006 6A,6B. p.19. RE6, 7/317a. NOC
		339	Com air plant	1982	Brick walls containing vents. Flat asphalt doors and timber double doors.	ACTA 2006 6A,6B. p.19. RE6, 7/339
		346	Fuel tanks		Brick walls with shallow metal mono-pitch roof. Fuel tanks adjacent.	ACTA 2006 6A,6B. p.19. RE6, 7/346
		349	Gate house	1990	Brick walls with pitched, tiled roof supported by timber posts.	ACTA 2006 6A,6B. p.19. RE6, 7/349
		350A	2 Portakabins	1925	2 portakabins	ACTA 2006 6A,6B. RE6, 7/350A. NOC
		UH37, UH38	Flowerbed	u/d	Brick wall	ACTA 2006 6A,6B. p.19. RE6, 7/UH37, 38
		UH41	u/d	u/d	u/d	
OA14B Character Area 14B Service Area						
OA14B.1		125	Station Armoury and lecture room (QEK office)	1926	Brown/ red brindled brick walls with pitched, tiled hipped roof.	ACTA 2006 6A,6B. p.19. RE6, 7/125
OA14B.2	Scheduled Monument (no. 30906-05)	129	Hardened Telephone Exchange	1987	Single storey with a taller section which house blast proof roof vents. Retains dull brown 'Novolant' finish	A5 (3) OA8. ACTA 2006 6A,6B. p.19. RE6, 7/129
		115, 117	Motor Transport Sheds	1939	Concrete and steel structure with brick and stone infill	ACTA 2006 6B. p. 19. RE6, 7/115,117
OA14B.3		133	Main Church and Store (Junior Citizens and Thames Valley Medical Rescue)	1926	Brick walls with pitched, tiled roof	ACTA 2006 6B. p. 19. RE6, 7/133
		59	Works Service Building	1940	Painted brickwork with asbestos tiles on pitched roof.	ACTA 2006 6E. p.20. RE6 6/59
OA14B.4		103	Workshop	1940	Brick walls with pitched tiled roof.	ACTA 2006 6B. p. 19
OA14B.5		132	The Parachute store	1926	Brick walls with pitched, tiled roof	ACTA 2006 6B. p. 19. RE6, 7/132
		114	The Power House	1940	Brick walls with flat roof.	ACTA 2006 6B. p. 19. RE6,

Archaeology and Cultural Heritage, Appendix 9.1 (A)

						7/114
		67	u/d	u/d	u/d	
		66, 68	Offices in use	1939	Brick building with metal pitched roof.	ACTA 2006 6E. p.20. RE6 6/66, 68
		72	Two storage sheds (Operations Blocks)	1940	Steel frame with timber panel and corrugated steel cladding	ACTA 2006 6E. p.20. RE6 6/72
		56	The Works Squadron	1951	Painted brickwork with metal pitched roof and windows.	ACTA 2006 6E. p.20. RE6 6/56
		53	Office	1940	Pebbled dashed prefabricated panel construction to walls. metal pitched roof.	ACTA 2006 6E. p.20. RE6 6/53
		54	Single story hut	1940	Rendered walls with corrugated roof.	ACTA 2006 6E. p.20. RE6 6/54
		70	Conference room	1972	Prefabricated unit, timber clad.	ACTA 2006 6E. p.20. RE6 6/70
		64, 65	Building	1940s	Brick walls, flat roof.	ACTA 2006 6E. p.20. RE6 6/64, 65, 73
		101, 102	The Fire Party House (Offices/Workshop)	1939	Brick and metal clad buildings.	ACTA 2006 6B. p. 19. RE6, 7/101,102
		62, 69	Workshops	1981	Blockwork walls and metal pitched roof.	ACTA 2006 6E. p.20. RE6 6/62,69
		106	Storage (Battle Command Centre)	1970s	Brick and metal clad walls with metal roof and metal windows.	ACTA 2006 6B. p. 19. RE6, 7/106
		UH 46	Office	u/d	Prefabricated unit	RE6, 6/UH46
		107	Water tank (Reservoir)	1952	Concrete	ACTA 2006 6B. p. 19. A6.(A.2)
		79	Garage	1940	Painted brick walls with parapet to flat roof.	ACTA 2006 6B,6C,6D. p.20. RE6 6/79
		108	Water tower (High level water tank)	1952	Concrete structure supporting concrete tank	ACTA 2006 6B. p. 19. A6.(A.2)
		113	Transformer enclosure	1920s	Red brick flat roof postwar additions	ACTA 2006 6B. p. 19. A6.(A.2)
		113b	Electric sub-station	u/d	Painted brick walls, flat roof.	ACTA 2006 6B. p. 19. RE6, 7/113b
		113a	Tanks	1990	Metal tanks on concrete plinth, with brick walled enclosure behind.	ACTA 2006 6B. p. 19. RE6 7/113a. NOC
		118	Office (Link trainer buildings)	1935	Brick walls with parapet to flat roof	ACTA 2006 6B. p. 19. RE6, 7/118
		119	Garage and store (The protected long bay)	1939	Brick walls with parapet to flat roof	ACTA 2006 6B. p. 19. RE6, 7/119
		145	Inflammables Store	1935	Brick walls with flat roof.	ACTA 2006 6B. p. 19. RE6, 7/145
		UH39	Tank	u/d	Brick plinth supporting metal tank	ACTA 2006 6A,6B. p.19. RE6, 7/UH39
		124	store	1940,	Rendered walls with flat roof.	ACTA 2006 6A,6B. p.19. RE6,

				1935		7/156
		121	Water tank	1952	Timber panel fence enclosure	ACTA 2006 6A,6B. p.19. RE6, 7/121
		146	The Lubricant store	1926	Brick walls with pitched, tiled roof	ACTA 2006 6B. p. 19
		123	Office	1950s	Rendered walls with flat roof/ metal clad industrial shed	ACTA 2006 6A,6B. p.19. RE6, 7/123, 318
		147	Office (Link trainer building)	1935	Concrete single storey building with external piers.	ACTA 2006 6B. p. 19. RE6, 7/147
		148	The gas defence centre (Office)	u/d	Brick walls with parapet to flat roof, and metal windows	ACTA 2006 6B. p. 19. RE6, 7/148
		149	Fenced enclosure	1950	High timber panel fence	ACTA 2006 6B. p. 19. RE6, 7/149
OA14C Character Area 14C: Copse and Open Ground						
		80	Workshops, car wash	1953	Industrial shed type buildings, brick or metal clad.	ACTA 2006 6B,6C,6D. p.20. RE6 6/80. NOC
		84	Petrol Kiosk	1975	Concrete block	RE6, 6/84
		85	Store/workshop	1981	Small brick structure with timber door and metal roof	RE6, 6/85. NOC
		86	Type depot – QEK	1981	Brick building with metal roof.	RE6, 6/86
		88	Industrial shed – Ranik	1986	Metal clad shed	RE6, 6/88
		89A	Petrol pump booth	1939	Small brick structure with tiled roof	RE6, 6/89A. NOC
		UH44	Electric sub-station		Concrete plinth	RE6, 6/UH44
OA14D Character Area 14D: Post-War Open Landscape						
OA14D.1		77, 78	Innovation centre	1971	Brick walls with exposed concrete floor slabs. Tiled, pitched roof.	RE6 6/77, 78
OA14D.2		41	Former dormitory	1987	Red brick walls with pitched, tiled roof.	ACTA 2006 6D. p.20. RE6 6/41
		32-35	The Commissary (General Storage/Workshops)	1947	Steel frame, metal clad, pitched metal roof industrial sheds	ACTA 2006 6D. p.20. RE6 6/32-34
		2x, 3x, 4x	Metal shed	u/d	Metal shed with flat metal roof.	ACTA 2006 6D. p.20. RE6 6/2x, 3x, 4x
		75	Water store	1950	High timber fence enclosing pond	ACTA 2006 6E. p.20. RE6 6/75
		36	Office	1970	Brown brick walls with flat asphalt roof	ACTA 2006 6D. p.20. RE6 6/36
		38	Carwash	1986	Concrete	ACTA 2006 6D. p.20. RE6 6/38
OA14E Character Area 14E: 1920s Core						
		51	The Briefing Rooms (Former Office/Admin)	1942	Brick plinth, timber weather boarding, metal clad pitched roof	ACTA 2006 6E. p.20. RE6 6/51
OA14E.1		52	Station Offices (Heyford House - Office/Admin)	1935	Brindled brick with black mortar. Tiled pitched roof.	ACTA 2006 6E. p.20. RE6 6/52

OA14E.2		100 (demolished to rear)	The Guardhouse	1925	Brick with pitched, tiled roof.	ACTA 2006 6B. p. 19. RE6, 7/100
OA14E.3		74	Officers' Mess and Single Officers' Quarters	1925	Red brick with steep pitched tiled roof.	ACTA 2006 6E. p.20. RE6 6/74
		63	Water tank	1952	Metal structure supporting metal tank	ACTA 2006 6E. p.20. RE6 6/63
		73	Squash Racquets Court	u/d	Brick walls with metal pitched roof	ACTA 2006 6E. p.20. RE6 6/73
		104	Gatehouse	1990	Brick walls with pitched, tiled roof and timber windows	ACTA 2006 6B. p. 19. RE6, 7/104
OA15 CHARACTER AREA 15: NORTH RESIDENTIAL AREA						
OA15A Character Area 15A: Officer Housing						
OA15A.1		1 – 7 Soden Road	4 Bed semi detached houses	1925-6	Brick walls with pitched, tiled roofs	ACTA 2006 7A. p.21. RE6 5/1,3,5
OA15A.2		8 – 9 Larsden Road	4 Bed detached houses	1925-6	Brick walls with pitched, tiled roofs	ACTA 2006 7A. p.21. RE6 5/8,9
		10 – 11 Larsden Road	4 Bed detached houses	1934-9		
		29	Electric sub-station	1950	Timber fence panel enclosure	ACTA 2006 7A. p.21. RE6 5/29
OA15B Character Area 15B: North Bungalows						
		13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40	3 Bed semi detached single story buildings	1956/1957	Pebble dashed prefabricated panel construction. Pitched, tiled roof.	ACTA 2006 7. p.20. RE6 5/13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40
		42	2 Bed semi detached single story building	1957	Pebble dashed prefabricated panel construction. Pitched, tiled roof.	ACTA 2006 7. p.20. RE6 5/42
		44	4 Bed semi detached single story building	1957	Pebble dashed prefabricated panel construction. Pitched, tiled roof.	ACTA 2006 7. p.20. RE6 5/44.
		UH72	Store	u/d	Brick walls with pitched tiled roof.	ACTA 2006 7. p.20. RE6 5/UH 72