

10 | Page
a population equivalent of approximately 1001-2500 the required distance for low risk of customer complaint is 200m.

Table 4. Anglian Water Risk Assessment Methodology (adapted from Anglian Water, 2012)

Population Equivalent (PE)	Distance between housing development and STW (m)				
	50	100	150	200	250
0-1,000	medium	medium	low	low	low
1,001-2,500	high	medium	medium	low	low
2,501-5,000	high	high	medium	medium	low

The cover photograph to this report shows the existing cordon sanitaire from the boundary fence at the sewage inlet.