



ITEMS LIST

- Toddler Equipment**
- A. Play House Ref: J287A
 - B. Vivarea Multiplay Unit Ref: J3315A
 - C. Combination Swings (Metal) Ref: J473A-M
 - D. Make It Rain Play Panel Ref: UKFIRAIN6NGP
 - E. Music Bongos Play* Ref:R34-FIMUBON6
 - F. Play Panel Chimes Ref:R34-FIECOCHA
- *Including 2x post for play panel Ref:G3422A
- Junior Equipment**
- G. IXO Multiplay Unit Ref:J2586A-M
 - H. Metal swing Ref: J472A
 - I. Metal Cableway Ref: J512A
 - J. Challenger Climbing Boulder Ref: UKChallenger
- Ancillaries**
- K. 2x Waste Bin Ref: J2822B
 - L. 2x Chaumont Bench Ref: RBA8
 - M. 2x A2PP Sign Post and Panel (BTC Spec) Ref: A2PP
 - N. 4m long x 1.2m high 3 Post Rope swing barrier Ref: UKB1420
 - O. 2X No Dogs Paver Ref:UKX11404
 - P. 100Lm Bowtop Fencing 1m high PPC (Black)
 - Q. Prosafe Gate 1m high PPC (Yellow)
 - R. Prosafe Combination Gate 1m high PPC (Yellow)

- Groundworks**
- Toddler area to be surfaced with 310m² Mulch, depths broken down as follows:
- 216m² @ 40mm
 - 13m² @ 50mm
 - 10m² @ 80mm
 - 46m² @ 110mm
 - 25m² @ 130mm
- Coloured wetpour wear pads have also been included as shown.
- 1x Coloured Number Snake Wetpour graphics.
- Cableway and Challenger Boulder to be surfaced with 167m² Grassmat.
- Post Installation Inspection Is Included.
- Optional Extras**
- 167m² Topsoil & Turf for under Grassmat.
- Optional Extra Internal Pathway**
- Tarmac surfacing requires:
- Excavate to reduce levels average 160mm deep 20m²
 - Level and compact bottoms of excavations 64m²
 - Cut-fill and dispose remainder of excavated material off site 20m²
 - Geotextile membrane 64m²
 - MOT Type 1 filling to make-up levels ave. 100mm thick 64m²
 - Level compact and filling 64m²
 - To be edged by 72Lm PCC edges.

Subject to full site survey.

Based on a flat grass site.

Planting, trees and pathway to be done by others.

Measurements taken from client drawing Ref: 5205/ CP / ASP4.2.

