


1. TREE STOCK, GENERALLY

Scale 1:25




2. GENERAL TREE PLANTING PRINCIPLES IN OPEN GROUND


Scale 1:25

TREE SUPPORT SYSTEMS & IRRIGATION MEASURES OMITTED FOR CLARITY

TREE PIT: PLAN VIEW



SECTION ELEVATION



N.B. tree pit dimensions are a function of rootball size. Rootball dimensions are dependant on size of tree specified. Refer to Table 1.

N.B.

- BS 8545: 2014 states that, "Sensible tree pit design begins with the intention of doing as little as possible other than digging a pit, planting the tree, and using the existing soil, separated as subsoil and topsoil, as backfill. Each additional level of complexity added to the basic pit design can be related to the amelioration of a particular constraint".
- Tree shown planted in open ground in optimal conditions with minimal site constraints.
- Tree support systems are omitted for clarity.
- Tree pit dimensions are a function of rootball size. Rootball dimensions are dependant on size of tree specified. Refer to table.

Table 1: TREE PIT DIMENSIONS

FORM	GIRTH	DIMENSIONS		PLANTING HOLE DIMS	
		(^{min} g)	(^{max} Dp)	(^{min} L)	(^{min} D)
LS	6-8	400	300	700	700
LSs	8-10	400	300	700	700
S	10-12	400	400	700	700
H	12-14	500	400	800	800
EH	14-16	600	500	900	900
H	16-18	600	500	900	900
H	18-20	600	500	900	900
SM	20-25	750	750	1050	1050
SM	30-35	1000	1000	1300	1300

where: ^{min}g = Rootball diameter, ^{max}Dp = Rootball depth, ^{min}L = Planting Hole length, ^{min}D = Planting Hole width.

LS = Light Standard, LSs = Standard, S = Selected Standard, H = Heavy Standard, EH = Extra Heavy Standard, SM = Semi Major.

N.B. Stated tree planting hole dimensions to accommodate the rootball are a minimum. Rootball dimensions can, & do, vary some variance to be expected naturally between species, tree stock suppliers and seasons. In the event that the rootball exceeds the stated dimensions, the contractor shall seek advice from the Landscape Architect before commencing further. Thereafter, the Landscape Contractor shall excavate the hole (or Open Ground) to the advice given in BS 8545: 2014 with the exception of tree pit dimensions which shall be varied to achieve a maximum dimension of 10mm greater than the rootball. Tree planting hole depth shall generally be no greater than the existing rootball or container depth. The Landscape Contractor shall take care not to damage any underground utilities before commencing.

* where root spread is related to rootball size.

** section 3.2.2 of BS 8545:2014 states that, "Tree pits should have a diameter at least 75mm greater than that of the root system." However, this does not allow adequate space for firming in around the rootball if footfall.

Notes: Information regarding 'Tree Planting in Open Ground, Generally' on this sheet is derived from BS 8545: 2014 'Trees - from nursery to independence in the landscape - recommendations'.


While every attempt is made to address the most relevant points raised within the BS, this should not be considered exhaustive as it is presented in summary format only. For further information, the reader is referred back to the relevant British Standard.

3. ABOVE GROUND SUPPORT TREE STAKES

Scale 1:25


TRIPLE STAKED (Tst)

PLAN VIEW - AG




N.B. tree pit dimensions are a function of rootball size. Rootball dimensions are dependant on size of tree specified. Refer to Table 1, detail 2

SECTION ELEVATION - AG




SINGLE STAKE - (Sst) TO REAR GARDENS

PLAN VIEW



SECTION ELEVATION




BELOW GROUND CONDITIONS AS PER TRIPLE STAKED TREE


5. BELOW GROUND TREE SUPPORT UNDERGROUND GUYED (UG) TREES

Scale 1:25

PLAN VIEW - UG




SECTION ELEVATION - UG



CEDEC FOOTPATH GRAVEL SURROUNDS*

SECTION ELEVATION - UG




4. ABOVE GROUND SUPPORT TREE STAKES

Scale 1:25


DOUBLE STAKE & CROSS BAR - (DstXb)

PLAN VIEW



IN AREAS SUBJECT TO: HIGH WIND LOADING / VANDALISM; TRIPLE STAKED TREES MAY BE SUBSTITUTED FOR A DOUBLE STAKE & CROSS BAR

SECTION ELEVATION



BELOW GROUND CONDITIONS AS PER TRIPLE STAKED TREE

Table 2. TREE SUPPORT HEIGHTS

CLEAR STEM HEIGHT (m)	SUPPORT HEIGHT (m)
1000	1000
1200	1200
1500	1500
2000	2000
2500	2500
3000	3000

Table 3. ABOVE GROUND TREE SUPPORT ORIENTATION IN RELATION TO TRANSPORT CONDUITS / SPINE ROADS / AVENUES / ETC.

STAKE TYPE	ORIENTATION	REASON
TRIPLE	PERPENDICULAR	Visual Amenity - Protection from Wind Damage
DOUBLE	PERPENDICULAR	Visual Amenity - Protection from Wind Damage

Table 4: UNDERGROUND GUYING SCHEDULE

ITEMS	SPECIFICATION
EARTH ANCHORING SYSTEM:	UNDERGROUND GUYED
MANUFACTURER:	PLATIPLUS
MODEL:	D-MAN
D-MAN CELL DIMENSIONS:	270x270x80mm (LxWxD)
CODE:	RFP2PMAN
SUITABLE FOR:	12-45cmg TREES
SYSTEM COMPRISING:	3no. Wire Chokes, 5m galvanised wire, 1no. ratchet tensioner, 3no. Plati-Mats, 6no. D-MAN cells (3 x 2no. cells connected).


N.B. Earth Anchoring Systems are to be installed to manufacturer's recommendations & requirements with a minimum of 3no. earth anchors & associated cables to be fitted per tree.

The RFP2PMAN system has been preferentially selected over the RFP2PMAN system b/c of adverse site conditions (exposure, wind & ground conditions).

6. PROPOSED TREE PLANTING IN HARD SURFACES OPEN SPACE CEDEC GRAVEL PATHS

Scale 1:25

SECTION ELEVATION - UG



GENERAL TREE PIT PLANTING NOTES:

- SPECIFIED MATERIALS:** all to be installed in accordance with the manufacturer's recommendations and/or instruction.
- PLANTING GENERALLY:** Correct planting depth is critical for transplanting success, with over-deep planting identified as a common cause of failure. The Contractor shall therefore ensure that the natural root flare of the tree is clearly visible at proposed finished soil surface. To ensure that correct final planting position / depth is achieved, the Contractor shall therefore take care to remove all:
 - soil placed above natural root flare during nursery packaging & production - rootballing, containerisation, etc.
 - adventitious roots above the root flare,
 - wire encircling the main stem,
 - wire cage & burlap where possible. Otherwise, peel back and remove once the tree is in the planting pit.
- BACKFILL MATERIAL:** Open ground & Verges: select 'as dug' material to be reused taking care to match adjacent soil horizons (where suitability assured for tree growth); TBC onsite by Contractor. All 'as dug' material to conform to BS 3882:2007 General Purpose Topsoil. Remove all deleterious material arising (weeds, broken brick & large stones, etc). Backfill & lift in layers no greater than 150-230mm deep. Compact to between 1.5 - 2.0 mega pascals: tread down using footfall, paying particular attention to the planting hole edges and rootball extents to eliminate voids. Avoid over compaction. **Hard Paved Surfacing:** Use Heicom Tree Soil within primary rooting zone to manufacturer's instruction. Compact to manufacturer's recommendations. Backfill loose & dry (as approx. 20% is lost by volume upon compaction) into the tree pit. Lift in layers no greater than 250-300mm deep, and compact to between 1.5 - 2.0 mega pascals making sure the material is dry as proper compaction cannot be achieved when wet, paying special attention to the edges of the tree pit. A calibrated Penetograph can be used by a specialist approved by the soil supplier, and employed by the Contractor who installed the soil, to assess and confirm the level of compaction. The corresponding graph should be supplied to both the Project Structural Engineer, the Landscape Contractor & the Contract Administrator for information, before tree planting commences. N.B. In the event that trees are to be installed into the root director post completion of surfacing & construction build-up; the contractor shall take care to install the root director to the correct depth, form and level, and ensure that the root director void is filled and compacted with the specified tree soil prior to the commencement of associated surfacing and construction build up. Reason: to prevent the root director from being crushed during the construction build-up process. This temporary fill can then be dug-out at tree planting to accommodate the rootball.
- BACKFILL SOIL AMELIORANTS:** the Contractor shall satisfy himself of the general suitability of the topsoil supplied for long term tree growth. Reason: to ensure the long term longevity of the tree supplied. Thereafter: to suit site conditions. Typically, this may comprise 5kg of broadleaf pt or similar (pre-hydrated with water) thoroughly mixed with the topsoil until the medium is homogeneous.
- ARISINGS:** all deleterious material arising, shall be removed off-site to a licensed tip by the Contractor.
- TREE SUPPORT SYSTEMS:** Unless otherwise stated, all trees within public open spaces shall be supported as identified on the Software drawings which use both the Triple Stake (Tst) & Underground Guyed (UG) method of tree support. In the case of high wind loading / vandalism, the Triple Stake & Crossbar method may be substituted for the Double Stake & Crossbar (DstXb) method. In rear gardens the Single Stake (Sst) method shall be used.
 - Tree support stakes along transport conduits are to be orientated in accordance w/ Detail 3 opposite.
 - Tree support stakes to butt up against the rootball to help stabilise it.
 - Tree support height above ground shall be as identified on Detail 3.
 - Stakes to be removed to a minimum 150mm below ground level with no sharp edges as soon as the developing root system is self-supporting & root firmness is proven.
 - Irrigation pipes to be installed around the AG tree support system & top of the UG tree support system.
- ROOT PROTECTION MEASURES:** supply & install permeable rootbarriers (Teram RootGuard, or equal & approved) to a min. depth of 600mm below ground. Installation: as per manufacturer's instruction. Finished level: top of barrier to be 10mm above G.L. Zone of Deployment: protection of hard surfacing / services lying within a min. 5m radius of the proposed tree and as dictated on plan.
- IRRIGATION:** Open ground & Verges: Create topsoil chaucer as Detail 2. Water at frequency necessary to ensure establishment & survival.
- DRAINAGE:** the contractor shall satisfy himself that the tree pit is free draining. The contractor shall notify the Contract Administrator of any problem areas and await further instruction before proceeding further. Reason: to ensure the longevity & viability of the tree supplied. TBC onsite.
- BARK MULCH:** Amenity, 8-40mm particle size, mid dark brown, Rolawn (or equal & approved). Coverage: 75mm deep, 1m Ø around base of tree.

NOTES

Related Drawings: This is a composite drawing based on information received from other consultants.

Issue: Drawn by David Jarvis Associates Limited (CROWN COPYRIGHT. ALL RIGHTS RESERVED 2015 LICENSE NUMBER 030003). This Drawing is for Planning purposes only. Do not use this drawing for Construction. The information contained in the drawing should be used as a guide to the final form and finish of the landscape scheme. Any revisions to be approved by the Client and Local Authority.

Scale: Refer to each drawing. Use given dimensions only.

Setting out: refer to Engineers for information regarding setting out. In the event of discrepancy refer to Engineers in the first instance.

Survey: Original survey provided by the Client.

Services: Where possible these are identified on the drawings but, for the avoidance of doubt all service/utility locations should be confirmed as per manufacturer's instruction. Finished level: top of barrier to be 10mm above G.L. Zone of Deployment: protection of hard surfacing / services lying within a min. 5m radius of the proposed tree and as dictated on plan.

Contractor's information: All installed design (including but not necessarily limited to: back barriers, burlap, ratchet, ratchet tensioner, construction build-up, levels, drainage etc.) to be provided by an appropriately qualified contractor/highway engineer to be appointed by the Client for presentation to (and subsequent discharge from) the relevant supervising authority and/or body.

Lighting: Refer to lighting engineers drawings.

Planting: Plant species are selected and located in line with consideration of the site conditions, BREB guidelines and discussions with the Local Authority and Design Team. All plans and planting procedure to conform to the David Jarvis Associates Limited Landscape Specification that will accompany the Construction Issue drawing. No species or plant location to be varied without prior consent of the Landscape Architect.

Tree Root Protection Measures: supply & install permeable rootbarriers (Teram RootGuard, or equal & approved) to a min. depth of 600mm below ground. Installation: as per manufacturer's instruction. Finished level: top of barrier to be 10mm above G.L. Zone of Deployment: protection of hard surfacing / services lying within a min. 5m radius of the proposed tree. To be increased to 200mm depth where services / utilities require to be installed adjacent to the tree.

Foundations: Developers / Contractors to ensure that all foundations (buildings and external walls) are designed and constructed so as to take into account, at the time of maturity, any existing or proposed trees, hedgegroves or other vegetation on the application site or existing vegetation on land adjoining the site at the time of construction and any trees listed or hedgroves removed or adjacent to the site during the previous 15 years. For this purpose the Developer / Contractor will submit all relevant details to the authority dealing with the Building Regulations certificate.

Design Levels: Refer to Engineers where design levels are not shown.

CODE: Drawings to be read in conjunction with Designers risk assessment. Potential risks above that of those associated with the general construction typical to the drawing are identified below:

Rev.	Date	Description	Drawn	Checked
C1	04/12/2017	First issue.	GR	BS

Status: **PLANNING**

Client: **ELMSBROOK (CREST A2D) LLP**

Project: **ELMSBROOK, BICESTER PHASES 3 & 4**

Drawing Title: **TYPICAL TREE PLANTING DETAILS**

Scale: **1:25** Sheet Size: **A1** Date: **04/12/2017**

Drawing No.: **14790/5500** Revision: **P1**

