

compacted during spreading.

xisting subsoil. Not to be

ound the root ball. Sub soil n

ArborRaft TRC 30 Geotextile

Bottom 300mm of pit backfilled with

placed under and around the root ba Sub soil must be carefully handled so as to retain soil structure

HERBACEOUS

Total:149 No.

Number Plant Name

CLIMBERS

Total:3 No.

149 No. | Bergenia 'Bressingham White' | 5L

Container | Specification | Density

Full Pot: C

Height Container Specification

3 No. | Clematis armandii | 150-200cm | 15L | Caned: Several Shoots: 3 brks: C | Counted

This drawing is to be used for planting information only, and is subject to alteration through changes to the site layout or until approved by the area designer.

Shrub Planting

Tree Planting

Grass: Mown

Bulbous Planting

Retained trees

similar approved)

Green-Tech Arboraft system(or

Hedging

Climbers

Any species substitution by the contractor must be verified with the Landscape Architect through the Job Architect.

This layout must be checked in accordance with NHBC Standards 2013 (Chapter 4.2 - Building Near Trees & Chapter 9.2 Drives, Paths and Landscaping) by the Regional

Excavations: Contractors must ensure that they have full information relating to service and drainage positions before undertaking any excavations.

Root barriers to be used in association with tree planting adjacent to kerbs / services / footpaths etc. (GreenBlue Urban ReRoot products or similar application, in accordance with manufacturer's instructions).

Climbers to be secured to suitable supports following good horticultural

Rev	Date	Description
A	17.03.22	Layout revisions
В	17.06.01	Species amendments/details added
С	17.06.05	Amended to revised base
D	17.07.26	Layout / Planting revisions
E	17.09.07	Tree to Plot 466-468 boundary remove
F	17.09.29	Planting amendments
_	40.04.45	

G 19.01.15 Amend to revised base and phase area

19.01.18 Planting and Baseplan Adjustment | Detailed Planting Proposals Parcel 5C

Dorchester Living | 2017.03.22 1:200 @ A0 Drawing No: | 1619 5C 01 H

T: +44 (0)1279 647044 E: office@lizlake.com www.lizlake.com

During each August within the Aftercare Period an inspection shall be made and all plants that have died, are missing, damaged or have failed to thrive, shall be noted and replaced in the following planting season.

During the first and subsequent growing seasons amenity grass shall be kept at a height of 25mm to 50mm. Any bare patches are to be resown. Selective weed

During the first growing season cut wildflower grassland every 2 months to a height of 50mm and in subsequent growing seasons cut to 50mm height during late March and late August / early September or as specified. All arisings shall be collected and removed from the site to avoid smothering the sward and to reduce

nutrient levels. Spot treat perennial weeds with Glyphosate at the manufacturer's recommended dose rate / or hand pull.

All planting that is within the root protection area of existing trees/shrubs to be retained, shall be undertaken by hand and positions altered should tree roots be

All plants shall be set out evenly over the areas as indicated, to the density and quantities shown. All plants shall be planted upright at the same depth as the

nursery soil level and evenly spaced, leaving room for growth. All restrictive containers shall be removed with roots not twisted. Immediately following planting,

50mm backfill beyond the root ball extent. Plants to be firmed, watered in and dead, damaged or lopsided branches shall be removed after planting. Bare-root

Container grown and root balled plants shall be planted in a planting pit sufficient to accommodate the plant without causing root damage, with a minimum

all plants shall be watered-in to field capaci

plants shall be slit planted, incorporating an approved high phosphate, slow-release fertilizer