


OS map data reproduced by permission of Ordnance Survey on behalf of
HAMS. © Crown copyright 2015. All rights reserved. Ordnance Survey
license number 0100040892

SCALE 1:250
@ A1 SHEET SIZE

OS map data reproduced by permission of Ordnance Survey on behalf of
HAMS. © Crown copyright 2015. All rights reserved. Ordnance Survey
license number 0100040892

SCALE 1:250
@ A1 SHEET SIZE



FOR CONTINUATION SEE ABOVE

	PIPE-1	
	UPSTREAM	DOWNSTREAM
EASTINGS:	177002.452	176997.661
NORTHINGS:	141665.278	141646.174
EXISTING DITCH LEVELS:	70.260	70.259
PIPE INVERT:	70.260	70.217
HEADWALL:	NOTE 3	
PIPE TYPE:	300mm CARRIER PIPE	
MINIMUM COVER:	1.0m	

- NOTES:**
- REFER TO STANDARD DETAIL DRAWING 133735_RW-EWR-XX-XX-DR-CH-000131 & 000132 FOR PIPE SURROUND AND BEDDING TYPES.
 - THE EXISTING DITCH INVERT LEVELS ARE TAKEN FROM AVAILABLE TOPOGRAPHIC SURVEY INFORMATION, WHERE AVAILABLE. THE CONTRACTOR WILL NEED TO CONFIRM DITCH LEVELS BEFORE INSTALLING CULVERT. ANY DISCREPANCIES IN LEVEL WILL NEED TO BE DISCUSSED WITH THE DESIGNER.
 - PROPOSED COMPOUND ACCESS EARTHWORKS TO EXTEND INTO THE EXISTING DITCH. CULVERT PIPE TO EXTEND A MINIMUM OF 100mm BEYOND THE TOE OF THE EARTHWORKS.

CULVERT REQUIREMENTS

KEY:

	HIGHWAY BOUNDARY
	TWAO BOUNDARY
	EXISTING ROAD EDGE
	PROPOSED ROAD EDGE
	GRASS VERGE
	PROPOSED WHITE ROAD MARKING
	PROPOSED YELLOW ROAD MARKING
	PROPOSED DRAINAGE CULVERT
	PROPOSED FENCE
	EXTENDED CARRIAGEWAY
	GRASS VERGE
	PROPOSED EARTHWORKS
	HB KERB
	PROPOSED GATE
	PROPOSED TRAFFIC SIGNALS
	PROPOSED LIGHTING
	PROPOSED TRAFFIC SIGN

SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION
THE WORKS ARE TO BE UNDERTAKEN BY A COMPETENT CONTRACTOR, AND THEREFORE ONLY EXCEPTIONAL RISKS RELATING TO THE WORKS ASSOCIATED WITH THIS DRAWING ARE IDENTIFIED BELOW. FOR FURTHER DETAILS AND PROPOSED SAFETY MEASURES REFER "EWR PHASE 2 HAZARD LOG WORKING COPY" EB DOC. REF: 133735-NWR-RSA-SSD-000001.

ID	HAZARD DESCRIPTION
EWR2-HAZ-02095	PRESENCE OF BURIED LV LINE


INDICATES PROJECT RISKS (EWR2-DRIS-)
 INDICATES H&S RISKS (EWR2-HAZ-)

- NETWORK RAIL (EAST WEST RAIL WESTERN SECTION PHASE 2)**
- NOTES:**
- THIS DRAWING IS NOT TO BE SCALED.
 - ALL DIMENSIONS ARE IN METRES (m) UNLESS SHOWN OTHERWISE.
 - THIS DRAWING IS TO BE READ IN CONJUNCTION WITH THE HIGHWAY DESIGN PACKAGE OF DRAWINGS AND DOCUMENTS.
 - WHEREVER REQUIRED, ROAD MARKINGS ARE TO BE LAID IN ACCORDANCE WITH THE TRAFFIC SIGN REGULATIONS AND GENERAL DIRECTIONS 2016 & 'TRAFFIC SIGNS MANUAL CHAPTER 5 (2003)'.
 - FOR DETAILS OF ROAD MARKINGS, REFER TO STANDARD CONSTRUCTION DETAIL TW5 ROAD MARKINGS FOR COMPOUND ACCESS DRAWING No. 133735_RW-EWR-XX-XX-DR-CH-000122.
 - REFER TO DRAWING 133735_RW-EWR-XX-XX-DR-CH-000123 FOR DETAILS OF PROPOSED DITCH REPROFILING.
 - WHERE A FENCE IS PROPOSED IT SHALL TIE-IN TO THE EXISTING HEDGEROW OR BOUNDARY TREATMENT TO PROVIDE A SECURE BOUNDARY.
 - FOR DETAILS OF TRAFFIC SIGNS, REFER TO SIGNAGE STRATEGY DRAWING FOR OXFORDSHIRE COUNTY COUNCIL DRAWING No. 133735_2A-EWR-OXD-XX-DR-CH-010258.



Rev	Date	Description of Revisions	Desd	Chkd	Appr	Suitability
B01	30/05/19	FOR INFORMATION				E.F.

SHARED - for Content Check S1



Project
East West Rail (Western Section) Phase 2

Drawing Title
ACCESS TO COMPOUND A1 GENERAL ARRANGEMENT

Designed	Tamsin Leaman-Hewitt	Signed	Leaman-Hewitt	Date	24/05/19
Drawn	Jameela Nawaz	Signed	J. Nawaz	Date	16/11/18
Checked	Garth Johnston	Signed	G. Johnston	Date	24/05/19
Approved	Edward Findlay	Signed	E. Findlay	Date	24/05/19

Scale(s)	1:250	ELR - Project Chainage (Miles Yards)	OXD - 108820
Design Package Risk Classification	Normal	Sheet	1 of 1
Alternative Reference		Revision	B01

Drawing Number
133735_2A-EWR-OXD-CC_A1-DR-CH-002001