



- EXISTING FOOTWAY
- PROPOSED 2.0M WIDE FOOTWAY
- PROPOSED 2.0M CYCLE BYPASS
- PROPOSED 3.0M WIDE SHARED FOOTWAY/CYCLEWAY
- VEHICLE CROSSING
- EXISTING GRASS VERGE
- PROPOSED GRASS VERGE
- NEW SURFACING TO BE CONSTRUCTED USING 68+ PSV CHIPPINGS
- EXISTING ROAD MARKINGS
- PROPOSED ROAD MARKINGS
- PROPOSED TACTILE PAVING
- PROPOSED CORDUROY PAVING

- HB2 Kerb 125mm Kerb Face
- BN Kerb 0-6mm Kerb Face
- BN Flush Kerb face
- EF Edging
- Tactile Paving
- 900mm Drop Kerb HB2 to BN as indicated

Recreation Ground

GENERAL ARRANGEMENT

KERBING



NOTE: CARRIAGEWAY SURFACING ON THE APPROACHES TO PROPOSED ZEBRA & TOUCAN CROSSINGS TO BE MINIMUM 68+ PSV AS A SKID PREVENTION MEASURE USING 68+ PSV CHIPPINGS, 40mm HRA 55/14 F SURFACE 40/60 PEN

REV	DESCRIPTION	DATE
D	Road marking clarified	16.5.19
C	Amendments made in line with OCC comments, car park entrance amended	16.5.19
B	Amendments made in line with RSA 1/2 comments	12.04.19
A	Amendments made in line with technical comments	04.03.19

STATUS:	Preliminary
SCALE:	1:200
DATE:	Dec 2018
DRAWN:	LB

TITLE:	Section 278 General Arrangement & Kerbing Layout
PROJECT:	White Post Road, Bodicote
DRG. No:	957-278-02 Rev D

